Sky and TELESCOPE

In This Issue:

Gas and Dust in Globular Clusters

Why Observe Stellar Eclipses?

American Astronomers Report

A New Universal Sundial Design

The Earth's Shadow Size at the March Lunar Eclipse

Northern and Southern Star Charts

★

Vol. XIX, No. 8

JUNE, 1960

50 cents

★

Weather satellite launching



15-inch CASSEGRAIN REFLECTOR

Equipped with:

3-inch finder telescope

5-inch guide telescope

2-inch Fecker-Ross f:7 astrograph

Sidereal rate electric drive

Circles for right ascension and declination

Clamps and slow motions

j. w. fecker

division of AMERICAN OPTICAL CO

6590 HAMILTON AVE., PITTSBURGH 6, PA.

Sky and TELESCOPE

CHARLES A. FEDERER, JR., *Editor*
JOSEPH ASHBROOK, *Technical Editor*

Copyright, 1960, by SKY PUBLISHING CORPORATION, all rights reserved.

Vol. XIX, No. 8 JUNE, 1960

CONTENTS

FRONT COVER: The giant Thor-Able-Allegany combination rocket that placed satellite Tiros I in orbit on the morning of April 1, 1960, is seen rising from its launching pad at Cape Canaveral, Florida. The new artificial satellite, traveling in a practically circular orbit more than 400 miles above the earth's surface, is televising to ground stations man's first over-all views of the cloud patterns that girdle our planet. National Aeronautics and Space Administration photograph. (See page 459.)

GAS AND DUST IN GLOBULAR CLUSTERS
— Otto Struve 456

WHY OBSERVE STELLAR ECLIPSES?
— Alan H. Batten 464

AMERICAN ASTRONOMERS REPORT 467

A NEW UNIVERSAL SUNDIAL DESIGN
— Hermann H. Egger 470

THE EARTH'S SHADOW SIZE AT THE MARCH LUNAR ECLIPSE
— Joseph Ashbrook 474

AMATEUR ASTRONOMERS 476
Northeast Region Holds New York City Convention
Old Battleship Is Source for an Observatory Dome

ASTRONOMICAL SCRAPBOOK 463
William Herschel and the Sun

BOOKS AND THE SKY 493
Introduction to the Mechanics of the Solar System
Kepler
Astrophysique Generale

CELESTIAL CALENDAR 508
Mercury in the Evening Sky This Month

GLEANINGS FOR ATM's 502
A Portable 6-inch Catadioptric Telescope
Glass Removal in Parabolizing

LETTERS 473

NEWS NOTES 472

OBSERVER'S PAGE 479
News of Comet 1959k
Deep-Sky Wonders

OBSERVING THE SATELLITES 459

QUESTIONS 466

SOUTHERN STARS 512

STARS FOR JUNE 513

INDEX TO VOLUME XIX 483

SKY AND TELESCOPE is published monthly by Sky Publishing Corporation, Harvard College Observatory, Cambridge 38, Mass. Second-class postage paid at Boston, Mass.

Subscription: $5.00 per year in the United States and possessions; $9.00 for two years; $13.00 for three years. To Canada, Mexico, and all countries of the Pan American Postal Union, $6.00 for one year; $11.00 for two years; $16.00 for three years. To all other foreign countries, $7.00 for one year; $13.00 for two years; $19.00 for three years. Canadian and foreign remittances should be made in United States currency. Single copy 50 cents. Back numbers, as available, 50 cents each.

All notices of change of address must be sent one month in advance and accompanied by old and new addresses. When sending your renewal order, or writing in regard to your subscription, your current mailing address must be given. Return our bill form with renewal payment. Circulation manager, Nancy R. Bolton. Office staff: Virginia K. Cox, J. Caroline Nason, Mary Silva, John Simmons, Helen B. Sniegiecki, Stacia Strong.

Editorial and advertising offices: 49-50-51 Bay State Rd., Cambridge 38, Mass. Advertising rates are listed in STANDARD RATE AND DATA SERVICE, or sent upon request. Advertising manager, Henry M. Corrado. Editorial assistant: William E. Shawcross.

Unsolicited articles and pictures are welcome, bearing adequate return postage, but we cannot guarantee prompt editorial attention, nor are we responsible for the return of unsolicited material. The principal articles are indexed in THE READERS' GUIDE TO PERIODICAL LITERATURE.

Although the contents of this magazine, its text, pictures, diagrams, and charts, are copyrighted with all rights reserved, we are pleased to give permission, upon request, for the use of SKY AND TELESCOPE material for educational and scientific purposes, with the exception of the monthly star and planet charts, which may not be copied or reproduced in any manner for any purpose. Permission to use matter from signed articles, and photographs and diagrams for which credit is given, must also be obtained from the person, observatory, institution, or agency concerned.

The Editors Note . . .

RAPID GROWTH of this magazine in recent years has made it necessary to adopt two volumes per year instead of one, as explained at the foot of this page. As a result of the tremendous rise in popularity of astronomy as a science and a hobby, and because of the growing availability of equipment of all kinds, the past seven years have seen some remarkable changes.

For instance, in 1952 our Here and There with Amateurs listing showed 102 amateur astronomical societies, but the latest (April, 1960) contains 305! During 1951-52 (Vol. XI) each copy of the magazine was 24 or 28 pages, for a yearly total of 316. Vol. XVIII, completed last October, averaged 60 pages an issue, totaling 400 more pages than in 1952. Meanwhile, the number of copies printed each month has more than tripled, now being 34,000.

It was about 1952 that inexpensive imported telescopes of good quality began to reach amateur astronomers in this country. American manufacturers also entered the suddenly active field, producing well-designed reflecting telescopes at moderate cost. Among our advertisers in Vol. XI, there were 38 different manufacturers and publishers, but last year's volume had 89 advertisers.

This growth in advertising not only helped newcomers to astronomy in getting started, but enabled us to publish much more astronomical material. We now devote an average of 16½ more pages each month to articles and pictures than we did seven years ago. Amateurs and professionals alike have generously contributed papers and reports, on an ever-widening range of subjects, and to them we are especially indebted.

They have always kept our advance-copy file amply supplied. Happily, our problem each month is to compress into the page allowance as many as possible of the best articles and pictures. Those of most current and lasting interest are selected, but important topics must often be omitted.

ANNOUNCEMENT

Since its beginning in November, 1941, each volume of SKY AND TELESCOPE has contained 12 monthly issues, the volume year ending with the October number. However, this issue terminates Vol. XIX, which began last November and contains eight numbers.

Starting with Vol. XX, July, 1960, SKY AND TELESCOPE will have two volumes a year, one to begin in January and the other in July. The index to Vol. XX will appear in the December issue. New binders for the smaller volume will be available, as announced on page 509.



Although some 40,000 light-years away, the globular NGC 6171 appears a quarter of the moon's diameter. It is shown here in blue light (left) and red light. Around its dense central portion several possible obscured regions are seen, especially an oval blob below center and a four-sided one toward upper right (southeast). Palomar 48-inch Schmidt photographs.

Gas and Dust in Globular Clusters

OTTO STRUVE, *National Radio Astronomy Observatory**

A PUZZLING FEATURE of many globular clusters is the presence in them of an appreciable number of fairly hot stars, in apparent defiance of the modern theory of stellar evolution. About a score of these blue objects are shown in the accompanying color-luminosity diagram of the globular cluster Messier 3, in the area at apparent magnitude +18, color index 0.0 to +0.2.

These are main-sequence stars, but they are located well above the *turn-off point* at magnitude +19, where the densely populated, nearly vertical main sequence turns sharply to the right. These brighter blue stars cannot be explained away as foreground objects, because they share the motion of the cluster and therefore are a part of it.

The problem they present is this. Globular clusters are very old, on the order of 10 billion years. If, when such a cluster was born, there were main-sequence stars above the turn-off point, they must have long since evolved into red giants, which would put them far to the upper right in the diagram. How can we account for their presence now? They are enough like "zero-age" main-sequence stars found elsewhere in the Milky Way galaxy that they cannot be over one billion (10^9) years old, and may in some cases be even younger.



A color-magnitude diagram for stars in the globular cluster Messier 3, by H. C. Arp, W. A. Baum, and A. R. Sandage. Blue stars are toward the left, bright ones toward the top. The main sequence is the densely populated short band near the bottom of the diagram, running from the lower right toward upper left.

The first explanation that might be given is that the process of star formation continues over a very long interval. In the much younger galactic clusters, we have direct evidence that member stars were not all formed at the same time, and there are strong reasons for believing that stars are at present being born in, for example, the Orion nebula. We might conjecture that even though most stars in a globular cluster originated 10 billion years ago, enough interstellar gas and dust remained at much later times to permit the formation of what are now a few relatively young stars.

But this hypothesis is contradicted by our belief that a globular cluster is swept clean of dust and gas when it travels

*Operated by the Associated Universities, Inc., under contract with the National Science Foundation.

through the central plane of our galaxy. The period of revolution of a typical globular in its highly elongated orbit around the nucleus of the Milky Way is of the order of 100 million years. Hence, each cluster has passed through the Milky Way about a hundred times, and should have lost all of its *original* interstellar material.

A second way of explaining the present existence of the hot blue main-sequence stars involves an alternative view of their evolution. The change of such stars into red giants has been predicted on the assumption that there is little mixing of the gases in their interiors. If there is efficient mixing, the outer layers would be rapidly transported inward to where they could participate in nuclear reactions at temperatures of about 20 million degrees. Matter from the deep interior would flow outward to where it temporarily ceases to generate energy. Theoretical astrophysicists pointed out many years ago that under these conditions the evolutionary track of a star would run upward, almost along the main sequence, as the total supply of hydrogen fuel decreased.

However, L. Mestel and others have shown that in most ordinary stars mixing is exceedingly slow, and matter from the outermost layers never actually reaches the hot core. Only in rapidly rotating bodies might there be meridional currents of gas, which could speed up the mixing process sufficiently to affect the evolutionary tracks perceptibly. But the difficult mathematical problem of mixing in rotating stars has not been worked out in full detail, and we really do not know whether mixing is ever fast enough for a star to evolve upward along the main sequence.

A third hypothesis assumes that, even though the original gas and dust inside a globular cluster was swept away during its first few passages through the galactic plane, there could be some mechanism continually operating to produce inside the cluster a small amount of diffuse matter. Then a few stars might be able to condense out of this material during the relatively long intervals between the sweepings out. Star formation at a greatly reduced rate might thereby still be going on in all globular clusters.

This proposal immediately raises the question: Has such diffuse matter actually been detected in globulars? A summary of what we know about this was given by Helen Sawyer Hogg at a symposium on globular clusters held at Toronto last year, during the meeting of the American Astronomical Society. She said:

"An important difference, most inadequately investigated, is the obvious streaks of dark nebulosity in certain globular clusters, in high or low latitudes. Among high-latitude clusters, they are very conspicuous in M13, M3, and M2, and less marked in M5 and M15. Whether or not the dark streaks in M13 are the optical result of chance star chains has been a controversial subject for 60 years. Many pages have been written to prove that they are illusions, due to chance groupings of stars, or to show that it is not possible for diffuse nebulosity to exist in a globular cluster.

M13 in red light, taken by A. Mowbray with the 36-inch Lick reflector. On the overexposed central area's southeast (upper-right) edge is an elongated dark lane, ascribed by Morton Roberts to an obscuring intraglobular cloud.

"As a person who has handled large-scale plates of globular clusters steadily for over thirty years, I stand firmly on the side that the dark lanes in the Hercules cluster and certain others are real patches of nebulosity, and are not effects of random groupings of stars. Whether the nebulosity is actually a part of the cluster, or is a wisp of interstellar material between us and the cluster, I have no conviction. But if there are small wisps of material in high galactic latitudes, can you name any other object against which they would show so well in projection as a globular cluster? Against an external galaxy it would be taken for granted that they were part of it. The time interval of large-scale cluster photographs may even now be getting sufficiently large that relative motion of the dark lanes with respect to the cluster stars, or relative dimming or brightening of cluster stars contiguous to the dark lanes, may be measurable." [From *Astronomical Journal*, December, 1959, page 427.]

As Mrs. Hogg stated, the dark lanes in globular clusters have been known for many years. As early as 1861, Lord Rosse published a sketch of M13, the great Hercules cluster, which shows them. E. S. Holden photographed them in 1890-91 at Lick Observatory. In 1955, A. P. Fitzgerald observed some dark patches in Omega Centauri, and four years later G. M. Idlis and M. Nikolsky commented upon the obscured regions in M4.

There is an interesting discussion of this problem in a yet unpublished paper by Morton S. Roberts, of the Berkeley astronomical department of the University of California. He has examined photographs in the Palomar Observatory sky survey with the 48-inch Schmidt telescope and pictures taken with the 36-inch Cross-

ley reflector at Lick Observatory. He has prepared a list of 12 globular clusters, out of 32 studied, that have one or more dark regions in them. The 32 clusters together cover 0.8 square degree of the sky. Since they contain at least 16 dark patches, the latter occur at the rate of 16/0.8 or 20 per square degree.

According to Roberts, this indicates that the dark lanes are *not* due to foreground wisps of absorption in our galaxy, as these are too few. All of the 32 clusters are at least 15 degrees from the central galactic plane, while even along the Milky Way there seems to be only about one dark globule per square degree, according to B. J. Bok and Edith F. Reilly. Although this argument is reasonably convincing, it is perhaps too early to regard it as more than a good guess.

If Roberts is correct, then the following question arises: Are the dark markings caused by obscuring dust clouds in the clusters, or are they merely statistical fluctuations in the distribution of cluster stars, areas where the stars by chance are few? The latter is highly unlikely, but to make sure Roberts has computed an artificial "model" of a cluster, using for this purpose a table of random numbers.

The number of star-free regions in the model decreases with increasing size of the region, dropping to zero at about 200 square seconds of arc. The most definite dark region in M13, at position angle 130° (upper right) in the page 457 picture, measures about 460 square seconds. The probability of finding such a large area vacant, as a result of statistical fluctuations, is effectively zero.

Hence, if the dark regions are really located within the globulars, the obscuration that they reveal must be due to interstellar dust. Roberts assumes for the prominent M13 absorbing lane a cylindrical shape having a volume of about 25 cubic light-years, or some 7×10^{55} cubic centimeters. The absorbing effect of the cloud, at least five magnitudes photographically, implies about 7.5×10^{-33} gram of dust per cubic centimeter. Thus, the dust content of the entire cloud in M13 would be roughly 5.2×10^{33} grams, or about 2.6 solar masses.

In the interstellar clouds of our Milky Way, dust particles account for only about one per cent of the total mass, the rest being gas — mostly hydrogen. Hence, Roberts finds that the M13 dark lane may contain an over-all mass of about 260 suns. He suggests that the total gas and dust in a typical globular cluster having several dark patches might equal 1,000 suns.

Roberts thinks that this diffuse matter in globulars is not the remains of their original dust and gas. Also, it could not have been collected by the clusters from the halo of the galaxy. Instead, he shows that a sufficient amount of gas may be released within the clusters when their fairly massive Population II stars shed material explosively to become white dwarfs (perhaps by supernovae processes).

He refers in particular to computations made in 1957 by H. Takebe and N. Matsunami, and by A. R. Sandage. The latter's results for M3 indicated that the *total* amount of ejected material could be half the present mass of the cluster, or about 100,000 suns. If, during its past lifetime, the cluster has made 100 revolutions around the galactic center, then approximately 1,000 solar masses could accumulate in the system before being swept out.

The Berkeley astronomer gives some reasons for believing that the time would be long enough for fresh stars to evolve from the diffuse matter before it was lost.



Blue stars of nine globular clusters are plotted in this composite color-magnitude diagram. Black dots indicate stars in Messier 3, while the curve shows the course of the zero-age main sequence. This chart is courtesy of Morton S. Roberts.

Presumably a protostar or globule could condense quite rapidly, and would not necessarily have to become a main-sequence object in order to be safe from the consequences of crossing through the plane of the Milky Way. In such a passage, stars and dense knots of matter would be relatively undisturbed, in comparison to more extended clouds.

Because the obscured regions in certain globulars appear to be fairly distinct clouds, the young stars that form within the cloud should be in groups, not distributed with spherical symmetry as are the old stars of Population II. For M3, Roberts finds that the blue stars do, in fact, tend to appear together in groups, but for other globulars the data are too scanty for any conclusions to be drawn.

Thus far, the only observational evidence for the existence of diffuse matter in globular clusters comes from the apparent obscuration by dust. No nebulosities with emission spectra have been discovered in globulars, except for one planetary nebula inside M15. This single exception is, perhaps, consistent with the rarity of planetaries in the Milky Way; furthermore, it lends some support to the hypothesis that old stars in globulars are expelling gas.

Roberts has calculated that the ionization of hydrogen in the diffuse clouds within clusters will not produce Balmer emission lines strong enough to be detected on spectrograms. Neither has he found the 21-centimeter line of hydrogen to be observable in M3 and M13 with the 85-foot radio telescope of the National Radio Astronomy Observatory.

One unanswered question is why the diffuse material that is shed by Population II stars should collect in compact, very dense nebulosities. Gas expulsion would be expected throughout the cluster, and the gas should therefore be distributed with a spherical symmetry, like the old stars themselves.

Dark lanes in M13 are shown in this drawing of May, 1851, made with Lord Rosse's 72-inch reflector at Birr Castle. The Irish amateur first recorded these features on May 6, 1850, and on the following April 6th commented that these streaks bore some resemblance to the dark lanes in the great Andromeda nebula. From "Philosophical Transactions" of the Royal Society (1861).

OBSERVING THE SATELLITES

Earth Observations from an Artificial Satellite

THE FEASIBILITY of surveying cloud patterns on a global scale has been demonstrated by the television system of Tiros I. This experimental weather-reconnaissance satellite was launched from Cape Canaveral on April 1st at 11:40:09 Universal time, under the auspices of the National Aeronautics and Space Administration (see front-cover picture).

The name *Tiros* is coined from *T*elevision and *I*nfrared *O*bservation *S*atellite, foreshadowing the use in future experiments of infrared detectors, in order to map the surface temperature of the earth. These heat sensors were not ready in time for the April ascent, but the television system has already revealed cloud systems encompassing unexpectedly large portions of the earth.

A Thor-Able-Allegany Ballistics Laboratory rocket configuration, similar to the one that placed Pioneer V in orbit around the sun on March 11th, was used to attain a nearly circular terrestrial orbit. The spin-stabilized 500-pound third stage, with the 270-pound payload attached, coasted upward for 6½ minutes after second-stage separation before it fired.

During this interval the vehicle was tracked by the Millstone Hill radar installation, at Westford, Massachusetts. Longer-range tracking was made possible by a newly developed repeater beacon attached to the third-stage rocket, thus permitting more accurate orbit determination.

The intended trajectory was achieved with high precision. At its burnout, the third stage was traveling 24,654 feet per second, within 0.1 per cent of the desired figure. The orbital inclination was determined as 48.4 degrees, very close to that planned. For observations of clouds, a circular orbit was intended, and the actual initial eccentricity amounted to only 0.0045.

Tiros is shaped like a giant hatbox, about 42 inches in diameter and 19 inches high, its top and sides covered with 9,000 solar cells. When this payload was injected into orbit, it was traveling slightly north of eastward, off the coast of Nova Scotia, with the six-foot-long final rocket case attached behind it.

Some 25 minutes later, when the satellite had completed about one-fourth of a revolution, it was passing southeastward over the Arabian Desert, north of Yemen. At this point, the rocket case was nearly below the satellite, since their relative orientation in space was unaffected by the motion in orbit. Powerful springs then forced the empty 50-pound rocket casing away from the instrument package.

At the same time, the payload was spinning around a nearly vertical axis at about 136 revolutions per minute — too fast for unblurred television operation. To brake the rotation, about 10 minutes after the separation two weights attached to long cables were released. As these swung outward, the spin slowed to some 12 times a minute, and then the cables slipped off their hooks and away from the payload, as planned. Soon afterward, weights within the satellite were released to shift along rods, serving as precession dampers.

In order to counteract the gradual slowing of rotation caused by interaction with the earth's magnetic field, three pairs of small spin rockets around the lower rim of the hatbox can be fired on ground command, when the spin becomes slower than nine revolutions per minute. At the time of writing (May 1st) none of these pairs had been fired.

To exploit scientifically the televised views of the earth, it is necessary to know for each moment the directions of the sun and horizon, as seen from the satellite. Two sets of sensors were provided for this, small infrared detectors being used to locate the horizon. The need for this elaborate system was demonstrated by the difficulties in interpreting cloud data from Vanguard II, whose spin was employed to scan the earth. Even for Tiros, there

Part of Lower California and a bit of mainland Mexico, as viewed by Tiros' wide-angle TV camera. The image was tape recorded, then radioed to Hawaii.



This cutaway drawing shows payload details of the meteorological satellite Tiros, launched on April 1, 1960. Labeled here are: 1, one of the two Vidicon TV cameras; 2, wide-angle camera lens; 3, tape recorders; 4, electronic timer for operations sequence; 5, TV transmitter; 6, chemical batteries; 7, camera electronics; 8, tape-recorder electronics; 9, control circuits; 10, auxiliary controls; 11, power converter for tape motor; 12, voltage regulator; 13, battery-charging regulator; 14, auxiliary synchronizing generator for TV; 15, transmitting antennas; 16, receiving antenna; 17, solar sensor; 18, solar cells; 20, de-spin mechanism; and 21, spin rockets (only three pairs were actually fitted). Both illustrations here are from National Aeronautics and Space Administration.



These two mosaics consist of 30 photographs by Tiros during its 14th and 15th circuits of the globe, on April 2nd. They show a vast cloud pattern associated with a mature cyclonic vortex about 400 miles west of Ireland. Cloud cover extends from Great Britain to Turkey, but skies were clear from the Strait of Gibraltar to Israel. Weather Bureau-NASA photo.

are some minor malfunctionings; the horizon sensors seem too responsive to small changes, and give data too complex for interpretation by the original electronic computer program. Also, there is some residual wobble, of a period too long to be controlled by the precession dampers. Together, these effects complicate the analysis of the cloud pictures.



The Tiros payload being given a vibration test at the Astro-Electronic Products Division of RCA, at Princeton, New Jersey. This satellite was designed and constructed by RCA, under the technical supervision of the U. S. Army Signal Research and Development Laboratory, Ft. Monmouth, New Jersey. Covering the sides of the cylindrical body can be seen some of the 9,000 solar cells that furnish electrical power. On May 1st this payload had a perigee height of 433.6 miles and an apogee of 473.3. The rocket casing had the same perigee, but apogee was 472.5. NASA photograph.

The television system in Tiros is powered by nickel-cadmium batteries that are kept charged by the solar cells. In all, the power consumption is about 19 watts. There are two television cameras having identical ½-inch Vidicon tubes, both with focal-plane shutters that provide 0.0015-second exposures. The cameras differ only in their lenses, one being an f/1.5 of about ¼-inch focus. This has a wide field of view, about 800 miles on a side from a height of 400 miles. The other is an f/1.8 2½-inch lens, covering an 80-mile square.

Images stored on the photoconductors of the Vidicon tubes are electronically scanned and converted into video signals. Some 250 picture elements form each line, and there are 500 lines per frame. The frame is scanned in two seconds, at a video band-width of 62.5 kilocycles per second. Magnetic tape traveling 50 inches per second can be used for storing the relatively slow video signal. Each camera has its own tape recorder with 400 feet of Mylar-base magnetic tape, enough for at least 32 consecutive frames.

When operated in this manner, the cameras take two exposures per minute, beginning at pre-selected times, which are stored in the satellite's memory device

by ground command. During readout of the tapes, in response to a radio order from a ground station, the 62.5-kilocycle signals modulate a 235-megacycle FM transmitter, operating at two watts. At two receiving stations — Ft. Monmouth, New Jersey, and Kaena Point, Hawaii — the transmitted pictures are displayed on a television system and photographed.

Alternatively, the cameras can transmit directly through the FM carrier, if desired, by-passing the tape-recorder system. This way of operation is feasible only when the satellite is above the horizon of a ground station. This was a fortunate provision, since the timer that regulated the tape recorder for the telephoto camera broke down soon after Tiros was put in orbit.

The problem of obtaining the maximum amount of televised information is complicated by the changing relations of the satellite's orbit plane, spin axis, and the sunrise-sunset line on earth. But the spin axis' departure from its intended orientation actually improves performance in some ways. Originally, views of the Northern Hemisphere were expected during the first 20 days in orbit, then those of the earth's southern portions until about the 35th day, then the Northern Hemisphere again until the 90th. Many of these views would be toward a very distant horizon, but a fair proportion would be nearly vertical.

Tiros has already yielded some highly significant scientific results. Weather Bureau meteorologists have found an unanticipated degree of large-scale organization in cloud systems. Previously, ground observations had covered only about one-fifth of the earth with reasonable completeness. The cost of a continuous patrol of the remaining areas should be less for satellites than for ships or planes.

A second Tiros is scheduled for late-summer launching by a Thor-Delta vehicle. It will be followed by a series of Nimbus meteorological satellites, featuring

This Tiros-eye view shows the Strait of Gibraltar, with clouds covering much of Spain and Portugal, while Morocco is clear. NASA photograph.

improved sensors that are to control orientation in polar orbits. The first Nimbus will be sent aloft, perhaps in late 1961, by a Thor-Agena B combination.

The third-stage rocket case of Tiros is larger and brighter than the instrument package itself, and hence they are designated 1960β1 and 1960β2, respectively. Their orbits are very similar, the period of revolution of the latter being 99.24 minutes on May 1st, only about 0.01 longer than the third stage's period.

Navigation Satellite

AN IMPORTANT new system of sea and air navigation has been brought much nearer practical use by the experimental Transit I-B satellite launched on April 13th. The day may not be far distant when ships at sea will routinely check their positions with the aid of earth-circling radio beacons — an all-weather method unaffected by clouds or by ionospheric disturbances that affect Loran, the present ground-based beacon system.

The 36-inch spherical payload, weighing 265 pounds, was sent aloft from Cape Canaveral at 12:02:36 Universal time that morning. The launching was the responsibility of the Air Force's Ballistic Missile Division, with the help of Space Technology Laboratories. A modified Thor IRBM served as the first stage, and the newly developed Able-Star for the second. The latter incorporated a revolutionary feature — its engine may be shut off after a period of powered flight, then turned on again by command.

It was planned to give Transit I-B a circular orbit by allowing the second stage to coast up to the desired height of over 500 miles, then restarting its engine to provide the final kick that would attain the circular velocity. As programmed, the second stage fired for 4.3 minutes before coasting upward for 19 minutes, its orientation being controlled by eight jets of nitrogen gas. The second burning period was 13 seconds, after which a pneumatic system started the satellite spinning about 168 times per minute. Seventeen seconds later, explosive charges separated the payload from the Able-Star stage.

The satellite itself is designated 1960γ2, while the second stage (14 feet 10 inches long and 4 feet 7 inches in diameter) that accompanies it in orbit is 1960γ1. Also in orbit is a third object, 1960γ3, detected by radar. This has been tentatively identified as the spin table to which the payload had been fastened.

The initial periods of these three bodies





Left: Cloud details observed with the narrow-angle TV camera from 450 miles above the Atlantic seaboard of the United States. Such high-resolution pictures have about 10 times the detail obtainable with the wide-angle camera. NASA photograph.

Right: At the top of the Tiros mosaic is a well-developed storm, centered over Nebraska at 3:30 p.m. EST April 1st. Compare it with the surface weather map (below); the cross marks the place from which the pictures were taken. U. S. Weather Bureau - NASA photographs.



Some components of the 36-inch spherical Transit 1-B are labeled here. Most of them are on an equatorial shelf, to aid the satellite's balance. Diagram from Applied Physics Laboratory, Johns Hopkins University.

were 95.9, 95.3, and 94.6 minutes, respectively, and all had orbital inclinations close to 51.3 degrees. Payload and second stage had perigee heights of 239 and 230 miles, respectively, while at apogee they rose to 472 miles. The scanty data for 1960γ3 gave 447 and 190 miles as its approximate limits.

Among the most important components of the payload sphere are two very stable oscillators, housed in Dewar flasks. These are being used to determine how ionospheric refraction of radio waves influences Doppler-effect measurements. One oscillator controls transmissions at 216 and 162 megacycles per second, and is powered by a double band of solar cells extending around the spherical satellite. The other, for 324- and 54-megacycle transmissions, is served by silver-zinc chemical batteries. Using four frequencies in a single payload gives much detailed information about ionospheric refraction.

Each transmitter operates at one-minute intervals. The antenna for all of them is a silver band painted around the surface of each hemisphere of the fiberglass housing, in the form of a logarithmic spiral. This arrangement permits the antenna to handle the sixfold range of transmitter frequencies.

Five ground tracking stations, in the United States, Canada, and England, are reporting their results to the Applied Physics Laboratory of Johns Hopkins University, which serves as prime contractor for the development of the navigation payload for the U. S. Navy's Bureau of Ordnance.

A second, entirely distinct experiment is also carried aboard Transit I-B, for the measurement of the earth's albedo (reflecting power) for infrared radiation. These results were telemetered to ground at a frequency of 108.03 megacycles until April 16th, when the Minitrack transmitter failed.

As mentioned, initially the Transit satellite was rotating 168 times a minute. By prearrangement, on April 19th two weights on long cables were released, slowing the spin to four times a minute.

Two additional experimental Transit satellites are planned before the actual navigational beacons are put into orbit. As presently envisioned, the complete navigation system will require four satellites simultaneously in orbit, to insure a convenient world-wide coverage. A key feature of the plan is that orbital data will be transmitted to each satellite, so that its continually repeated broadcasts will provide the shipborne navigator with all necessary information for determining his geographical position.

The ship's receiving equipment would include an oscillator for finding the frequency change (Doppler effect) in the received signals. From the manner in which the Doppler shift varies with time, the distance between the ship and satellite can be ascertained. At the moment when the shift becomes zero, the distance is a minimum, and the direction is perpendicular to the satellite's trajectory (to a very close approximation).

In actual practice, allowance will have to be made for the refraction of radio waves in the earth's atmosphere. A suitable shipboard computer should allow geographical positions to be determined with an accuracy of perhaps 0.1 mile.

The Transit navigational system may actually be less expensive to maintain than the Loran now in use, which moreover does not give complete coverage of the globe. Launching each of the operational Transit satellites, for which a five-year lifetime may be anticipated, might cost a million dollars, and the operating expenses of the ground installations could amount to three million dollars a year. Estimates of the cost of the shipborne equipment are comparable to that of Loran devices.

Discoverer XI

THE SEVENTH Discoverer satellite to attain an orbit around the earth is noteworthy as the first probe to carry its own light source. This object was Discoverer XI, sent aloft from Vandenberg Air Force Base in California, on April 15th at 20:30:37 Universal time.

Included in the 300-pound payload of 1960δ was a 10-pound package of tracking devices, which contained a Doppler radio beacon and external lights. The latter were arranged to shine for a few minutes when the satellite passed near each of four Smithsonian stations equipped with Baker-Nunn cameras. These stations, together with certain neighboring Moonwatch groups, were alerted to observe the high-flying speck of light, expected to be of about magnitude 8, as Discoverer XI passed within the shadow of the earth. Three of the four Smithsonian tracking stations were clouded out, but at San Fernando, Spain, successful observations were made.

On the satellite's 17th circuit of the earth, the recovery capsule separated from the Agena, according to telemetry data. But some unknown mishap seems to have occurred shortly after, for the capsule was not observed to descend within the recovery area. It did not continue in the same orbit as the satellite, for radar stations failed to detect it.

According to Space Track, the initial period of 1960δ was 92.3 minutes, and its apogee and perigee heights were about 345 and 110 miles, respectively. The nearly polar orbit had an inclination of about 80.1 degrees. This short-lived satellite is already down, having perished during its 172nd revolution, on April 26th between 17 and 18 hours Universal time. The descent probably took place in the Southern Hemisphere.

Discoverers IX and X had also been fitted with tracking lights, but neither went into orbit. The first failed to attain the necessary velocity; the other was blown up by the range safety officer 56 seconds after take-off.

MARSHALL MELIN
Research Station for Satellite Observation
P. O. Box 4, Cambridge 38, Mass.

CORRECTION

In the first paragraph on page 409 of the May issue, line 9, read "Lunik I" instead of "Lunik III." This error was pointed out by Jay H. Respler, Bronx, New York.

ASTRONOMICAL SCRAPBOOK

William Herschel and the Sun

FEW major astronomical discoveries have remained barren for so many years before springing into life as did the detection of sunspots in 1610 by Galileo and Fabricius. For two centuries following, these temporary dark markings attracted only casual attention, though from many astronomers.

The spots seemed of astronomical importance only in finding the rotation period of the sun, and the direction of its axis. To most astronomers of the 18th century, the sun was merely a convenient skymark for the determination of time and geographical latitude.

The beginnings of solar physics can be traced to Sir William Herschel. In his famous experiment of 1800, the great English astronomer used a prism to spread sunlight into a spectrum, then measured the rise in temperature of a sensitive thermometer exposed to different portions of the colored band. To his surprise, a marked heating effect occurred beyond the red end of the visible spectrum. Often this is nowadays referred to as the discovery of infrared radiation; Herschel, however, concluded that the visible light and the heat of the sun must be essentially different in nature. This misinterpretation of an ingenious experiment misled physicists for a generation, thanks to the prestige of Herschel's name.

In 1796, at a time when he was thinking much about variable stars, Herschel suggested that the sun itself might vary, and that this might explain climatic changes. Looking for some index number to characterize solar radiation, he proposed using the price of wheat in different years. A modern social scientist might call Herschel's notions of economics oversimplified, but clearly here is a pioneer attempt to study solar-terrestrial relations in a modern spirit.

Both these papers of Herschel's were anticipations of things to come, inspirations that awaited physical knowledge in one case, and statistical data in the other, before they bore fruit. The same cannot be said of Herschel's memoir of 1795 on the constitution of the sun, which is a curious survival of older fancies.

From time to time, Herschel noted that the umbrae of sunspots appeared to lie at a lower level than the solar photosphere. For example, "In the year 1783, I observed a fine large spot, and followed it up to the edge of the sun's limb. Here I took notice that the spot was plainly depressed below the surface of the sun; and that it had very broad shelving sides." From a number of such observations, he came to the belief that the sun is encased by a "shining atmosphere," in which occasional gaps occur, revealing the cool, dark "real body of the sun itself."

Analogies were collected to support this idea. To an observer on the moon, the earth's surface would be seen only between cloud areas, and this cover would be in part luminous, because of aurorae. Herschel continued: "Nay, we have pretty good reason to believe, that probably all the planets emit light in some degree; for the illumination that remains on the moon in a total eclipse cannot be entirely ascribed to the light which may reach it by the refraction of the earth's atmosphere. . . . The unenlightened part of the planet Venus has also been seen by different persons . . . this faint illumination must denote some phosphoric quality of the atmosphere of Venus."

Herschel did not hesitate to carry his speculation further: "The sun, viewed in this light, appears to be nothing else than a very eminent, large, and lucid planet . . . all the others being truly secondary to it. Its similarity to the other globes of the solar system with regard to its solidity, its atmosphere, and its diversified surface; the rotation upon its axis, and the fall of heavy bodies, leads us on to suppose that it is most probably also inhabited, like the rest of the planets, by beings whose organs are adapted to the peculiar circumstances of that vast globe. . . . [I] am persuaded that the foregoing observations, with the conclusions I have drawn from them, are fully sufficient to answer every objection that may be made against it."

Solar inhabitants! This fantasy was actually published in the *Philosophical Transactions* of the Royal Society. The suggestion that the sun was a cool, planetary body with a glowing atmosphere was not new, as John Flamsteed in 1681 and J. E. Bode in 1772 had proposed similar ideas.

But in an English courtroom in 1787, only eight years before Herschel wrote, the holding of this theory was alleged as a proof of insanity. This was the trial of Dr. Elliot for a murderous assault on Miss Boydell. A friend of the accused man offered as evidence of mental derangement a letter Dr. Elliot had written him the year before. This stated "that the sun is not a body of fire, as hath been hitherto supposed, but that its light proceeds from a dense and universal aurora, which may afford ample light to the inhabitants of the surface beneath, and yet be at such a distance aloft as not to annoy them. . . . Vegetation may obtain there as well as with us. There may be water and dry land, hills and dales, rain and fair weather; and as the light, so the season must be eternal, consequently it may easily be conceived to be by far the most blissful habitation of the whole system!"



These changes in the appearance of a sunspot indicate it is a depression. From W. M. Baxter, March "Journal," British Astronomical Association.

These strange notions still recur from time to time among persons who invent private cosmologies without benefit of modern astronomy. Shortly after World War II, a German named Gottfried Bueren became an enthusiastic champion of the cold-sun theory, and publicly wagered 25,000 marks that he could not be proven wrong. A group of leading West German astronomers took up this challenge, and submitted the proof. When Bueren refused to accept it, the case was taken to court, and in 1953 the astronomers won the 25,000 marks with costs.

JOSEPH ASHBROOK

NEW YERKES-McDONALD DIRECTOR

William W. Morgan has been appointed director of Yerkes Observatory, Williams Bay, Wisconsin, and of McDonald Observatory, Ft. Davis, Texas. At the same time, he becomes chairman of the joint astronomy department of the universities of Chicago and Texas.

He succeeds Gerard P. Kuiper, who will become a research professor at the University of Arizona, dividing his time between its Institute of Atmospheric Physics, the astronomy department, and Steward Observatory.

Dr. Morgan has been associated with Yerkes for three decades, and is world-known for his refinements in the classification of stellar spectra. Some of his most recent work was on typing of galaxies.

To assist Dr. Morgan, Frank N. Edmonds, Jr., has been named associate director of McDonald, and Joseph W. Chamberlain, associate director at Yerkes.

MEDAL TO E. J. OPIK

The J. Lawrence Smith medal for 1959 has been awarded by the National Academy of Sciences to Dr. E. J. Opik, University of Maryland, until recently at Armagh Observatory and editor of the *Irish Astronomical Journal*. The medal is granted not more than once every two years for investigations of meteoric bodies, a field in which Dr. Opik has made outstanding contributions.

Why Observe Stellar Eclipses?

ALAN H. BATTEN, *University of Manchester, England**

TOTAL ECLIPSES of the sun for a long time have afforded astronomers their only chances of observing certain solar phenomena. Even though coronagraphs and other special instruments have been developed, solar eclipses still provide opportunity for many important observations. Likewise, for the past half century, eclipses of stars have been recognized as a source of much useful information.

Since the orbital plane of the moon is only slightly inclined to that of the earth, the moon can pass in front of the sun from time to time, producing a solar eclipse. Similarly, stellar eclipses result when the orbital plane of a binary star system is so oriented in space that each component can alternately obstruct the other's light on its way to the earth.

Just as eclipses of the sun can be total, annular, or partial, so can those of the stars; and, as with the sun, total stellar eclipses are the most useful ones to observe. There is one difference, however. For any given binary system, the kind of eclipse is fixed by the position of the orbit in space. Thus, we always observe either successive partial eclipses or total and annular eclipses; in the latter cases the larger star of the pair is first in front of and then behind the smaller one.

Viewed from the earth, these eclipsing systems appear as single stars; how, then, can they be recognized? It is obvious that eclipses must cause variations in the total light that we receive from each pair. Eclipsing binaries, therefore, are usually discovered in the course of any systematic search for variable stars. The characteristic nature of their light curves distinguishes eclipsing stars from other kinds of variables.

In the ideal case, the light of the system is constant for a considerable part of each orbital revolution, because both stars are shining unobstructed. (Only rarely is either component a truly variable star.) Then, as an eclipse begins the system's brightness gradually decreases, for one star is cutting off the light of the other. If the eclipse is total, there is another time of constant but fainter light: then, as the second component emerges from behind the first one, the light of the system increases until it regains its former level.

When the smaller star is in front of the other, the eclipse is annular instead of total. On the other hand, during an eclipse that is only partial, the light varies continuously and increases again as soon as minimum is reached. Light curves of these different possibilities are illustrated here.

Most eclipsing systems go through a complete cycle of two eclipses in a few days; these are stars that are close to each other and so are traveling quickly in their orbits. Many have periods of less than a day (refer to page 508). On the other hand, a few eclipsing systems have periods of some years; the stars may be widely separated in proportion to their sizes, but their orbits lie very nearly in the line of sight, that is, at right angles to the plane of the sky.

John Goodricke (1764-86) was the first to recognize the typical variation of an eclipsing system. During his short life, he discovered the periodic nature of the light changes of Algol and Beta Lyrae, and suggested that they were caused by eclipses. But it was not until the early part of this century that the work of H. N. Russell and H. Shapley made it possible to begin extracting the information a light curve contains. Since then, the simultaneous development of new computational techniques and of more accurate methods of observation has allowed a wealth of important astrophysical data to be obtained from eclipsing variables.

The details of the light curve depend on the geometry of the eclipsing binary system. Thus, the duration of each eclipse, measured as a fraction of the period, must depend on the dimensions of the two stars relative to the diameter of the orbit, as well as on the angle between our line of sight and the orbital plane.

The problem of analyzing a light curve is to calculate these various quantities from the observations. Then a scale "model" of the system can be made, in which all relative dimensions and the orientation of the orbit are known. However, the absolute size of the orbit is un-



In this schematic diagram, five varieties of eclipsing-variable light curves are interpreted. For each case, brightness increases upward, and time toward the right. The hotter star has the greater surface brightness, so the deeper eclipse always occurs when it is behind the other one. The hotter component may be either the larger or smaller of the pair. In the fourth example, the stars are brightest at their centers, darkest at their edges.

*At present on leave of absence to the Dominion Astrophysical Observatory, Victoria, British Columbia, Canada.



Above: The Algol-type eclipsing variable TX Ursae Majoris consists of a main-sequence B8 star and an F2 giant. In this light curve, based on photoelectric observations by C. M. Huffer and O. J. Eggen, small reflection and ellipticity effects are visible. The period of light variation is about 3.06 days.

Right: The limb-darkening of many stars also occurs in the sun, as shown by this photograph, which was made June 16, 1937, by W. M. Kearons, with a refractor.

known, and the geometrical problem is complicated by various physical considerations.

For example, depth of eclipse is determined by the relative luminosities of the two stars. For a totally eclipsing binary, these can be obtained from an inspection of the light curve, but in a partially eclipsing system the fraction cut off from the total light of the eclipsed star adds another unknown quantity. To complicate matters further, stars do not radiate uniformly all over their apparent disks. Photographs of the sun show that it is darkened toward its edge or limb. The limb darkening of stars cannot be observed in this fashion, but when one star moves across the other during an eclipse the amount of light loss is different for equal areas at the center and at the limb of the eclipsed star. This affects the shape of the light curve during partial and annular phases.

Another difficulty is caused by the limited accuracy of photometric observations. Even the best observer with the most modern photoelectric apparatus can do no better than the earth's atmosphere will allow. The many small irregularities that cause the stars to twinkle can wreak havoc with photometric observations. To illustrate this point, it is helpful to recall that a planet's orbit may be calculated from three observed positions. So too, in principle, an orbit for a totally eclipsing system might be deduced from only three brightness measurements at different phases of the eclipse. In practice, however, up to several hundred have to be used to compensate for the limited observational accuracy.

Formidable difficulties are introduced in very close binaries where the components are separated by only a few times their radii. In such a case, tidal distortion of the stars and "reflection" of the light of one by the other produce brightness variations during the time between eclipses. Analysis of the light curve becomes very intricate when an elongated star, whose surface brightness differs from point to point, is partially covered by another distorted star.

Since so many factors influence the shape of a light curve, it is not surprising that unraveling the various effects presents a complex problem. In a strict mathematical sense, it has no exact solution, because some properties of the system have to be assumed before others can be derived. To obtain any solution at all, we have to find the ratio of the radii of the two stars, and the limb-darkening coefficient, which expresses the amount by which the eclipsed star is darkened at the limb. The problem is simpler for a light curve displaying a total eclipse. We can tell immediately which star is the hotter, as it is being eclipsed during the deeper minimum. The relative depths of the primary and secondary eclipses can then be used to give the ratio of the radii. An annular eclipse allows the limb darkening to be determined, for there is a slow variation of light during the annular phase.

In a partially eclipsing system, neither of these aids is available, and it is often necessary to start with an outright guess of these two quantities. Fortunately, the solutions possess the property of convergence. That is to say, if values of the ratio of the radii and limb darkening are assumed, certain information can be derived about the binary system, including improved values of these quantities. Employing them, a new solution can be made. But even this method is useful only if both eclipses are deep and have been well observed. Otherwise, a light curve of a partially eclipsing system is practically useless.

If knowledge can be obtained from stellar eclipses only with so much dif-



F. B. Wood used 323 photoelectric observations for this light curve of RX Herculis. The slight rise and fall in brightness between eclipses indicates elliptical stars, but there is no appreciable reflection effect. This is one of the few cases in which orbital eccentricity (0.018) can be determined from the light curve alone. The system's normal maximum magnitude is 7.3, and the components are of spectral type A0.

ficulty, why is so much time spent observing them? The answer is that they are the principal source of many kinds of much needed information. From eclipsing binaries a great deal can be learned about the sizes and masses of stars, the structure of stellar atmospheres, and even about the internal structure of stars.

It has already been indicated that relative dimensions of an eclipsing variable may be obtained from its light curve, providing, in effect, a scale model of the system. If the binary has been observed spectroscopically, the radial velocity measurements should give the actual orbital speeds of the component stars, in kilometers per second. From these values, all the linear dimensions of the scale model can be obtained, that is, the actual sizes of the two stars and their distance apart. Furthermore, masses of the components may be determined from a generalized form of Kepler's third law of planetary motion. In addition, the stars' surface temperatures may be estimated from their spectral characteristics. These, combined with their actual dimensions, lead to their intrinsic luminosities or absolute magnitudes, and to an estimate of the distance.

Information about the structure of stellar atmospheres is obtained from the limb-darkening coefficients. With modern procedures, it is possible to observe the same system simultaneously in several colors. The limb darkening of a star is not the same in different colors, varying with wave length in a manner that depends on the opacity of its atmosphere. The most suitable binaries to observe for this effect are those undergoing deep annular eclipses.

Those double stars that have noncircular orbits aid studies of stellar internal structure. In an elliptical orbit, the speed of each component is not constant and the eclipses are usually not separated by half the period, nor are both eclipses of the same duration. This displacement of one minimum of the light curve with respect to the other, and the difference in duration of minima, depend on the shape or eccentricity of the orbit, and the angle that the major axis makes with the direction to the earth. If the stars are close enough to distort each other, the major axis will rotate slowly, thus changing the form of the light curve. The rate of the rotation depends on the internal structure of the stars themselves. Although velocity curves of spectroscopic binaries also yield this information, eclipsing stars serve as a useful check.

Perhaps it was obvious that eclipsing systems should provide data about the sizes and shapes of their component stars. It may seem surprising, however, that they should also prove to be a source of facts concerning physical conditions in the atmospheres and deep interiors of stars. It is this wide range of information that makes stellar eclipses so important.

It may well be that there are more double than single stars in the sky. Of course, only a tiny fraction of these will be observable as eclipsing binaries, but even this number is so large that there is no hope of discovering all such systems as are believed to exist. And among these, many different types of stars will be found. Thus, from a comparative study much may be learned about stellar evolution — a further reason for observing eclipsing variables.



One famous eclipsing binary system is u Herculis, which varies between magnitudes 4.5 and 5.1 in a period of 2.05 days. At the left is its velocity curve, determined by Burke Smith in 1945. The black dots show the motion of the primary component, the circles the secondary. The curves cross when the stars' relative motion in the line of sight is zero, at mid-eclipse. These times correspond to the minima in the light curve plotted below, where the time scale is expanded.



An early photoelectric light curve of u Herculis by W. Calder, at Harvard.

QUESTIONS... FROM THE S+T MAILBAG

Q. When will Saturn's rings next be presented edgewise to the earth?

A. On December 13, 1965, when the earth will pass through the plane of the rings from north to south. The following year two passages through the ring plane will take place. The rings were last edgewise on September 14, 1950.

Q. How much of the time is the moon above the horizon at the North Pole?

A. Not counting the effect of atmospheric refraction, it is above the horizon at each pole for half of the lunar month, being generally invisible at one pole when visible at the other. It appears about two weeks at a time, and is absent equally long; but it is difficult to detect when the sun is high in the sky during the six-month polar day. In winter, however, the gibbous or full moon is a conspicuous and welcome sight in arctic and antarctic regions.

Q. How much dust and gas is there in interstellar space, compared with the material in the form of stars?

A. In the region of the nearer stars, about a quarter or a fifth as much, but this is uncertain.

Q. How were the constellation boundaries used in modern atlases established?

A. To avoid ambiguity in assigning stars (especially variables) to individual constellations, in 1930 the International Astronomical Union officially defined the boundaries of all 88 star groups. The dividing lines run along circles of right ascension and declination, referred to the epoch 1875.0. This epoch was chosen because it had already been employed in B. A. Gould's delimitation of southern constellations.

Q. What is a Julian day number?

A. Assigned to any date, it is the count of days that have elapsed since January 1, 4713 B.C., which is Julian day 0. This consecutive numbering of days makes it easy to find the exact interval between two widely separated dates, such as of variable star maxima or minima. June 1, 1960, is Julian day 2,437,087.

Q. What is a planetary nebula?

A. It is a luminous body of very rarified gas, having a roundish appearance and superficially resembling a planet's disk as seen in a small telescope. Usually, there is a very faint, hot central star that causes the gas of the nebula to glow, producing a spectrum of bright lines.

W. E. S.

AMERICAN ASTRONOMERS REPORT

Here are highlights of some papers presented at the 105th meeting of the American Astronomical Society at Pittsburgh, Pennsylvania, April 18-21, 1960. Complete abstracts will appear in the Astronomical Journal.

Symposium on Subdwarfs

Stars along the main sequence of the spectrum-luminosity (H-R) diagram with spectral types later than *A* are generally called dwarfs, the sun being a typical example. Among them, however, are some objects that have low intrinsic luminosities for their spectral classes and therefore lie below the main sequence by amounts ranging up to 1½ magnitudes. These are usually designated *subdwarfs*, though whether they constitute a particular kind of star or a mixture of kinds is not known.

On April 21st at Pittsburgh, five astronomers discussed current problems of the subdwarfs, the symposium moderator being Martin Schwarzschild of Princeton University Observatory. His comments and the question period after each paper served to emphasize the fluid character of present-day thinking concerning subdwarfs, their nature, and their evolution, and indicated very strongly the need for more observations of their parallaxes, motions, and spectra.

The first speaker was the director of Sproul Observatory at Swarthmore College, Peter van de Kamp, who pointed out that we have very few reliable trigonometric parallaxes for subdwarf stars. Many such stars are considerably too faint for the 24-inch Sproul refractor or the 30-inch Thaw refractor of Allegheny Observatory in Pittsburgh (where stars to the 13th magnitude are on the parallax observing program), and even the brighter cases have been insufficiently observed.

Therefore, Dr. van de Kamp's talk was mainly a plea for the use of larger telescopes, including the biggest reflectors, for measurements of distances to these stars. Work has been done with the 100-inch Mount Wilson reflector, but parallax programs require repeated observations at particular times over a number of years, and the large instruments are heavily scheduled for other work. Furthermore, they were not designed to have the extreme optical and mechanical stability desirable in trigonometric measurements.

Hence, the Sproul astronomer supported strongly the construction of a long-focus astrometric reflector, perhaps 60 inches in aperture, f/10, as proposed by K. A. Strand several years ago. Such an instrument, designed with the special problems of parallax work in mind, could reach stars of apparent magnitude 18 or 18.5 in about seven minutes of exposure time. The effects of temperature changes, which are particularly serious during the early evening observations essential in parallax programs, could be practically eliminated if the primary mirror and secondary optical components were made of quartz, something now entirely feasible.

Subdwarfs are in general high-velocity stars, that is, their motions with reference to the center of the Milky Way galaxy differ greatly from the sun's. Perhaps they originated in the galactic center, and indicate some of its characteristics. Thus it becomes very important to determine their individual and collective space motions, and this problem was discussed by Olin J. Eggen, an American-trained astronomer now on the staff of the Royal Greenwich Observatory, Herstmonceux, England.

In order to determine a star's space motion, we must know its parallax, proper motion, and radial velocity (motion in the line of sight). Concerning these quantities, Dr. Eggen said his talk was "really a report on the inadequacy of the data." But known subdwarfs range in apparent magnitude from 4th to 14th, and a few good radial velocities have been obtained, mostly by A. H. Joy with the 100-inch Mount Wilson reflector and by G. Munch and D. M. Popper with the McDonald 82-inch telescope. Several newly discovered subdwarfs in the southern hemisphere have been observed by T. J. Deeming with the 74-inch reflector at Pretoria.

By diligently searching through the material on faint stars, the Herstmonceux astronomer has culled out of all suspected subdwarfs some 200 relatively good cases. About 50 of these have fairly reliable values for radial velocity, proper motion, and three-color photometric data. Distances have been determined for them

Participating in the Pittsburgh symposium were, from left to right, Thomas L. Swihart, Los Alamos Scientific Laboratory; Pierre R. Demarque, Louisiana State University; Olin J. Eggen, Royal Greenwich Observatory; Martin Schwarzschild (hand on arm), Princeton University Observatory; Lawrence H. Aller, University of Michigan Observatory; and Peter van de Kamp, Sproul Observatory.

The old home of Allegheny Observatory, founded in 1860. It was located about one mile south of the present observatory site. The large dome housed a 13-inch Fitz refractor, with which S. P. Langley in the 1870's made marvelously detailed sunspot drawings. Other Allegheny directors of the first rank were J. E. Keeler, F. L. O. Wadsworth, F. Schlesinger, and H. D. Curtis.

An early view of the present Allegheny Observatory of the University of Pittsburgh, dedicated in 1912. In the largest dome is the 30-inch refractor by Brashear, used for stellar parallaxes; the others house a 31-inch Brashear reflector (stellar spectroscopy), and the 13-inch Fitz telescope.

on the basis of the observed ultraviolet excess in the colors and the relation between this excess and the absolute luminosity that is predicted by the line-blanketing theory of Dr. Eggen and A. R. Sandage.

The space motions obtained for this small sample indicate that some 25 per cent of its stars may belong to two stellar groups, one of which is the Groombridge 1830 group previously studied by Drs. Eggen and Sandage. Also, the velocity vectors for the stars in the sample seem to show that subdwarfs do not partake of the rotational motion of the galaxy as measured for the majority of the stars near the sun. Better faint-star proper motions would help extend analyses of this kind.

The physical and chemical characteristics of the subdwarfs were considered by the last three speakers in the symposium, beginning with Pierre R. Demarque, Louisiana State University, who has calculated theoretical models for the interiors of stars with subdwarf characteristics. He pointed out that the chief problem was to explain the apparent metal-deficient composition of most subdwarfs. His first work concerned star models having 0.6, 0.8, and 1.0 solar mass.

In some cases hydrogen was assumed to comprise 0.999 of the star by weight, with the metals only 0.001, and in other cases the hydrogen was taken as low as 0.75 and the metals as high as 0.1, the remainder being helium. As with other dwarf stars as cool as the sun, the proton-proton reaction — building up helium from hydrogen — was taken as the main source of the star's radiant energy.

The Demarque models, calculated with the aid of an IBM 650 computer, have a central core in radiative equilibrium and an outer zone in which convection plays a predominant role in the transportation of energy. These models are like those already calculated by D. E. Osterbrock for red dwarf stars. The star's radius depends on the boundary conditions, but the helium content has a strong effect on the total luminosity. For stars of the same mass, a bolometric difference of two magnitudes was found between the extreme cases of all hydrogen and 75 per cent hydrogen, with the metal abundances affecting the results only slightly. Thus, helium content determines such a star's place in the H-R diagram. Unfortunately, these theoretical models can only be compared with the subdwarf stars in a general way, because we do not yet have a first-class mass determination of any individual object of this variety.

Similarly, models for subdwarf atmospheres have been worked out by the fourth symposium speaker, Thomas L. Swihart, of Los Alamos Scientific Laboratory in New Mexico. His examples included cases in which the metal abundances were 1/3, 1/10, and 1/100 those in the sun. The effective surface temperatures were taken at six values between 4,200° and 8,400° K. The logarithm of surface gravity varied between 4.1 and 4.44, the latter being the value on the sun; while the helium content was taken as zero in some cases and as high as 20 per cent in others.

In the visible region of the spectrum, the emitted radiation of the model atmospheres is in satisfactory agreement with that observed in subdwarf stars, but at shorter wave lengths (in the ultraviolet) important discrepancies do exist. The uncertainties are too large to allow a definite conclusion, but it appears that subdwarfs have nearly the same radii, and therefore luminosities, as normal stars of the same temperatures. The excess amount of radiation that these stars have in the ultraviolet makes them appear hotter and earlier in spectral type than they actually are.

The final speaker, Lawrence H. Aller, University of Michigan Observatory, further considered the abundances of elements in subdwarf atmospheres. He pointed out that the faintness of the most interesting subdwarfs makes them difficult objects for spectral analysis, particularly since their spectrum lines are weak owing to the low metal abundances. It is necessary to secure plates with the highest possible dispersion, otherwise the worker will tend to overestimate the equivalent widths of weak lines.

Jesse L. Greenstein has used the coude spectrograph of the 200-inch telescope at Palomar Observatory to secure spectra with a dispersion of 4.5 angstroms per millimeter. These plates provide the best

The American Astronomical Society had not met at Pittsburgh since August 28, 1912, when these members were among those present. At upper left is J. S. Plaskett, Dominion Astrophysical Observatory. Seated left is F. C. Jordan, Allegheny, and just behind him W. S. Eichelberger, U. S. Naval Observatory. In the left foreground is F. Schlesinger, Allegheny, and standing center E. C. Pickering of Harvard. Behind his left shoulder is G. C. Comstock, Washburn Observatory, and at upper right Z. Daniel of Allegheny. J. A. Brashear has his arm around fellow Pittsburgher Stephen Thaw.

data for analysis of two extreme subdwarfs, HD 19445 and HD 140283. Drs. Aller and Greenstein found that the so-called *F* subdwarfs were really *G* stars with temperatures comparable to that of the sun. Furthermore, they differ in metal depletion from one object to another. HD 19445 has a metal abundance only 1/40 that of the sun, whereas for HD 140283 this factor is 1/100.

Can the atmospheric composition differ from that of the stellar interior? Diffusion of gases might produce such an effect, because heavier elements sink with respect to lighter ones. The precise amount of this effect depends on the outer layers of a star. We believe that generally in stars like the sun there is a thick convection zone surrounding the interior core. Diffusion from the lower surface of this zone could result in the loss of heavier atoms, but the process cannot influence the atmospheric layer unless the convection zone is thin.

Quantitative calculations are difficult, but some estimates for the sun have been carried out by Dr. Aller and Sidney Chapman. Their work indicates that in 4½ billion years the abundances of the heavier metals in its atmosphere could be altered by 50 or even 100 per cent. The exact amount of the effect depends on the depth of the convection zone and cannot be determined until this depth is known.

But such diffusion apparently cannot explain the metal deficiencies in subdwarfs, since diffusion depletion should depend smoothly on atomic number, that is, increasing with the weight of the atoms involved. It does not do this in subdwarfs, where, for example, the deficiency of nickel appears to be considerably less than that of iron, while the light element carbon is more strongly depleted than any metal. Therefore, explanations of subdwarf abundances must be sought in terms of processes whereby elements are built up or broken down.

Calculations of mean pressures, masses above the photosphere, and chemical-compound concentrations have also been carried out by Dr. Aller and his coworkers. Next to H_2, the most abundant molecule in cool subdwarfs is water, H_2O; the hydrides are emphasized, and molecules like CN and CH are decreased.

Companion of Fourth Nearest Star

The 7th-magnitude red dwarf Lalande 21185 is only 8.1 light-years distant, and has the unusually large proper motion of 4.8 seconds of arc per year. It is in Ursa Major, at $11^h\ 00^m.6$, $+36°\ 18'$ (1950 coordinates).

Since 1912, this star has been photographed with the 24-inch refractor of Sproul Observatory, where in 1944 P. van de Kamp found that the proper motion underwent slight variations, indicating the existence of an unseen companion. Sarah Lee Lippincott now reports new



Deviations of Lalande 21185 from straight-line proper motion are plotted here in right ascension (east-west) and declination (north-south), the wavy curve representing a Keplerian orbit. On the original Sproul Observatory plates, an image displacement of 0.04 second of arc corresponds to only 0.002 millimeter.

facts about this binary system, based on plates taken on 315 nights over the years from 1912 to 1959, which gave data that were analyzed with an IBM 650 computer.

From measurements of the positions of Lalande 21185 with respect to field stars, she first redetermined the parallax and average proper motion. The remaining deviations indicated that the visible star was moving with a period of 8.0 years in an elliptical orbit (eccentricity 0.30) around the center of gravity of itself and the invisible companion.

The primary star has an absolute magnitude of +10.5, so it is intrinsically about 1/200 as bright as the sun. The secondary star may be more than three magnitudes fainter, for it has hitherto escaped detection, even though when farthest apart the two stars should be separated on the sky by more than a second of arc. This considerable brightness difference implies that the companion is of very small mass, perhaps only 1/40 that of the primary, which itself has about 4/10 the sun's.

Thus, the invisible companion is an object of exceptionally small mass, perhaps 1/100 of the sun's and only 10 times Jupiter's. Direct detection, perhaps in the infrared with photoelectric scanning apparatus at one of the times of widest separation of the pair, might permit a straightforward determination of the companion's mass.

Proposed Explanation of Martian Phenomena

Viewed from space, the earth would show striking seasonal changes resulting from the presence in its atmosphere of water, which can exist in solid, liquid, and gaseous form at terrestrial temperatures. In the atmosphere of Mars, there is too little water vapor for spectroscopic detection, but oxides of nitrogen may play an analogous role there. This suggestion has been advanced by C. C. Kiess, S. Karrer, and Harriet K. Kiess, of Georgetown College Observatory.

Absorption of light by gaseous nitrogen peroxide ($NO_2 + N_2O_4$) could account for the low albedo of Mars as observed in green, blue, and violet light. The polar caps of the planet might be attributed to chalky white deposits of solid nitrogen tetroxide (N_2O_4), which in equilibrium with the dioxide has a yellowish tint.

The melting point of nitrogen tetroxide is −11° centigrade or 12° Fahrenheit. This is 20 degrees below the melting point of water, but Mars' average temperature is lower than the earth's. Hence, the dark band observed at the edge of a melting Martian polar cap may be composed of liquid N_2O_4, with nitric oxide (NO) or nitrogen trioxide (N_2O_3) in solution, or both. However, for nitrogen tetroxide to exist as a liquid, the pressure of Mars' atmosphere would have to be about twice as great as its estimated 65 to 75 millimeters of mercury.

Dr. Kiess and his colleagues proposed that heavy N_2O_4 gas spreading toward the Martian equator may cause the seasonal changes in color of the dark regions. Minute crystals of nitrogen oxides in the planet's atmosphere could produce such observed phenomena as haze, transient blue and white clouds, and limb brightening.

One long-standing Martian puzzle has been the *blue clearing* — a temporary transparency of the planet's atmosphere to blue and violet light, which normally cannot penetrate it. If the veiling is due to NO_2, then the clearing may be attributed to polymerization of this gas to N_2O_4, as a result of a cold wave over a large part of the planet. On the other hand, during a heat wave there would be an increase in the NO_2 concentration, perhaps accounting for the yellow clouds, which at times are almost planet wide.

If this interpretation of Martian phenomena is correct, life on that planet is unlikely, because of the toxicity of the oxides of nitrogen.

Dr. Kiess has reported to the National Academy of Sciences spectroscopic observations of Mars with moderate dispersion, finding diffuse absorption features that he identifies as unresolved bands of NO_2. But the question must be studied of whether nitrogen peroxide in the Martian atmosphere would be stable against photochemical decomposition by ultraviolet sunlight. Laboratory data are somewhat contradictory.

Left: A wall-type sundial, erected at Rapperswil, Switzerland, in 1947-48, that here reads about 11:10 a.m. Right: This ornamented modern armillary sphere at Andover, Massachusetts, can indicate apparent solar time.

A New Universal Sundial Design

HERMANN H. EGGER

RECENT improvements in the design and manufacture of sundials have brought these long-neglected timekeepers to the forefront again as objects of interest and beauty. Modern sundials are both ornamental and useful when placed in gardens, public places, and school recreation grounds, or at observatories, planetariums, and museums.



Made in 1740 by T. Müller, Augsburg, Germany, this four-inch universal sundial's hinged equatorial ring (carrying the shadow pin) can be set for any latitude. In the Southern Hemisphere, shadow travel is reversed.

Usually a sundial remains in a single location throughout the years. It is set to match the latitude of the place and cannot be conveniently moved to another latitude. This is especially true of wall sundials, like the one here in Switzerland shown above, and Newton's sun and moon-dial at Queens' College, Cambridge (SKY AND TELESCOPE, August, 1957, page 480).

Universal sundials have the advantage of being usable in various places, without the need of a new calculation for each particular location. An old example is the portable dial of 1740 pictured here. Its hinged equator ring is set in accordance with the latitude, and the shadow cast by its central pin shows, for northern latitudes, the apparent solar time of the place.

In my two new universal sundials, there is no central shadow-pin or gnomon, standard time being read by broad shadows from the straight edges of the portions of cylinders that make up the device. This unique construction results in hour intervals that are relatively twice as wide, and therefore more accurate, as those on a sundial with the style on the axis of the cylinder.

The sketch shows the principle by which these dials work. They are erected with the shadow-casting edges parallel to the earth's axis of rotation, that is, with

the edges pointing to the celestial poles. This setting corresponds to the equatorial mounting of a telescope, the cylinder segments being inclined from the vertical by an amount equal to the observer's latitude.

When this orientation is obtained, the sundial is rotated about its central axis until it reads the *standard time* of the moment of setting. As long as the geographical location is not altered, this setting does not change, and automatically compensates for the difference between the observer's longitude and that of the standard-time meridian. The sundial will thus continue to show standard time.

The difference between mean time and apparent time is taken care of by the wavy character of the hour marks, which incorporate the principle of the analemma found on many sundials. They compensate throughout the year for the equation of time – the amount the real sun is running ahead of or behind the mean sun.

To retain a simple appearance for this model, I have used the numerals I, II, III, IIII to indicate the four quarters of the year, but the large construction of the scale permits marking the month and day down each of the hour curves. It is also possible to add undulating minute lines between the hour lines, to facilitate accurate reading of the time. In a dial of sufficient size, it is thus a simple matter to represent every minute of every day throughout the year.

Each segment takes care of four hours, for those dials made up of six cylinders, or two hours for the 12-cylinder design. Only in polar regions during the summer would the sun cast shadows for continuous 24-hour periods all the way around the dial. The lower row of numerals appears right side up when the device is used in the Southern Hemisphere.

The simple beauty of these sundials makes them very appropriate for garden ornaments. When made of bronze, they are unbreakable and weatherproof, and lend themselves to reproduction in series. They can be built of stone in larger sizes.



Standard time can be shown anywhere on the earth with this universal sundial designed by Hermann Egger. Each cylindrical section measures four hours, and contains reading curves to compensate for the equation of time. A supporting shaft, inserted in the hollow center, must be aligned to the pole.

SOLARIUM·UNIVERSALE





Left: Beneath a plan sketch of the Egger sundial is the scheme of the side markings. Three hourly positions of the sun are indicated at bottom right, the dashed lines showing how the shadow moves across the sundial.

Right: Mr. Egger's "classical" design has 12 flutings instead of six, being patterned after Grecian columns. The author supplied all illustrations with this article.

NEWS NOTES

MASS OF SATURN

Last year R. H. Krotkov and R. H. Dicke of Princeton University called attention to a small discrepancy between the observed and predicted motions of Jupiter. This has the form of a small oscillation in the orbital longitude of that planet, amounting at most to only 0.25 second of arc as seen from the sun, and with a period close to the 12 years of Jupiter's revolution.

This effect has now been explained by G. M. Clemence, of the U. S. Nautical Almanac Office, as due to a small error in the adopted value of the mass of Saturn, a body whose attraction greatly influences the motion of Jupiter. Dr. Clemence finds that the discrepancy is removed if Saturn's mass is 1/3499.7 that of the sun.

Previously, the most precise value of the mass of Saturn was 1/3497.6, determined in 1953 by H. G. Hertz from a study of Jupiter's motion. An older figure, 1/3501.6, is still used by the national ephemerides, since there are great advantages in keeping predicted positions of the planets on a strictly uniform basis over many years. Dr. Clemence has reported his study in the February *Astronomical Journal*.

PECULIAR SOLAR OBSERVATIONS EXPLAINED

On January 16, 1959, Swedish astronomer Yngve Ohman was observing the sun at Stockholm Observatory through a telescope equipped with a hydrogen-alpha filter. His attention was caught by a rapidly moving dark object crossing the sun, which on passing the solar limb appeared as a bright surge, visible for about two seconds and extending about two minutes of arc outward from the sun. A month later, a similar observation in white light was made by a colleague of Dr. Ohman's.

It was suspected that these apparent prominences might be caused by very distant jet planes passing in front of a fairly low sun. The Swedish Air Force co-operated in testing this hypothesis, and two transits of a jet plane, distant about 10 kilometers, were observed. In each case apparent prominences were seen, lasting somewhat over one second, and having a brightness similar to that of the solar surface. Dr. Ohman's account appeared in the *Observatory* for December.

C. S. GUM DIES

Colin Stanley Gum, noted 36-year-old Australian radio astronomer and senior lecturer in astrophysics at Sydney University, died on April 28th in a ski accident near Zermatt, Switzerland. He had spent 10 months as a Carnegie fellow at Mount Wilson and Palomar Observatories, and was vacationing on his way to Germany to discuss with manufacturers plans for a 36-inch reflector for Sydney. He was much interested in interstellar polarization and galactic magnetic fields.

Previously, Dr. Gum had served on the International Astronomical Union's subcommission 33b, which established the new system of galactic co-ordinates adopted at the Moscow meeting.

NSF TENTH ANNIVERSARY

Established a decade ago by an act of Congress, and beginning operations in 1951 with an appropriation of $3\frac{1}{2}$ million dollars, the National Science Foundation has become a major stimulus to the development of scientific research and education in this country. The appropriation for the current fiscal year, 1960, is 152 million dollars.

Astronomy has received no small part of NSF funds over the years, beginning with $8,000 in 1952 for basic research grants. In 1959, 51 grants were made, totaling almost two million dollars. During those eight years, 190 project applications were accepted, and over four million dollars expended. Combined with physics, the fellowship awards amounted to six in 1952 and 21 in 1959.

Furthermore, the foundation directly maintains the National Radio Astronomy Observatory at Green Bank, West Virginia, the total budget for construction, operation, and maintenance through 1960 being $10,380,000. Kitt Peak National Observatory, Tucson, Arizona, has the same status, at a cost of $8,445,000 to the present.

A detailed history of NSF's first 10 years is given by its director, Alan T. Waterman, in *Science* for May 6, 1960, page 1341. But on page 1363 of the same issue, there is a disconcerting report that on April 20th the House of Representatives curtailed the foundation's 1961 budget by $31,600,000. The two observatories could receive only pre-operational interim support, and the space telescope project at Kitt Peak would have to be canceled, if the Senate goes along with the House in this matter.

PLANETARIUM ENDOWMENT

The sum of $50,000 has been given to Newark Museum by Mr. and Mrs. Leonard Dreyfuss for the maintenance of its planetarium, and to outfit and maintain an observatory, whose construction began this spring. The planetarium is the only one in New Jersey, and has been attended by over 200,000 people since it opened in January, 1953.

The administration of grants in astronomy by the National Science Foundation has been carried out by these program directors, who gathered for the Kitt Peak National Observatory dedication in March. In order of service they stand right to left: Peter van de Kamp, Sproul Observatory, 1954-55; Mrs. Helen S. Hogg, David Dunlap Observatory, 1955-56; Frank K. Edmondson, Goethe Link Observatory, 1956-57; Geoffrey Keller, formerly of Perkins Observatory, 1957 to present. At the left is Gerard F. Mulders, NSF associate program director for astronomy, formerly with the Office of Naval Research. National Science Foundation photograph.

IN THE CURRENT JOURNALS

APLANATIC CEMENTED DOUBLET DESIGN, by M. G. Dreyfus, R. E. Bishop, and J. E. Moorhead, *Journal* of the Optical Society of America, April, 1960. "The design of a cemented doublet thin lens involves choice of seven independent variables: three radii, two refractive indices, and two reciprocal dispersions. If glass types are arbitrarily selected, then only the three radii remain available as variables for design purposes. The design of a specific lens often requires a specific focal length, achromatic performance, and correction of spherical and comatic aberrations, making a total of four imposed conditions. If we wish to satisfy all four of these requirements we must use one of the four glass constants as a design parameter in addition to the three radii."

LETTERS

Sir:

Comet Schaumasse, with a period of 8.2 years, was the first comet we observed with the Curtis Schmidt telescope at Portage Lake. With that instrument we took both of the accompanying pictures, the left-hand one on February 23, 1952, a 20-minute exposure on 103a-O emulsion. Now the comet is around again, the right-hand photograph being obtained on April 22, 1960, a 30-minute exposure on IIa-O emulsion.

As printed side by side, the two pictures are in all respects comparable, and show differences in the comet's true size. In 1952, the comet was 12 days after perihelion, in 1960 it was five days past. In 1952, it was 0.31 astronomical unit from the earth, this year 1.27, so we have compensated for this by enlarging the 1960 print four times as much as the 1952 picture. On either print one millimeter equals 27,000 kilometers at the comet's distance, and it is readily apparent that the comet this time had not developed as extensive a coma as eight years ago.

FREEMAN D. MILLER
University of Michigan Observatory
Ann Arbor, Mich.



Periodic Comet Schaumasse in 1952 (left) and 1960, enlarged 1¼ and five times, respectively, from plates taken with the University of Michigan's 24-inch Schmidt telescope. The reproduction scale is 27,000 kilometers per millimeter for both pictures. When the 1960 exposure was made, the comet was about magnitude 12.

Sir:

On March 19th, a large planetarium was opened at the Rakurakuen Recreation Ground just outside of Hiroshima, Japan. The 60-foot theatre chamber accommodates about 300 persons.

The planetarium instrument, which was designed by M. Nobuoka, optically projects about 8,000 fixed stars and other objects. An unusual characteristic is that the fixed stars twinkle. The 24 brightest stars are shown separately, to make their images smaller and more intense. Supplementary projectors are used for demonstrating the motion of the sun, moon, and planets, and for special effects such as aurorae, artificial satellites, and variable stars.

The planetarium has a small museum for astronomical photographs and exhibits. Visitors are always welcome.

TAKESHI SATO
Rakurakuen Planetarium
Itsukaichi, Hiroshima, Japan



A typically Japanese skyline decorates the dome of Hiroshima's new Rakurakuen Planetarium. Takeshi Sato is at the controls of the projector, which was manufactured at Osaka by Chiyoda Optical Co.

Sir:

The United States committee for the International Union of the History and Philosophy of the Sciences is participating in a world-wide inventory of scientific instruments of historical importance. Our first step is to determine the present locations of such instruments.

For the purposes of this survey, an instrument of historical importance is defined as one which has been the basis of an important discovery. As chairman of the committee, I would be grateful for suggestions from SKY AND TELESCOPE readers as to specific instruments deserving inclusion in this inventory, and for any details about their present custody.

ROBERT P. MULTHAUF
Department of Science and Technology
U. S. National Museum
Washington 25, D. C.

Sir:

Venus has been in the news for a considerable length of time, but the persons concerned with her have been careful not to jeopardize her classical attributes. Recently, however, ballisticians, electronics engineers, and scientists of the new, unclassical generation have shown an active interest in Venus, and this has resulted in a flurry of writings in which the adjective *Venusian* has made its ugly debut.

I have no objection to the creation of new words, which are often needed to cope with an expanding technology. *Jeep, bazooka,* and even *sputnik* are acceptable words, but *Venusian* jars my classical nerves. By the same derivative process, we would have *Jupiterian, Martian,* and *Uranusian!*

The 1955 *Oxford Universal Dictionary* has the entry: "*Venerean.* 1. connected or associated with, relating or pertaining to Venus or her service. . . ." If one has to use an adjective in connection with Venus, this is it, and *honi soit qui mal y pense.* Those who wish may avoid it entirely by rephrasing the sentence, for example, "the Venus atmosphere" or "the atmosphere of Venus."

LUIGI G. JACCHIA
Smithsonian Astrophysical Observatory
Cambridge 38, Mass.

EDITOR'S NOTE: We agree with Dr. Jacchia's objection to *Venusian.* A suitable substitute, used in astronomical literature for nearly a century, is the adjective *Cytherean,* for which the Merriam-Webster unabridged dictionary gives the meaning "Of or pertaining to the goddess Aphrodite or Venus, or the planet Venus."

The Earth's Shadow Size at the March Lunar Eclipse

JOSEPH ASHBROOK, *Harvard College Observatory*

AMATEUR ASTRONOMERS enthusiastically responded to the request on page 230 of the February SKY AND TELESCOPE for special observations of the March 13, 1960, eclipse of the moon, for the purpose of determining the enlargement of the earth's umbral shadow

Our globe's shadow has two concentric parts. The dark, inner shadow or *umbra* was about 1.4 degrees in diameter, at the moon's distance. Surrounding it was the lighter *penumbra*, 2.5 degrees in diameter. The moon, 0.5 degree in diameter, passed nearly centrally through this pattern, and thus served as a probe whose brightness and color indicated conditions within the shadow.

Everyone who has watched a lunar eclipse attentively has noticed how the darkness of the shadow decreases progressively from its center out to the indefinite penumbral fringe. The eye, however, sees a fairly definite apparent edge to it, whose radius marks the distance from the center where the shadow gradient is steepest.

This apparent radius is always roughly two per cent larger than would be computed from the geometry of the eclipse, if no allowance is made for the earth's atmosphere, which has a profound influence on the shadow. The amount of enlargement is not the same at all eclipses, and may perhaps serve as a geophysical index number, characterizing the state of the earth's atmosphere.

The simplest kind of observation to evaluate this enlargement is recording the times of contacts during an eclipse. Consider, for example, contact I, when the moon begins to enter the umbra, and the lunar disk is externally tangent to the umbra's outline. We can deduce the umbral radius by calculating the angular distance of the moon's center from the shadow center, and subtracting the lunar radius.



How the radius of the earth's umbra is found from crater contact times at an eclipse of the moon.

This kind of analysis has been made for 100 observed times of the four contacts at the March 13th eclipse. In the following summary, for each contact are given the number of timings, the average of the observed times, its mean error in seconds of time, and the enlargement of the umbra, expressed as a percentage excess over the theoretical value.

Contact	*No.*	*UT*	*m.e.*	*Enlargement*
I	26	6:38:29	±07	1.6%
II	39	7:40:25	±05	2.8
III	21	9:15:42	±10	3.3
IV	14	10:17:46	±12	3.0

The enlargement comes out too small for contact I, since timings of that phenomenon tend to be a little late, and similarly observations of IV may tend to be systematically early. Giving half weight to the results from those contacts, and unit weight to contacts II and III, we obtain 2.8 per cent as the average amount of the enlargement of the umbra.

More precise results are given by a second observational method, which consists of noting when particular craters appear to enter or leave the umbra. In all, 203 crater timings are analyzed here. Some discordant observations have been omitted that appear to have been affected by crater misidentifications, errors of record, or overcast sky. Also omitted are a number of incomplete or indefinite observations.

The manner in which the umbra's radius was found from each timing is indicated by the accompanying diagram. The location of the moon's center with respect to the shadow center can be calculated for the time of observation. Next, the position of the crater relative to the moon's center is known, proper allowance being made for libration. Finally, these data give the crater's distance from the shadow midpoint, which is the observed umbral radius, r_o.

In the actual calculations, I used the formulas published by the Russian astronomer S. Kosik in 1940. These take account of the ellipticity of the earth, which affects the shadow's shape. The first step in all the reductions was to convert the observed Universal times to Ephemeris times, by adding 35 seconds.

The accompanying table reports 203 crater timings. Each Universal time is followed by the deduced value of r_o, expressed as a fraction of the equatorial radius of the earth. The last column gives the difference $(r_o - r_c)$ between the observed and computed radii of the umbra.

The average of all these $(r_o - r_c)$ values is $+0.0194 \pm 0.0004$ earth radius. Dividing this by r_c, we find that the enlargement of the umbra was 2.71 ± 0.06 per cent at this eclipse. This agrees well with the 2.8 per cent from the timings of the four contacts.

Evidently the March, 1960, eclipse had a more marked umbral enlargement than did some other recent ones. On November 17-18, 1956, the value was 2.15 per cent, from 42 crater timings reported to SKY AND TELESCOPE (see page 196, Febru-

At Chicago, Illinois, on March 13th, the totally eclipsed moon was photographed by F. K. Leisch with a 3½-inch Questar telescope. He used a 1-inch eyepiece, Praktica camera, and Tri-X film, each exposure two minutes long. At the left, the moon is shown at 8:35 Universal time (just after midtotality), while third contact, at 9:16, is at the right. The moon is still within the umbra, but very bright along its southeastern edge.

ary, 1957). Also, Czech observers found only 1.8 per cent for the May 13-14, 1957, eclipse (March, 1959, issue, page 269).

The next opportunity for amateurs in the United States to make similar observations will be during the September 5, 1960, total lunar eclipse, which takes place before and during dawn on the morning of Labor Day.

ENTRANCE INTO UMBRA

Crater	*Obs'r.*	*UT*	*Observed Rad. (r_o)*	*Diff. ($r_o - r_c$)*
Riccioli	Sn	6:42.2	0.735	+0.018
Grimaldi	Jo	6:43.3	.751	.035
Riccioli	Lu	6:43.7	.722	.005
Grimaldi	Gr	6:44.0	.745	.029
Grimaldi	Hu	6:44.0	.745	.029
Grimaldi	Sn	6:44.2	.743	.027
Grimaldi	Bt	6:44.2	.743	.027
Grimaldi	Fr	6:44.2	.743	.027
Grimaldi	No	6:44.2	.743	.027
Reiner	Bw	6:44.8	.736	.019
Herodotus	Hu	6:45.0	.742	.025
Grimaldi	Bn	6:45.1	.734	.018
Grimaldi	Lu	6:45.3	.732	.016
Herodotus	Bt	6:45.5	.738	.021
Herodotus	Gr	6:45.9	.734	.017
Aristarchus	No	6:46.0	.740	.023
Aristarchus	Bu	6:46.2	.739	.022
Aristarchus	Lu	6:46.4	.736	.019
Aristarchus	Kr	6:46.5	.735	.018
Aristarchus	Bt	6:46.8	.733	.016
Aristarchus	Gr	6:46.8	.733	.016
Aristarchus	Bw	6:47.8	.723	.006
Kepler	Fo	6:50.2	.744	.027
Kepler	Hu	6:50.4	.742	.025
Kepler	Lu	6:51.7	.731	.014
Hansteen	Gr	6:51.9	.737	.021
Letronne	Bt	6:53.1	.740	.023
Euler	Bw	6:54.2	.732	.015
Gassendi	Hu	6:56.2	.743	.026
Gassendi	No	6:56.5	.741	.024
Lambert	Bw	6:57.2	.737	.020
Gassendi	Gr	6:57.4	.734	.017
Copernicus	Kr	6:57.7	.750	.033
Gassendi	Bt	6:57.8	.731	.014
Copernicus	Ay	6:58.0	.747	.030
Copernicus	Fo	6:58.2	.745	.028
Copernicus	Hu	6:58.4	.743	.026
Copernicus	Ci	6:58.6	.741	.024
Copernicus	Ba	6:58.7	.740	.023
Copernicus	Is	6:58.7	.740	.023
Copernicus	Bt	6:58.8	.739	.022
Copernicus	Gr	6:59.0	.738	.021
Copernicus	Lu	6:59.0	.738	.021
Copernicus	Ri	6:59.1	.737	.020
Copernicus	Sa	6:59.1	.737	.020
Copernicus	Bw	6:59.2	.736	.019
Copernicus	Bl	6:59.2	.736	.019
Copernicus	Te	6:59.2	.736	.019
Copernicus	Sh	6:59.7	.732	.015
Copernicus	Fi	6:59.9	.730	.013
Copernicus	Bn	7:00.0	.728	.011
Copernicus	Bu	7:00.0	.728	.011
Timocharis	Bt	7:00.8	.735	.018
Timocharis	Bw	7:01.1	.732	.015
Plato	Fo	7:01.2	.740	.023
Plato	Bt	7:01.4	.738	.021
Timocharis	Sh	7:01.5	.728	.011
Plato	Ri	7:01.5	.737	.020
Plato	Cn	7:01.5	.737	.020
Plato	Fr	7:01.5	.737	.020
Plato	Ci	7:01.6	.737	.020
Plato	Ay	7:01.6	.737	.020
Plato	Sa	7:01.6	.737	.020
Plato	Ba	7:01.7	.736	.019
Plato	Gr	7:01.8	.735	.018
Plato	Lu	7:01.9	.734	.017
Plato	Te	7:01.9	.734	.017
Plato	Cu	7:02.0	.733	.016
Plato	Is	7:02.1	.732	.015
Plato	De	7:02.2	.731	.014
Plato	Hu	7:02.3	.731	.014
Plato	No	7:02.7	.727	.010
Plato	Bw	7:02.7	.727	.010
Plato	Bu	7:02.8	.726	.009
Plato	Bn	7:02.9	.725	.008
Plato	Fi	7:03.1	.724	.007
Schickard	Hu	7:04.1	.736	.019
Archimedes	Bt	7:04.1	.741	.024
Archimedes	Lu	7:04.2	.740	.023
Schickard	Bt	7:05.0	.731	.014
Autolycus	Gr	7:06.6	.740	.024
Aristoteles	Hu	7:10.4	.737	.020
Linné	Cn	7:10.8	.744	.027
Eudoxus	Hu	7:11.0	.746	.029
Schiller	Hu	7:11.4	.740	.023
Pitatus	Gr	7:12.0	.733	.016
Alphonsus	Hu	7:12.1	.738	.021
Pitatus	Lu	7:12.3	.730	.013
Pitatus	Bw	7:12.8	.726	.009
Menelaus	Sn	7:15.4	.740	.023
Menelaus	Sg	7:15.4	.740	.023
Menelaus	Kr	7:15.5	.739	.022
Tycho	No	7:15.9	.745	.028
Tycho	Sg	7:15.9	.745	.028
Tycho	Hu	7:16.7	.738	.021
Tycho	Ri	7:16.8	.737	.020
Tycho	Sa	7:16.8	.737	.020
Tycho	Fo	7:16.9	.736	.019
Tycho	Cm	7:16.9	.736	.019
Tycho	Is	7:17.0	.736	.019
Tycho	Ay	7:17.0	.736	.019
Tycho	Ba	7:17.1	.735	.018
Tycho	Fr	7:17.3	.734	.017
Tycho	Cu	7:17.3	.734	.017
Atlas	Cn	7:17.4	.752	.035
Tycho	Gr	7:17.4	.733	.016
Tycho	Te	7:17.6	.732	.015
Tycho	Le	7:17.6	.732	.015
Tycho	Ci	7:17.6	.732	.015
Tycho	Bt	7:17.6	.732	.015
Tycho	Lu	7:17.6	.732	.015
Tycho	Fi	7:17.8	.730	.013
Tycho	Bw	7:17.8	.730	.013
Tycho	Cs	7:17.8	.730	.013
Tycho	Bl	7:17.8	.730	.013
Posidonius	Lu	7:19.9	.741	.024
Maginus	Hu	7:20.6	.737	.020
Macrobius	Bw	7:24.8	.752	.035
Macrobius	Hu	7:25.2	.750	.033
Proclus	No	7:27.2	.747	.030
Cleomedes	Hu	7:27.8	.734	.017
Fracastorius	Bw	7:29.5	.738	.021
Fracastorius	Hu	7:29.8	.736	.019
Gutenberg	Lu	7:31.2	.733	.016
Gutenberg	Hu	7:32.5	.722	.005
Goclenius	Gr	7:32.7	.744	.027
Langrenus	Gr	7:36.1	.751	.034
Langrenus	Hu	7:36.4	.749	.032
Furnerius	Ha	7:36.8	.748	.031
Wrottesley	Ha	7:36.9	0.737	+0.020

EXIT FROM UMBRA

Crater	*Obs'r.*	*UT*	*Observed Rad. (r_o)*	*Diff. ($r_o - r_c$)*
Riccioli	Gr	9:17.6	0.743	+0.027
Riccioli	Lu	9:18.1	.747	.031
Grimaldi	St	9:18.3	.723	.006
Grimaldi	Cl	9:18.5	.724	.007
Grimaldi	Jo	9:18.5	.724	.007
Grimaldi	Gr	9:18.8	.729	.012
Grimaldi	Lu	9:18.8	.729	.012
Grimaldi	Bt	9:18.9	.729	.012
Schickard	Bt	9:23.3	.735	.020
Billy	Ha	9:24.2	.735	.019
Mersenius	Bt	9:25.0	.744	.028
Gassendi	Lu	9:26.7	.726	.010
Gassendi	Bt	9:28.0	.736	.020
Gassendi	Ha	9:28.2	.738	.022
Aristarchus	Kr	9:28.3	.731	.016
Gassendi	Gr	9:28.4	.740	.024
Aristarchus	No	9:28.4	.732	.017
Aristarchus	Ha	9:28.5	.733	.018
Aristarchus	Gr	9:28.7	.734	.019
Aristarchus	Bt	9:28.9	.736	.021
Aristarchus	Lu	9:29.6	.743	.028
Kepler	Ha	9:30.7	.734	.017
Kepler	Cl	9:30.8	.734	.017
Kepler	Bt	9:31.2	.738	.021
Kepler	Gr	9:31.2	.738	.021
Kepler	Lu	9:31.4	.739	.022
Bullialdus	Ha	9:36.2	.735	.018
Tycho	Cl	9:38.4	.729	.013
Tycho	Fr	9:38.4	.729	.013
Tycho	Lu	9:38.4	.729	.013
Tycho	No	9:38.5	.731	.015
Tycho	Bt	9:38.7	.732	.016
Tycho	Ha	9:38.8	.734	.018
Tycho	Gr	9:39.1	.736	.020
Tycho	Ri	9:39.2	.736	.020
Tycho	De	9:39.2	.736	.020
Pitatus	Bt	9:39.5	.735	.019
Copernicus	Lu	9:39.8	.735	.019
Copernicus	Bt	9:39.9	.736	.020
Copernicus	Ha	9:39.9	.736	.020
Copernicus	Te	9:40.1	.737	.021
Copernicus	Ri	9:40.4	.739	.023
Copernicus	Gr	9:40.5	.740	.024
Tycho	Fi	9:40.5	.745	.029
Straight Range	Bt	9:41.9	.737	.021
Timocharis	Ha	9:43.8	.732	.017
Eratosthenes	Lu	9:43.9	.732	.017
Timocharis	Bt	9:44.2	.737	.022
Eratosthenes	Ha	9:44.5	.735	.020
Plato	Ri	9:45.0	.734	.017
Plato	No	9:45.1	.735	.018
Plato	Ha	9:45.1	.735	.018
Plato	Cn	9:45.1	.735	.018
Plato	Bt	9:45.2	.735	.018
Plato	De	9:45.2	.735	.018
Plato	Lu	9:45.3	.737	.020
Plato	Te	9:45.4	.738	.021
Plato	Gr	9:45.7	.740	.023
Plato	Cu	9:46.4	.746	.029
Alphonsus	Ha	9:47.2	.736	.020
Archimedes	Bt	9:48.6	.726	.009
Aristillus	Bt	9:50.6	.738	.021
Aristillus	Gr	9:50.8	.740	.023
Cassini	Bt	9:51.6	.740	.023
Manilius	Ha	9:55.0	.732	.015
Linné	Ha	9:55.5	.738	.021
Manilius	Lu	9:56.2	.743	.026
Menelaus	Bt	9:58.4	.738	.021
Menelaus	Kr	9:58.5	.738	.021
Plinius	Bt	10:01.1	.728	.011
Plinius	Gr	10:02.4	.739	.022
Posidonius	Bt	10:02.5	.738	.021
Proclus	No	10:10.8	.736	.019
Proclus	Bt	10:10.8	0.736	+0.019

KEY TO OBSERVERS

Ay, H. Ayala Rodriguez, 6-inch reflector, Ciudad Juarez, Mexico; *Ba,* R. Barnes, 6-inch reflector, Trinidad, W. I.; *Bl,* J. Blair, 18½-inch refractor, 200x, Evanston, Ill.; *Bn,* H. Bondy, 3½-inch reflector, 60x, Flushing, N. Y.; *Bt,* E. Both, 8-inch refractor, 40x, Buffalo, N. Y.; *Bu,* A. Burek, 3-inch refractor, Hempstead, N. Y.; *Bw,* J. Brownridge, 3-inch refractor, 12x, Jackson, Miss.

Ci, R. Citron, 5-inch refractor, Jupiter, Fla.; *Cl,* W. Coleman, 4½-inch reflector, 40x, Phoenix, Ariz.; *Cm,* Mrs. W. Cameron, 3½-inch catadioptric, 80x and 160x, Adel-

phi, Md.; *Cn*, R. Conklin and F. Clark, 6-inch reflector, 60x, Richmond, Va.; *Cs*, Case Astr. Soc., Cleveland, Ohio; *Cu*, F. Cushing, 6-inch reflector, Richmond, B. C.; *De*, C. Dean, 4¼-inch reflector, Narberth, Pa.; *Fi*, J. Fitzpatrick and K. Savage, 3½-inch reflector, 60x and 125x, New York, N. Y.; *Fo*, G. Foley, 6-inch reflector, Philadelphia, Pa.; *Fr*, M. Francis and others, 6-inch reflector, 40x, and 4-inch reflector, 60x, Bellwood, Ill.

Gr, H. Grams, 4-inch reflector, 50x, Gillette, Wyo.; *Ha*, W. Hartmann, 6-inch refractor, 90x, State College, Pa.; *Hu*, Hudson County Astr. League, 5 telescopes, Union City, N. J.; *Is*, C. Isbell, 3½-inch reflector, 60x, El Paso, Tex.; *Jo*, E. Jones and G. Vetrovec, 4-inch reflector, 47x, Sandston, Va.; *Kr*, J. Krebs, 6-inch reflector, 40x, Washington, D. C.; *Le*, E. Lerner, 7 × 50 binoculars, Pikesville, Md.; *Lu*, H. Luft, 2-inch refractor, 48x, Oakland Gardens, N. Y.

No, E. Nordeen, 8-inch reflector, 85x and 52x, St. Paul, Minn.; *Ri*, Richmond Ass'n. of Jr. Astronomers, 8-inch reflector, Richmond, Va.; *Sa*, Sangamon Astr. Soc., several telescopes, Springfield, Ill.; *Sg*, Star Gazers Club, several telescopes, Northfield, Minn.; *Sh*, J. Shannon, Kittanning, Pa.; *Sn*, J. Sunshine, 4-inch reflector, 65x, University Heights, Ohio; *St*, J. Sutcliffe, 20 × 65 binoculars, San Jose, Costa Rica; *Te*, Terre Haute Astr. Soc. and Moonwatch Team, Terre Haute, Ind.

SMALL PLANETARIUM IN ARIZONA

After reading David DeBruyn's description of his basement planetarium in this department last November, I decided to develop a similar project. I also punched holes in a small Spitz, Jr., planetarium instrument to project the fainter stars of the constellations and Milky Way. A commercial opaque projector was purchased for special effects.

At first I planned to house the setup in my basement, but I decided to put it in an old grain shed on our farm. This has worked out very well.

Shows are changed monthly, and anyone in the area is welcome to visit.

GILFORD C. BISJAK, JR.
P. O. Box 121
Chino Valley, Ariz.

THIS MONTH'S PROGRAMS

Washington, D. C.: National Capital Astronomers, 8:15 p.m., Commerce Department auditorium. June 4, Dr. G. F. W. Mulders, National Science Foundation, "Optical Phenomena in the Earth's Atmosphere."

STEUBENVILLE, OHIO

The Ohio Valley Amateur Astronomers has eight members. Its president is Fred A. Donaldson, P. O. Box 270, Steubenville, Ohio.

GLEN BURNIE, MARYLAND

Nineteen amateurs have formed the Chesapeake Astronomical Society. Further information is available from Mike Meyerhoff, 1045 Thomas Rd., Glen Burnie, Md.

Amateur Astronomers

Northeast Region Holds New York City Convention

NINETY-ONE amateurs from 11 societies attended the Northeast regional meeting of the Astronomical League at New York City on April 30th and May 1st. The Junior Astronomy Club was the host.

Dr. Robert I. Wolff, professor of astronomy at the City College of New York, spoke on frontiers in astronomy, at the convention banquet in the Hotel New Yorker. He discussed the possibility that studies of the neutrinos that come from the sun may give us information on the processes going on deep in its interior.

Included in the meeting was a trip to the American Museum-Hayden Planetarium for a showing with the new Zeiss projector.

Officers for the coming year are Mrs. Helen Velardi, New Haven, Connecticut, chairman; Edgar Everhart, Mansfield Center, Connecticut, vice-chairman; John Welch, W. Springfield, Massachusetts, treasurer; and Walter Whyman, Batavia, New York, secretary.

Ralph Dakin announced plans for the regional meeting at Rochester, New York, in May, 1961, which will include a visit to Bausch and Lomb Optical Co. to witness a pouring of optical glass.

NORTHWEST CONVENTION DATE CHANGED

The Northwest Region of the Astronomical League will meet at the University of Oregon in Eugene on July 30-31, instead of the beginning of the month, as originally announced. The registration fee of $1.00 per individual or $1.75 for a family may be sent to M. McDerman, 3625 Willamette St., Eugene, Ore., from whom housing information is obtainable.

AAVSO SPRING MEETING

The 49th spring meeting of the American Association of Variable Star Observers is scheduled at the American Museum-Hayden Planetarium in New York City, May 27-30.

Old Battleship Is Source for an Observatory Dome

A LARGE sheet-metal dome that sheltered a pair of antiaircraft guns aboard the mothballed battleship U. S. S. *Colorado* will be used for an observatory to be constructed at Camp William G. Long in Seattle, Washington.

Seventeen feet in diameter and weighing about 1,900 pounds, the dome was purchased for $50 from the salvage company that is scrapping the ship. Robert N. Walton, camp director, estimates its conversion cost as about $300. It will be equipped with a slit and is to rotate on steel wheels on a circular track, the sides of the cement-block building to be 10 feet high.

The entire observatory project will cost around $2,000, with all of the money and parts donated by interested business firms. Members of the Seattle Amateur Astronomical Society have offered to build a 12½-inch Cassegrainian telescope, fitted with a Polaroid-type camera.

The observatory will be operated primarily for children by the Seattle park department. Camp Long is located on a 70-acre tract within the city limits. About 24,000 youngsters visit it each year.

Robert N. Walton supervises moving of the dome. Seattle "Times" photograph.

ASTRONOMICAL LEAGUE 1960 CONVENTION PLANS

REGISTRATION is now open for the general convention of the Astronomical League at Haverford College, outside Philadelphia, Pennsylvania, over Labor Day weekend, September 3-5, 1960. Until August 15th, the fee is $1.00 per person; $1.50 after that date.

Housing will be available in the college dormitories for $5.00 a night per individual, each room accommodating two persons. There will be separate floors for men and women. Registration fees and room reservations should be sent to General Convention Astronomical League, c/o Franklin Institute, Philadelphia 3, Pa.

Amateurs desiring program time are requested to submit outlines of their proposed talks to the following:

Junior session — Tim Wyngaard, 5202 Hammersley Rd., Madison, Wis.

General session — James H. Conklin, East Ave., Mullica Hill, N. J.

Association of Lunar and Planetary Observers session — Walter Haas, Pan American College Observatory, Edinburg, Tex.

Instrument session — George Keene, 100 Southern Parkway, Rochester 18, N. Y.

STELLAFANE MEETING

The 1960 Stellafane convention of amateur telescope makers is scheduled for Saturday, July 30th, on Breezy Hill in Springfield, Vermont. The meeting is being cosponsored by the Springfield Telescope Makers and the Amateur Telescope Makers of Boston.

Informal talks and a panel discussion will take place from 2 to 4 p.m. G. C. Camilli, Pittsfield, Massachusetts, will relate his experiences with two types of observatory buildings; Dr. Henry E. Paul, Norwich, New York, will talk on astrophotography for the amateur; and Ralph K. Dakin, Pittsford, New York, will discuss the correct alignment of Newtonian reflecting telescopes.

The evening program, from 7 to 9 o'clock, is to include northern Milky Way photographs by Edgar Everhart, Mansfield Center, Connecticut; a movie on solar research by Walter Semerau, Kenmore, New York; slides showing differences in star colors by William G. Cleaver, Mt. Carmel, Connecticut; Stellafane lore by John C. Pierce, Springfield, Vermont.

In addition to the usual awards for good telescope design and operation, a prize will be given the oldest instrument exhibited and another to the best-performing telescope over 15 years old.

Overnight camping is allowed in a nearby pasture. Hotel and room reservations may be made with E. Merryfield, Hartness House, Springfield, Vt. Further information about the meeting may be obtained from James W. Gagan, c/o Charles Hayden Planetarium, Museum of Science, Boston 14, Mass.



Carl P. Richards, always an enthusiastic conference delegate, as he appeared at the 1955 Seattle convention, where he received the Astronomical League award for his amateur work.

CARL P. RICHARDS DIES

One of the founders of the Astronomical League, Carl Price Richards, of Salem, Oregon, passed away on April 27th. He was 78 years of age. He received the league's annual award in 1955 for his leadership and accomplishments in the amateur astronomy field.

At the convention in Philadelphia in 1947, Mr. Richards was elected the first treasurer of the Astronomical League, and he later became vice-president. He was active in the development of the Northwest region, and a member of both amateur groups in Portland, Oregon.

The Salem amateur took pride in calling himself an "armchair astronomer," because he did most of his astronomical work with books and atlases instead of at the telescope. But he went on several expeditions to observe total solar eclipses, and was active in lecturing and demonstrating devices to amateur groups.

Geology was among his spare-time activities, and he was an enthusiastic mountain climber. Until his retirement about five years ago, Mr. Richards was a civil engineer with the Oregon state highway commission.

SOUTHWEST CONVENTION

The Children's Museum in Ft. Worth, Texas, will be the site of the Southwest regional meeting of the Astronomical League, on June 10th and 11th. Four groups are hosts: Ft. Worth Astronomical Society, Junior Astronomy Club of the Children's Museum, Texas Astronomical Society, and Astronomical Section of the Convair Recreation Society.

Registration begins at 3 p.m. Friday; the fee is $1.00 for adults, 50 cents for juniors. The chairman is Dr. H. C. Sehested, 3223 Westcliff Rd. W., Ft. Worth, Tex.

+++ AMATEUR BRIEFS +++

How good are you at unscrambling? The following astronomical terms are from the *Stellar Journal* of the Louisville (Kentucky) Junior Astronomical Society: LOGLA, OI, AREHT, RESCE, ALNU, ISNOJUR. (Answers are below.)

The Eastbay Astronomical Society of Oakland, California, apparently has enough doctors, lawyers, and Indian chiefs. It recently polled its membership to find out how many are in the "insurance game." What was the final count?

Case Institute of Technology in Cleveland, Ohio, will offer, for the first time, courses leading to a bachelor's degree in astronomy, starting this fall. Effective July 1st, Western Reserve University students will also be able to take Case astronomy courses, under a co-operative arrangement between the two institutions.

From the Grumman Astronomical Society's *Astro-Gas*: "The young son of a Cape Canaveral missile engineer was attending his first day at kindergarten. When the teacher announced that they were going to learn to count, the boy said proudly that he already knew how and proceeded to demonstrate: '10-9-8-7-6-5-4-3-2-1 — Nuts!' "

It's never too late. William Cleaver, a retired banker, has been named a research assistant at Yale University Observatory. He's an active member of the Astronomical Society of New Haven, Connecticut.

"Anyone who can see can be an amateur astronomer" is the inviting slogan printed each month in the Yakima (Washington) Amateur Astronomers' *Observer*.

The relative merits of solar and sidereal clock drives for a telescope are considered in the April bulletin of the San Francisco (California) Amateur Astronomers. "A drive running at the solar rate will handle [visual] observations very nicely, and the cost of construction is considerably less. . . . If your interest is long-exposure photography, then it may well be worth the extra effort and cost to install a sidereal drive as it will make for less hand-guiding."

Twelve beautiful drawings of Messier objects are featured in the spring issue of *'Scope*, published by the Observation and Study Group of the Toronto Centre, Royal Astronomical Society of Canada. The striking sketches are part of a Messier catalogue the club is compiling.

On April 30th, Jack Borde, Dave Steinmetz, and Jerry Fritcke, of the Mt. Diablo (California) Astronomical Society spent the entire night observing artificial satellites and set some sort of a record for Moonwatching. By dawn, the trio had seen six different satellites, 12 different passes, and recorded 30 positions! The satellites observed were 1960β1, 1960β2, 1959$\eta_1$2, 1959α2, 1959t1, and 1960γ2.

Quiz answers: Algol, Io, Earth, Ceres, Luna, Juniors.

H. M. C.

Elizabeth Roemer took this photograph of Comet Burnham 1959k on April 25, 1960, near the time of its closest approach to the earth, at a distance of about 20,000,000 miles. The comet was then of the 4th magnitude, slightly fainter than early predictions had suggested. This is a 15-minute exposure with the 40-inch reflector of the U. S. Naval Observatory's Arizona station, near Flagstaff. A fast blue-sensitive emulsion was used, Eastman 103a-O. On this enlargement, each millimeter corresponds to 9½ seconds of arc. The comet was in Cygnus, traveling northward at about one-third of a degree per hour. To obtain an unblurred image, Dr. Roemer guided the telescope on the comet, letting the stars trail during the exposure, the trail lengths indicating the amount of the comet's motion. Note the delicate columnar structure of the tail, which was surprisingly faint for a comet of this brightness. Official U. S. Navy photograph.

OBSERVER'S PAGE

Universal time (UT) is used unless otherwise noted.

News of Comet 1959k

THE very faint moving patch of nebulosity discovered by Robert Burnham, Jr., at Lowell Observatory last December 30th has become the brightest comet in several years. Nearest to the sun on March 20, 1960, Comet Burnham on its outward course passed close to the earth in April, providing a fine sight in the northern sky for binoculars and small telescopes.

The long, faint tail of Burnham's comet could be traced to a length of 7.4 degrees on the original of this photograph by Alan McClure, Los Angeles, California, on April 22nd, from 11:00 to 11:20 Universal time. His camera with a Zeiss 5½-inch lens, f/5.0, was set up on Mt. Pinos, 8,300 feet above sea level.

As told in an earlier article (page 292 of the March issue) the comet was nearly in line with the sun in March, and was for a time unobservable in the solar glare. One of the earliest recoveries was by the New Zealand amateur A. F. Jones, at Timaru. On March 26th he saw it as magnitude 6.6, and by April 8th the comet had brightened to 6.0. On two dates during that interval, he recorded the visible tail as 10 minutes of arc long.

One of the most intensive observing series by an American amateur was that of Alan McClure, Los Angeles, California. From his visual examination of the comet on April 7th and 8th in 12×70 binoculars, he found it of magnitude 6.2, resembling a small unresolved globular cluster, and without a tail. On the morning of the 8th, he obtained a 17-minute photographic exposure in blue light with a 7-inch f/7.0 Fecker lens. This showed a very faint tail about 3° long.

At that time the comet was in Aquarius, and beginning to move rapidly northward across the morning sky. Full moon came on the 11th, so for some time bright nights interrupted watch on the comet. A photograph taken April 17th, by Elizabeth Roemer with the U. S. Naval Observatory's 40-inch reflector in Arizona, showed much delicate fibrous structure in the tail, even though her 10-minute exposure was badly fogged by moonlight and haze.

According to Dr. Roemer's estimates of the magnitude of the comet, as seen extrafocally in binoculars, it was brightening steadily. She reports the following values: April 4, 7.3; 17, 5.9 or 6.0; 21, 4.5; and 25, 4.3 or 4.4. On that last date, she saw the head of the comet as a well-condensed coma about 15 minutes of arc in diameter, but without any starlike nucleus.

The striking peculiarity of Comet 1959k during most of April was the unusual faintness of its tail, which was much less conspicuous than for most other comets that become so bright. Late in the month, however, the tail was becoming more apparent.

The properties of the tail were well shown in a photograph made the morning of April 26th at Organ Pass, New Mexico, by John Priser, who took a 60-second exposure with the f/1 Baker-Nunn camera

Optron Solar Filters

The OPTRON SOLAR FILTER is a **precision-polished, optical-quality** glass window, mirrored on one surface to reflect most of the sun's abundant light before it gets into your telescope and can harm any of the optical elements, including of course, your eye.

With an OPTRON SOLAR FILTER you can look at the sun directly through the eyepiece — observe and photograph its changing features (sunspots, granulations, rotation) — safely, comfortably, and with the full resolving power of the filter aperture.

Permanently mounted in an attractive anodized aluminum cell with a flange for easy attachment to your own telescope adapter or to one which we can supply. Four sizes are available from stock — 2½-, 3-, 4-, and 6-inch apertures.

Low priced, yet manufactured to a precision matching high-grade astronomical reflectors and refractors. An OPTRON SOLAR FILTER lets you observe the most important member of the solar system, and enjoy the use of your telescope more than ever before — in the daytime.

2½", $13.50; 3", $21.50; 4", $32.50

Send for free literature.

OPTRON LABORATORY

Box 25, D.V. Station, Dayton 6, Ohio



in the long run

Quality costs no more

and *Excellence* is

our *Standard*

★ **Instruments**
★ **Optics**
★ **Accessories**

Address inquiries to

TF OPTICAL LAB

P. O. Box 481, Huntington Beach, Calif.

of the Smithsonian Observatory's satellite tracking station. The tail was fully 6° in extent on the original negative, forming a faint, very narrow fan. About two diameters of the coma outward along the tail, there were several slight kinks.

By the end of April, Comet Burnham was a northern circumpolar object, hence observable all night, and many amateurs took it under watch. W. E. Iversen, Stamford, Connecticut, noted it as plainly visible in binoculars, near the head of Draco, on April 28th. Its motion was detectable during his three-hour scrutiny. This was the fifth night on which he had viewed the comet. According to Mr. McClure, the magnitude was 4.8 on that date, and the object had less tail than previously.

Also on April 28th, Edgar Everhart, Mansfield Center, Connecticut, obtained a 25-minute exposure with a Petzval lens of 20-inch focus, used with a field flattener. His picture showed a very narrow straight tail about 4° long.

The following night, Comet Burnham was accidentally picked up by Bruce Gelin, Wilmington, Delaware, as he was scanning the vicinity of Zeta Ursae Minoris with his 2.4-inch refractor. At the time he did not know the identity of the "strange fuzzy object."

At Philadelphia, Pennsylvania, G. M. Foley took successful photographs on April 30th with a Biotar 58-mm. f/2 lens on 35-mm. Plus-X film. An exposure of 30 seconds gave strong images.

The latest available information about Comet Burnham is from observations by Dr. Roemer on May 1st. A 20-minute exposure with the 40-inch reflector showed that the tail was very much fainter, and only 40′ long. The visual magnitude was 5.4, representing a marked fading since April 29th.

D. Meisel, who is director of the comets section of the Association of Lunar and Planetary Observers, is collecting amateur reports of this comet for a comprehensive discussion. He mentions that the maximum observed extent of the tail was on April 22nd, when it amounted to 7°.4 on a negative taken by Mr. McClure (see picture on page 479). Observing reports for Mr. Meisel should be sent to him at 800 Eighth St., Fairmont, W. Va.

The spectacular show presented by Comet Burnham 1959k is now over, and it is fading very rapidly as its distances from the earth and the sun are increasing. No ephemeris later than that on page 292 of the March issue is available; it extends to May 26th, when the comet was to be an inconspicuous telescopic object in the constellation Leo Minor.

DRAWING THE MOON AND PLANETS

Many helpful hints for the amateur who wishes to make pencil drawings of lunar or planetary surface features are given by William K. Hartmann in the January-February issue of the *Strolling Astronomer*.

In sketching a lunar crater, for example, Mr. Hartmann recommends first inserting the major features from observation with relatively low magnifications. Smudging is useful for obtaining uniform shadings. The subject is then viewed with higher powers, and smaller details are added until the observer is satisfied that all that can be certainly seen has been included.

Every drawing should be accompanied by descriptive notes to aid its interpretation. For the beginner, copying lunar photographs helps develop drawing techniques, and sketching the naked-eye appearance of the moon is useful practice for planetary observers.

The issue in which Mr. Hartmann's article appeared can be obtained at 70 cents per copy from its editor, Walter H. Haas, Pan American College Observatory, Edinburg, Tex.

SUNSPOT NUMBERS

The following American sunspot numbers for March have been derived by Dr. Sarah J. Hill, Whitin Observatory, Wellesley College, from AAVSO Solar Division observations.

March 1, 66; **2**, 63; **3**, 57; **4**, 81; **5**, 87; **6**, 83; **7**, 103; **8**, 119; **9**, 107; **10**, 92; **11**, 94; **12**, 65; **13**, 57; **14**, 66; **15**, 82; **16**, 88; **17**, 92; **18**, 94; **19**, 93; **20**, 103; **21**, 100; **22**, 133; **23**, 121; **24**, 119; **25**, 128; **26**, 53; **27**, 88; **28**, 118; **29**, 115; **30**, 121; **31**, 97. Mean for March, 93.0.

Below are provisional mean relative sunspot numbers for April by Dr. M. Waldmeier, director of Zurich Observatory, from observations there and at its stations at Locarno and Arosa.

April 1, 140; **2**, 143; **3**, 152; **4**, 162; **5**, 156; **6**, 143; **7**, 123; **8**, 112; **9**, 98; **10**, 103; **11**, 107; **12**, 136; **13**, 128; **14**, 133; **15**, 162; **16**, 159; **17**, 110; **18**, 116; **19**, 128; **20**, 116; **21**, 123; **22**, 108; **23**, 99; **24**, 96; **25**, 95; **26**, 96; **27**, 86; **28**, 99; **29**, 82; **30**, 100. Mean for April, 120.4.

Precision Diagonals

You will get the best possible performance from your telescope with one of our clear **fused quartz** diagonals. Accuracy guaranteed 1/20 wave.

Ellipse 1.25" x 1.77" . . $12.00
Ellipse 1.5" x 2.12" . . $15.00

Pyrex diagonals, 1/8-wave accuracy.

Ellipse 1.25" x 1.77" . . $ 6.00
Ellipse 1.5" x 2.12" . . $ 9.00

Without aluminum coating, deduct $1.00.

Send for our complete list of supplies, quartz mirrors, blanks, oculars, coatings, and accessories.

E & W OPTICAL CO.
2406 E. Hennepin Ave.
Minneapolis 13, Minn.

Magnusson Telescopes and Accessories

★ Mountings as low as $29.00 and $59.00.
★ Low-priced clock drives and other accessories.

Parts are sold separately. Write for prices.

SETTING CIRCLES

Made of choice aluminum or brass, machined and polished all over. Hour circles, machine-scribed with hour, half-hour, and five-minute marks. Declination circles scribed in degrees 0-90-0-90. Numbers stamped with 1/8" dies. Holes reamed standard sizes. State sizes.

	Aluminum	Brass
5" circles, set of two	$15.00	$19.50
6" circles, set of two	$17.00	$22.10
8" circles, set of two	$24.00	$31.20

O. MAGNUSSON
14570 West 52nd Ave.
Arvada, Colorado

Read This Advertisement

Here is a combination of a Barlow and a particular ocular which gives outstanding results. It consists of our new Barlow and our 16.3-mm. (⅔" focal length) Erfle eyepiece. While the Barlow was not specifically designed to work with this eyepiece, it does so to an astonishing degree. All images are sharp and hard to the very edge of the field.

The Barlow gives magnification up to slightly over three times that of the ocular alone. It is achromatic, coated, and mounted to the U. S. standard size of 1.250 inches.

The modified Erfle eyepiece has a field of 75 degrees with excellent eye relief. The combination gives an equivalent focal length of slightly under 6 millimeters. Many users state it is far superior to any shorter focal length ocular of equivalent magnification.

The Barlow sells for $16.00 postpaid, and the Erfle for $15.30 postpaid. Both are guaranteed to perform as stated above or money refunded.

ORTHOSCOPIC OCULARS—All hard coated, standard 1¼-inch outside diameter.

28-mm.	$15.60	10.5-mm.	$16.80	4-mm.	$17.70
16.3-mm. (Erfle)	$15.30	7-mm.	$17.70	Barlow 3x	$16.00

Telescopics
6565 Romaine Street
Los Angeles 38, Calif.

Warranted to equal or surpass any oculars obtainable anywhere or money refunded.

Finished mirrors, mirror kits, spiders, elliptical flats, focusing devices, aluminizing.

Send for catalogue.

You'll find these fully professional features in every Custom DYNASCOPE®!

Exquisite optical systems, fully achromatic and corrected to meet the most critical research standards • Massive equatorial mounts that provide exceptional stability and embody the latest mechanical refinements for ease of operation. • Full sets of matched orthoscopic and achromatic eyepieces with wide flat fields sharp to extreme edges. • Needle bearings carefully fitted on substantial shafts to assure movements so fine that they equal the ease and precision of a fine watch. • Lifetime materials throughout, for atmospheric resistance and dimensional stability. • Fully rotating tubes, with counterpoise to provide perfect balance during rotation. • Rotary secondary supports to minimize diffraction. • Exclusive Dyna-mesh rack and pinion focus for smoother, more accurate focusing action. • Two-way pier tripods (Pat. Pending) in 6-inch and 8-inch models. 45-pound pier can be mounted permanently. Portable tripod is instantly removable for field trips. • Highly accurate electric drives, free from backlash, with fully compensating clutch. • 8 x 50 coated achromatic finderscopes with crosshairs and extra-large 6° fields. • 7"-diameter setting circles spoked for easy setting. Graduated with verniers. • Super sensitive slow motion flex line control • Adjustable to all latitudes.

MASTERPIECES

of precision performance!

All sizes of these superb instruments are available for unusually prompt delivery . . . including this Deluxe 12.5-inch model

CUSTOM DYNASCOPES®

in your choice of 6"-8"-10" 12.5"-16" models

Every Custom DYNASCOPE is designed and built to meet such high standards and exacting specifications that it is the overwhelming choice of schools, colleges, universities, and many well-known professional astronomers. Each of these magnificent instruments incorporates features that are years ahead in optical engineering, yet based on time-tested principles. Each is painstakingly produced and assembled by craftsmen who put careful workmanship before speed. Each is required to pass, flawlessly, a long series of rigid performance and operational tests. Nothing is overlooked to make sure that these superb telescopes are the finest in their class, regardless of price. Whichever size you select, we guarantee that it *must* measure up to this standard or your purchase price will be refunded in full. You can order with absolute confidence . . . and with the exciting expectation of new thrills and experiences ahead.

Colorful New Brochure Yours FREE!

Send today for this fascinating new booklet that gives you the full specifications on all Custom Dynascopes, plus helpful information to guide you in the selection of your next telescope. A postcard will bring your copy FREE!

CUSTOM DYNASCOPES—PRICE AND DELIVERY SCHEDULE

CONVENIENT TIME PAYMENT PLANS AVAILABLE ON ALL MODELS

SIX-INCH STANDARD	SIX-INCH DELUXE	EIGHT-INCH STANDARD	EIGHT-INCH DELUXE	10-INCH DELUXE	12.5-INCH DELUXE	16-INCH OBSERVATORY MODEL
$265 Complete	$475 Complete	$385 Complete	$595 Complete	$895 Complete	$1,265 Complete	$4,200 up
Shipping Weight 80 lbs.	Shipping Weight 150 lbs.	Shipping Weight 145 lbs.	Shipping Weight 185 lbs.	Shipping Weight 245 lbs.	Shipping Weight 300 lbs.	Equipped To Your Specifications
21 Day Delivery		21 Day Delivery		30 Day Delivery	30 Day Delivery	

Standard Six and Eight Inch Models Do Not Include Electric Clock Drive, Setting Circles, Slow Motion Control Or Pier
All Telescopes Are Shipped F.O.B. Hartford, Connecticut • No Additional Charge For Packing and Crating

© Copyright 1960 Criterion Mfg. Co.

® TM Registered U.S. Pat. Office

CRITERION MANUFACTURING CO. *Manufacturers of Quality Optical Instruments*
DEPT. D-38, 331 CHURCH ST., HARTFORD 1, CONN.

Sam Houston College's vibration-free Tinsley telescope

Sam Houston State Teachers College, Huntsville, Texas, needed a telescope primarily for visual and photographic instruction of undergraduate astronomy classes. ☐ A custom-made Tinsley telescope was chosen for two simple reasons: 1) there is no more responsive, reliable telescope made; 2) its massive size and rigidity assure crisp, sharp images—in spite of the fact that it is housed in a rooftop observatory on a busy science building. ☐ When the Sam Houston 16" Newtonian-Cassegrain reflector is set properly, it remains accurately set. ☐ Large, pre-loaded tapered cone bearings on both axes provide effortless control of the instrument. It is powerful, too. Total effective focal length is 256 inches. ☐ There is no limit to the photographic research Sam Houston students can perform with this telescope. Its versatile Baker Photographic Corrector permits photography of a seven-degree field. ☐ The Sam Houston telescope—like all custom instruments from Tinsley—was designed to meet the client's special needs. If you are faced with a problem such as rooftop mounting, Tinsley can help you solve it. Please address your inquiries to Department C. Tinsley Laboratories, Inc., 2526 Grove Street, Berkeley, Calif.

TINSLEY
LABORATORIES, INC.

Sky and TELESCOPE

INDEX to Volume XIX

November, 1959, to June, 1960

Titles

Abbé Lacaille's List of Clusters and Nebulae, *Owen Gingerich,* 207

Amateur's Night Out, An, *Mrs. Joseph E. Stevens,* 199

Amateur's Tour of Planetary Nebulae, An, *Leland S. Copeland,* 214; correction, 316

AAAS Astronomy Highlights, *John B. Irwin,* 347

American Astronomers Report—
- Absolute Magnitude of X Monocerotis, 94
- Are Stars Alike in Different Parts of the Universe? 286
- Color-Magnitude Diagram for Visual Binaries, 17
- Coma Berenices Cluster and White Dwarfs, 339
- Companion of Fourth Nearest Star, 469
- Diameters of Lunar Craters, 285
- Distance of the Sun, 16
- Gas Motions in the Central Part of M31, 285
- Intense Solar Flares of July 16, 1959, 339
- Microwave Study of the Moon, 93
- Moon's Distance by Radar, 16
- Older Meteor Streams, 286
- Polarization of Light of Moon and Planets, 17, 94
- Pressure-Induced Nuclear Reactions in Stars, 16
- Primordial Composition of the Solar System, 338
- Proposed Explanation of Martian Phenomena, 469
- Ratio Spectrometer, 18
- Shattered Rocks Beneath Meteorite Craters Compared, 94
- Spectral Surveys Including the Ultraviolet, 285
- Symposium on Subdwarfs, 467
- Unusual Star Cluster Messier 71, 93
- Variable Stars in the Scutum Cloud, 93

April Cover Picture Not an Aurora? 391

Astronomy at Brigham Young University, *D. H. McNamara,* 274

Comet Morehouse 1908 III, *Otto Struve,* 74

Eclipse of the moon of March 13, 1960 (see also under Departments, Observer's Page)—
- Amateur Photographs of the March Lunar Eclipse, 402
- Earth's Shadow Size at the March Lunar Eclipse, The, *Joseph Ashbrook,* 474

Eclipse of the sun of October 2, 1959 (see also under Departments, Observer's Page)—
- Eclipse over New England, 4
- German Amateurs View Eclipse, *Edgar Mädlow,* 219
- Total Eclipse at El Aaiun, *M. Waldmeier,* 82

Fauth, Philipp, and the Moon, *Hermann Fauth,* 21

First Photograph of Moon's Far Side, 72; correction, 156

Foucault Pendulum, A, *Warren I. Fillmore,* 144

Gas and Dust in Globular Clusters, *Otto Struve,* 456

Graphic Time Table of the Heavens—1960, 165, 166-167

Great Aurora of Early September, The, 14

Historic Debate About the Universe, A, *Otto Struve,* 398

How Can We Detect Radio Transmissions from Distant Planetary Systems? *Frank D. Drake,* 140

Instruments at the Leiden Southern Station, 205

Lunar Occultation Observations by Amateurs, 71

McCrea's Theory of the Solar System's Origin, *Otto Struve,* 154

New Astronomical Chronograph, A, *William Mussetter,* 209

New National Observatory Dedicated at Kitt Peak, *Charles A. Federer, Jr.,* 392

New Universal Sundial Design, A, *Hermann H. Egger,* 470

Occultation Supplement — 1960 Predictions for the United States and Canada, 99

Practical Use of Ephemeris Time, The, *G. M. Clemence,* 148

Predicting and Observing Lunar Occultations, *Flora McBain Sadler,* 84

Project Stratoscope Obtains Finest Pictures of the Sun, 79

Radio Astronomy Receivers, *Frank D. Drake,* I, 26; II, 87

Radio Astronomy Study of the Earth's Atmosphere, A, *Jules Aarons,* 406

Reflections of a Spectroscopist, *Otto Struve,* 7

Reminiscences of the Discovery of Pluto, *Clyde W. Tombaugh,* 264

RZ Scuti—A Peculiar Spectroscopic Binary, *Otto Struve,* 276

Simple Replica-Grating Spectroscope, A, *Ernst Keil,* 343

Some New American Radio Telescopes, 3

Some Observations of VV Puppis, *P. T. Oosterhoff* and *A. D. Thackeray,* 337

Structure of Galactic Clusters, The, *Otto Struve,* 329; correction, 505

Theory of the Origin of Lunar Rills, A, *Gilbert Fielder,* 334

Two Eastern Planetariums Re-equipped, 271

Variable Stars in the Orion Nebula, *Leif J. Robinson,* 152

Visual Observations of Meteors, *Otto Struve,* 200

Why Observe Stellar Eclipses? *Alan H. Batten,* 464

Authors

Aarons, Jules, Radio Astronomy Study of the Earth's Atmosphere, A, 406
Acsbock, Joseph L., Casting the Parts of an Aluminum Mounting, 185
Ashbrook, Joseph, Astronomical Scrapbook, 92, 213, 342, 463
book reviews, 369, 370
Earth's Shadow Size at the March Lunar Eclipse, The, 474
In Focus, 151; correction, 280
Observations of the March Lunar Eclipse, 418
Observing Programs for the Lunar Eclipse in March, 227
Batten, Alan H., Why Observe Stellar Eclipses? 464
Bisjak, Gilford C., Jr., Small Planetarium in Arizona, 476
Boilard, Robert C., New England Observatory, A, 160
Bondy, Harry L., letter, 263
Brackbill, M. T., book review, 180
Brichta, Ralph, Milwaukee, Wisconsin, 159
C. A. F., see *Federer, Charles A., Jr.*
Calder, William A., book review, 431
Carter, George D., Jr., Telescope Camera Holder, 56
Clemence, G. M., Practical Use of Ephemeris Time, The, 148
Copeland, Leland S., Amateur's Tour of Planetary Nebulae, An, 214; correction, 316
Corrado, Henry M., Amateur Briefs, 413, 477
Cox, Robert E., Concerning Spherical-Mirror Telescopes, 376
conductor, Gleanings for ATM's, 51, 123, 185, 246, 310, 374, 438, 502
Designing a Finder, 440
Some Advantages of a Transfer Lens, 53
Twyman Effect in Diagonals, The, 186
Cruikshank, Dale P., letter, 327
Dall'Olmo, U., letter, 263
Davis, Morris S., book review, 493
DeBruyn, David, Michigan Amateur's Basement Planetarium, A, 29
Dennington, S. H., letter, 327
de Vaucouleurs, G., book review, 495
Doucet, René, Occultation of Neptune, 41
Drake, Frank D., How Can We Detect Radio Transmissions from Distant Planetary Systems? 140
letter, 263
Radio Astronomy Receivers, I, 26; II, 87
Egger, Hermann H., New Universal Sundial Design, A, 470
Eigsti, W. E., Nebraska Planetarium with an Unusual Entrance, A, 287
Evans, William H., letter, 327
Fauth, Hermann, Fauth, Philipp, and the Moon, 21
Federer, Charles A., Jr., book review, 432
New National Observatory Dedicated at Kitt Peak, 392
Fielder, Gilbert, Theory of the Origin of Lunar Rills, A, 334
Fillmore, Warren I., Foucault Pendulum, A, 144
Fogelquist, Rune, letter, 139
Freeman, Jay, letter, 417
Gingerich, Owen, Abbé Lacaille's List of Clusters and Nebulae, 207
book reviews, 115, 431
Glenn, William H., Meteors, 60, 131, 190, 381, 446
Sun, Moon, and Planets This Month, The, 61, 131, 191, 255, 319, 381, 447, 509
H. M. C., see *Corrado, Henry M.*
Harris, Wallace E., Flat-Roof Observatory, A, 124
Herring, Alika K., Observing the Moon, Bessel, 169; Bürg and Lacus Mortis, 357; Parry and Bonpland, 32
Houston, Walter Scott, Deep-Sky Wonders, 42, 108, 171, 234, 297, 360, 490
Hynek, J. Allen, book review, 175
Irwin, John B., AAAS Astronomy Highlights, 347
book review, 44
J. A., see *Ashbrook, Joseph*
Jacchia, Luigi G., letter, 473
James, Robert V., Simple Mounting Made of Thick-Walled Tubing, A, 188
Johnson, Craig L., Ursid Meteors Observed, 294
Jones, Albert F., Observations of a Nova in Ophiuchus, 35
Keene, George T., book review, 241
Keil, Ernst, Simple Replica-Grating Spectroscope, A, 343
Ketchum, Jesse, Toronto, Canada, 351
Konstanzer, Gordon, Portable 6-inch Catadioptric Telescope, A, 502
Lichtenstein, Pearl R., book review, 366
Lorenz, Ernest, Long Beach, California, 413
Lugo, Delfin J., Amateur in Colombia, An, 413
Mackintosh, Allan, Glass Removal in Parabolizing, 504
Mädlow, Edgar, German Amateurs View Eclipse, 219
Marks, Allan C., Amateur's Observatory Down Under, An, 224
Masson, Kelvin, Proper Location for a Newtonian Diagonal, 126
May, Tommy, Young Amateur's Observatory in Texas, A, 29
Mayall, Mrs. Margaret W., Peculiar Variable Star V Sagittae, The, September, 1959; correction, 98
McDonough, Alexander, Omaha, Nebraska, 287
McNamara, D. H., Astronomy at Brigham Young University, 274
Melin, Marshall, Observing the Satellites, 11, 90 (correction, 284), 157, 222, 283, 346, 409 (correction, 462), 459
Miller, Freeman D., letter, 473
Mohler, Orren C., book review, 301
Multhauf, Robert P., letter, 473
Musselter, William, New Astronomical Chronograph, A, 209
Nieves, Andres, Jr., Juniors in Puerto Rico, 350
Oort, J. H., letter, 417
Oosterhoff, P. T., and *Thackeray, A. D.,* Some Observations of VV Puppis, 337
R. E. C., see *Cox, Robert E.*
Rizzo, P. V., book review, 366
Roberts, Valerie A., film review, 47
Robinson, Leif J., Variable Stars in the Orion Nebula, 152
Roth, Nathan R., Silo-Domed Observatory for a 12½-inch Telescope, A, 374
Rush, J. H., book review, 116
Sadler, Flora McBain, Predicting and Observing Lunar Occultations, 84
Sato, Takeshi, letter, 473
Schultz, Sherman W., Jr., Low-Power Microscope System for High Magnifications, A, 51
Setteducati, Arthur F., Listening to Meteors on Short Wave, 363
Shaw, R. William, book review, 237
Shawcross, William E., book review, 370
Questions from the S+T Mailbag, 24, 94, 165, 220, 286, 345, 408, 466
Shinkle, C. E., Ohio Turnpike Amateurs, 78
Smith, Bradford A., letter, 417
Snowden, Michael S., Memphis Astronomical Society Observatory, The, 438
Stevens, Mrs. Joseph E., Amateur's Night Out, An, 199
Stevenson, Merritt, Ohio Students Build High School Observatory, 159
Stewart, John Q., "Red Tunnel" at a Sunrise Total Solar Eclipse, The, 111
Struve, Otto, Comet Morehouse 1908 III, 74
Gas and Dust in Globular Clusters, 456
Historic Debate About the Universe, A, 398
McCrea's Theory of the Solar System's Origin, 154
Reflections of a Spectroscopist, 7
RZ Scuti — A Peculiar Spectroscopic Binary, 276
Structure of Galactic Clusters, The, 329; correction, 505
Visual Observations of Meteors, 200
Thackeray, A. D., see *Oosterhoff, P. T.*
Tombaugh, Clyde W., Reminiscences of the Discovery of Pluto, 264
Urey, Harold C., letter, 94
Vaughn, Frank, Astronomical Seeing, 37
W. E. S., see *Shawcross, William E.*
W. H. G., see *Glenn, William H.*
Waldmeier, M., Total Eclipse at El Aaiun, 82
Watts, Raymond N., Jr., book review, 494
Wells, James A., All-Purpose Telescope Assembly, An, 186
Wood, Frank Bradshaw, book review, 303
Wylie, Lloyd R., letter, 417
Youdale, Jack, English Catadioptric Telescope, An, 123
Young, Bradley H., 20-inch Reflector Built in Brazil, A, I, 246; II, 310
Zirin, Harold, book review, 176

Departments and Features

Amateur Astronomers —

Albuquerque, New Mexico, 29
Amateur Briefs, 413, 477
Amateur in Colombia, An, 413
Amateur's Observatory Down Under, An, 224
AAVSO Meets at Nahant, 78
AAVSO Spring Meeting, 476
Astronomical League 1960 Convention Plans, 477
Bartlesville, Oklahoma, 29
Brisbane, Australia, 350
Burlington, Iowa, 29
Cleveland, Ohio, 413
Contacting National Organizations, 287
Farmingdale, New York, 224
Georgia Amateur Dies, 287
Glen Burnie, Maryland, 476
Great Lakes Convention, 350
Hampton, Virginia, 224
Humboldt County, California, 29
Huntsville, Alabama, 78
Juniors in New Hampshire, Pennsylvania, and Wisconsin, 351
Juniors in Puerto Rico, 350
Kenosha, Wisconsin, 350
La Habra, California, 350
Lubbock, Texas, 351
Michigan Amateur's Basement Planetarium, A, 29
Milwaukee, Wisconsin, 159
Montreal, Canada, 159
Mt. Vernon, Ohio, 413
Nebraska Planetarium with an Unusual Entrance, A, 287
New Editor of *Reflector*, 351
New England Observatory, A, 160
Noble, Miss C. M., Dies, 159
Northeast Convention, 78, 350; Northeast Region Holds New York City Convention, 476
Northwest Convention, 350; Northwest Convention Date Changed, 476
Ohio Students Build High School Observatory, 159
Ohio Turnpike Amateurs, 78
Old Battleship Is Source for an Observatory Dome, 476
Omaha, Nebraska, 287
Planetarium in New Zealand, 350
Richards, Carl P., Dies, 477
Richland, Washington, 351
Riverside, California, 29
Silver Spring, Maryland, 413
Sioux Falls, South Dakota, 224
Small Planetarium in Arizona, 476
Society Listing, 224
Southeast Convention, 350
Southwest Convention, 477
Stamford, Connecticut, 29
Stellafane Meeting, 477
Steubenville, Ohio, 476
This Month's Programs, 29, 78, 160, 224, 287, 350, 413, 476
Toronto, Canada, 351
Two Clubs in Industry, 350
Two Louisiana Groups, 351
Washington, D. C., 29, 160
Western Amateurs To Meet in San Jose, 160
Young Amateur's Observatory in Texas, A, 29
Yucaipa, California, 287

Astronomical Scrapbook —

Plato Illusion, A, 92
Trapezium in Orion, The, 213
Visual Star Colors and a List of Red Stars, 342
William Herschel and the Sun, 463

Books and the Sky —

Astronomical Photography at the Telescope, Thomas Rackham, 241
Astronomy, Theodore G. Mehlin, 115
Astrophysique Générale, J. C. Pecker and E. Schatzman, 495
Close Binary Systems, Zdenek Kopal, 303
Elementary Astronomy, Otto Struve, Beverly Lynds, and Helen Pillans, 237
Handbuch der Physik, S. Flügge, editor, Vol. 53, Astrophysics IV: Stellar Systems, 44
Individual and the Universe, The, A. C. B. Lovell, 116
Introduction to the Mechanics of the Solar System, Rudolf Kurth, 493
Kepler, Max Caspar, 494
Larousse Encyclopedia of Astronomy, Lucien Rudaux and G. de Vaucouleurs, 431
Our Sun, Donald H. Menzel, 301
Paris Symposium on Radio Astronomy, Ronald N. Bracewell, editor, 175
Planet Venus, The, Patrick Moore, 370
Planetaria and Their Use for Education, Miriam Jagger, editor, 180
Radio Studies of the Universe, R. D. Davies and H. P. Palmer, 366
Rainbow, The, Carl B. Boyer, 369
Sky Observer's Guide, The, Newton Mayall, Margaret Mayall, and Jerome Wyckoff, 366
Sun, The, Karl Kiepenheuer, 176
Transits of Venus, The, Harry Woolf, 431
Unity of the Universe, The, D. W. Sciama, 432

Celestial Calendar —

Configurations of Jupiter's Four Bright Moons, The, 446
Giacobinid Meteor Reports, 131
Jupiter's Satellites, 508
Mercury in the Evening Sky This Month, 508
Meteors, 60, 131, 190, 381, 446
Minima of Algol, 60, 130, 190, 254, 319, 380, 446, 508
Minor Planet Predictions, 60, 190, 254, 319, 381, 447, 509
Moon Phases and Distance, 61, 131, 190, 254, 319, 381, 447, 509
Occultation of Aldebaran, 318
Occultation Predictions, 130
Occultations in January, 190
Occultations of the Hyades and of Aldebaran, 380
Sun, Moon, and Planets This Month, The, 61, 131, 191, 255, 319, 381, 447, 509
Variable Star Maxima, 61, 130, 190, 254, 318, 380, 446, 509
Variable stars: Observable Algol Minima, 60; R Leporis, 130; R Hydrae, 190; Betelgeuse, 254; T Centauri, 318; V Bootis, 380; R Virginis, 446; SZ Herculis, 508

Editors Note, The — Two volumes of SKY AND TELESCOPE per year, 455

Feature pictures —

Kappa Crucis, NGC 4755, 328
Mare Serenitatis region on moon, 150
Nebula surrounding Eta Carinae in southern Milky Way, 206

Films and the Sky —

Story of the Universe, The, Harlan J. Smith, Unit I: The Earth and Its Moons, 47

Front-cover photographs —

Kitt Peak Observatory 36-inch reflector, 389
Leiden 36-inch light collector in South Africa, 197
Moon's other side, 69
New projector in New York, 261
Springfield's Foucault pendulum, 137
Total eclipse and shadow, 1
Unusual aurora in February, 325 (see also April Cover Picture Not an Aurora? 391)
Weather satellite launching, 453

Getting Acquainted with Astronomy —

Planets, The, Mercury, I, 221; II, 275; Venus, I, 416
Techniques of Lunar and Planetary Observing, I, September, 1959; II, 25

Gleanings for ATM's —

All-Purpose Telescope Assembly, An, 186
Casting the Parts of an Aluminum Mounting, 185
Concerning Spherical-Mirror Telescopes, 376
Designing a Finder, 440
English Catadioptric Telescope, An, 123
Flat-Roof Observatory, A, 124
Glass Removal in Parabolizing, 504
"Gleanings" Index, 505
Low-Power Microscope System for High Magnifications, A, 51
Memphis Astronomical Society Observatory, The, 438
Portable 6-inch Catadioptric Telescope, A, 502
Proper Location for a Newtonian Diagonal, 126
Silo-Domed Observatory for a 12½-inch Telescope, A, 374
Simple Mounting Made of Thick-Walled Tubing, A, 188
Some Advantages of a Transfer Lens, 53
Telescope Camera Holder, 56

20-inch Reflector Built in Brazil, A, I, 246; II, 310
Twyman Effect in Diagonals, The, 186

Here and There with Amateurs, 351

In Focus, 151 (correction, 280)

In the Current Journals, 19, 81, 147, 219, 281, 333, 414, 472

Letters, 94, 139, 263, 327, 417, 473

New Books Received, 48, 119, 181, 232, 306, 372, 434, 501

News Notes —

AAS To Meet in Pittsburgh, 332
Anderson, John A., Dies, 218
ASP Meeting in Oregon, 332
Astronomy TV Programs from Philadelphia, 151
Auroral Wall of Light, 81
Big Reflector Planned for Argentina, 333
Catalogue of Dwarf Galaxies, 19
Daytime Auroras, 18
December Meetings, 81
84-inch Mirror Blank Being Ground in Tucson, 218
Ejection of Matter from Red Giant Stars, 333
Fireball of July 26, 1938, 281
Flare-Patrol Photographs, 147
General Magnetic Field of the Sun, 147
Geochemical Table of the Elements, 149
Gum, C. S., Dies, 472
Harvard Appointments, 415
High Solar Prominences, 415
International Astronomical Union 1961 Meeting, 19
Land, Gustav, Dies, 19
Lunar Ray Formation, 146
Mass of Saturn, 472
Medal to E. J. Opik, 463
Meteor Trails Used in Radio Communication, 19
Mitchell, S. A., Passes Away, 333
Molecular Spectra, 415
Moon-Venus Conjunction, 81
NSF Grants for Observatory Development Projects, 212
NSF Tenth Anniversary, 472
New Bright Variable Star, 280
New Director for Dearborn, 81
New German Observatory, 212
New Harvard-Smithsonian Research Building, 282
New Leuschner Director, 151
New Lunar Atlas, 415
New Yerkes-McDonald Director, 463
Nova Herculis 1960, 414
Ohio Appointment, 282
142-foot Radar Telescope for Stanford University, 80
Optical Testing on Stars, 282
Parenago, P. P., Death of, 219
Peculiar Solar Observations Explained, 472
Peculiar Southern Binary, 414
Peculiar Variable Star, 81
Perkins 69-inch Telescope To Be Moved to Arizona, 281
Pioneer Radio Telescope, 143
Planetarium Endowment, 472
Planetarium Inventor Dies, 146
Polaris and the Pole, 218
Radar Echoes from the Sun, 281
Radio Storm in Sun's Corona Recorded, 147
Range of Radio Telescopes, 282
Rapidly Varying Star, A, 218
Report of New Principal Planet Unfounded, 333
Satellite Secures Weather Picture, 73
Seasonal Changes in Night Vision, 415
16th-Century Planetary Position Predictor, 80
Solar System Satellites, 281
Soviet Journal, 332
Texas Summer Workshop for High School Students, 282
Tycho Brahe's Theory of the Solar System, 282
University Gives Observatory to Amateur Astronomer, 19
Unusual Irregular Galaxy, 146
Velocity of Light, 19
Visiting Professor Program, 415
Water in Venus' Atmosphere, 343
Wilkins, H. P., Dies, 280
Xenon in Meteorites, 282

Observer's Page —

Aldebaran Occultation, 41
Another Comet Burnham, 298
April Auroras, 489
Astronomical Seeing, 37
Auroras in February, 359
Celestial Shadows, 298
Comet Burnham 1959k, 292; News of Comet 1959k, 479
Comet Giacobini-Zinner, 112
Deep-Sky Wonders, 42, 108, 171, 234, 297, 360, 490
Drawing the Moon and Planets, 480
Eclipse of the moon of March 13, 1960 (see also under Titles): List of Correspondents on March Lunar Eclipse, 426; Observations of the March Lunar Eclipse, 418; Observing Programs for the Lunar Eclipse in March, 227
Eclipse of the sun of October 2, 1959 (see also under Titles): Amateur Observations of October's Eclipse, 97; "Red Tunnel" at a Sunrise Total Solar Eclipse, The, 111
Late-November Aurora, A, 170
Listening to Meteors on Short Wave, 363
March Aurora, 428
New Variable Stars, 35
Observations of a Nova in Ophiuchus, 35
Observing the Moon, Bessel, 169; Bürg and Lacus Mortis, 357; Parry and Bonpland, 32
Occultation of Neptune, 41
Occultation of Regulus by Venus, 98
Peculiar Variable Star V Sagittae, The, September, 1959; correction, 98
September's Penumbral Eclipse of the Moon, 107
Sidereal Time for 1960, 171
Solar Photography with Autopositive Film, 359
Sunspot Numbers, 41, 108, 172, 232, 299, 365, 428, 480
Ursid Meteors Observed, 294
Venus-Jupiter Conjunction, 299

Observing the Satellites —

Astronomical Observing from Above the Earth's Atmosphere, 283
Discoverers VII and VIII, 157
Discoverer XI, 462
Earth Observations from an Artificial Satellite, 459
Explorer VI and Lunik III, 157
Explorer VII, 90; More About Explorer VII, 223
First Two Years of the Space Age, 12
Lunik III, 91 (correction, 284)
Navigation Satellite, 461
Pioneer V, 409 (correction, 462); Motion of Pioneer V, The, 411
Project Echo, 222
Satellite Nomenclature, 412
Satellites in Orbit — March 1st, 346
Touching the Moon, 11
Translunar Orbit, 13
"Unknown" Satellite, The, 346
Vanguard III, 11

Planetarium Notes, 30, 288

Questions from the S+T Mailbag, 24, 94, 165, 220, 286, 345, 408, 466

Southern Stars, 64, 256, 384, 512

Stars for . . . (current month), 65, 133, 193, 257, 321, 385, 449, 513

OPTICS

Coated Binoculars

Beautifully styled imported binoculars. Precision made.

LOW, LOW PRICES!

American Type "Zeiss" Type

Complete with carrying case and straps. American type offers a superior one-piece frame and clean design. Individual Focus (IF) or popular Center Focus (CF).

Cat. No.	Size	Field at 1,000 yards	Type	Price, ppd.
$1149	6 x 15 IF	360 ft.	Opera	$12.75
$1436	6 x 30 CF	395	"Zeiss"	18.75
$1435	6 x 30 IF	395	"Zeiss"	16.75
$1438	7 x 35 CF	341	"Zeiss"	20.75
$1437	7 x 35 IF	341	"Zeiss"	17.95
$1771	7 x 35 CF	341	American	23.50
$1439	7 x 35 CF	578	American*	35.00
$2191	7 x 50 CF	530	American**	42.50
$1106	7 x 50 CF	372	"Zeiss"	24.95
S-961	7 x 50 IF	372	"Zeiss"	22.50
$1503	7 x 50 CF	372	American	32.50
$1443	8 x 30 CF	393	"Zeiss"	21.00
$1229	8 x 30 IF	393	"Zeiss"	18.25
$1108	10 x 50 IF	275	"Zeiss"	26.75
$1442	20 x 50 CF	183	"Zeiss"	33.75
$1441	20 x 50 IF*	183	"Zeiss"	31.75

*Wide-angle 11° **Wide-angle

All prices above plus 10% Federal tax.



Monoculars

Brand new, coated optics, complete with pigskin case and neck straps.

Cat. No. $1576	6 x 30	$10.00 ppd.
Cat. No. $1577	8 x 30	11.25 ppd.
Cat. No. $1578	7 x 35	12.50 ppd.
Cat. No. $1303	7 x 50	14.75 ppd.
Cat. No. $1579	16 x 50	17.50 ppd.
Cat. No. $1580	20 x 50	20.00 ppd.

8-Power Elbow Telescope

This telescope has a brilliant-image 48° apparent field; actually 325 feet at 1,000 yards. Can be adjusted for focusing 15 feet to infinity. 2" achromatic objective, focusing eyepiece 28-mm. f.l., Amici erecting system. Turret-mounted filters: clear, red, amber, and neutral. Lamp housing to illuminate reticle for night use. Truly the biggest bargain you were ever offered. Original Gov't. cost $200.

8 x 50

Cat. No. $1686 Not Coated ..... $13.50 ppd.
Cat. No. $1975 Coated ..... $17.50 ppd.

Mirror Mounts

Cast aluminum, holds all of our mirrors with metal clips. Completely adjustable, assembled.

Cat. No. $1634 3-3/16" Mount for 4½" Tubing $4.00 ppd.
Cat. No. $1633 4¼" Mount for 5" Tubing . 4.00 ppd.
Cat. No. $1632 6" Mount for 7" Tubing . 6.50 ppd.

Prismatic Telescope



NEW!

80-mm. Objective

Big 80-mm.-diam. (3⅛") objective. Use for spotting or astronomical viewing. Great light-gathering power that will pick up faint objects even under poor sky conditions. Will show stars of the 11th magnitude — 100 times fainter than the faintest visible to the naked eye. Tripod included.

FIVE EYEPIECES

Power	Field at 1,000 yards	Exit pupil diam.	Relative Brightness
15x	122 ft.	5.4 mm.	29
20	122	4.0	16
30	61	2.7	7
40	49	2.0	4
60	32	1.3	1

Cat. No. $2052 ..... $59.50 ppd.

60-mm.-diam. Scope. Same as above but with smaller objective. Equipped with same five eyepieces — 15x, 20x, 30x, 40x, 60x. With tripod.

Cat. No. $1721 ..... $42.95 ppd.

ASTRONOMICAL OBJECTIVES

• • • Air-spaced • • •

"THOSE WHO KNOW" BUY FROM US BECAUSE:

Each lens is thoroughly tested and guaranteed to resolve to Dawes' limit. They are corrected for the C and F lines (secondary chromatic aberration). The zonal spherical aberration and the chromatic variation of spherical aberration are negligible. The cells are machined to close tolerances so that they fit directly over or into our standard aluminum tubing, eliminating any mounting problems. Test a lens, or have any qualified person test it; we are certain that you will be satisfied. If not, take advantage of our money-back guarantee. *We offer the lowest-priced, hand-corrected, precision, American-made astronomical objective,* mounted in an aluminum cell. Our reputation for high-quality lenses has established us as the most reliable source in the industry.

HARD-COATED ON 4 SURFACES.

3¼" APERTURE f/15 — 48" F. L.	Cat. No. $1447	NOT COATED	$28.00 ppd.
	Cat. No. $1471	COATED	32.00 ppd.
4⅛" APERTURE f/15 — 62" F. L.	Cat. No. $1472	NOT COATED	$60.00 ppd.
	Cat. No. $1473	COATED	69.00 ppd.
6" APERTURE f/10 — 60" F. L.	Cat. No. $1861	UNMOUNTED	$150.00 ppd.
	Cat. No. $1860	MOUNTED	175.00 ppd.
6" APERTURE f/15 — 90" F. L.	Cat. No. $1863	UNMOUNTED	$150.00 ppd.
	Cat. No. $1862	MOUNTED	175.00 ppd.

"BIG" ACHROMATIC TELESCOPE OBJECTIVES

We have the largest selection of diameters and focal lengths in the United States available for immediate delivery. These are perfect magnesium-fluoride coated and cemented Gov't. surplus lenses made of finest crown and flint optical glass. Not mounted. Fully corrected. Tremendous resolving power.

● ALUMINUM TUBING and CELLS are in stock ●

Cat. No.	Diam.	F.L.	ppd.
$1476	(2⅛")	(10")	$12.50
$1112	(2⅛")	(11¾")	12.50
$1110	(2⅛")	(13")	12.50
S-958	(2⅛")	(15½")	9.75
$1145	(2⅛")	(20")	12.50
S-952	(2⅛")	(23½")	12.50
$1431	(2⅛")	(30")	12.50
$1432	(2⅛")	(40")	12.50
$1520	(2⅛")	(50")	$12.50
S-851	(3-1/16")	(15")	21.00
$1158	(3⅛")	(19½")	28.00
S-822	(3-3/16")	(24½")	22.50
$1092	(3¼")	(26")	28.00
$1093	(3¼")	(28")	28.00
$1139	(3¼")	(30")	28.00
S-955	(3¼")	(34½")	28.00
S-957	(3¼")	(40")	$30.00
$1155	(4")	(34½")	60.00
$1460	(4¼")	(36")	60.00
$1159*	(4⅜")	(42")	60.00
$1225	(4⅜")	(42")	67.50
$1474*	(5-1/16")	(24¾")	75.00
$1475	(5-1/16")	(24¾")	85.00

*Not coated.

Astronomical Mirrors

These mirrors are of the highest quality. Aluminized and silicon-monoxide protective coating. You will be more than pleased with their performance.

Cat. No.		Diam.	F.L.	ppd.
$1429	Plate glass	3-3/16"	42"	$ 9.75
$1506	Pyrex	4¼"	45"	13.50
$1507	Pyrex	6"	60"	25.00
$2188	Pyrex	6" parabolic	48"	54.50

Mounted Eyepieces

The buy of a lifetime at a great saving. Perfect war-surplus lenses set in black-anodized standard aluminum 1¼" O.D. mounts.

Cat. No.	F.L.	Type	ppd.
$2192	6 mm. (¼")	Orthoscopic	$13.25
$1851	6 mm. (¼")	Ramsden	4.75
$1853	12.5 mm. (½")	Ramsden	4.50
$1207	12.5 mm. (½")	Symmetrical	6.00
$1251	16 mm. (⅝")	Erfle (wide-angle)	12.50
$1257	16 mm. (⅝")	Orthoscopic	12.50
$1209	18 mm. (¾")	Symmetrical	6.00
$1211	22 mm. (27/32")	Kellner	6.00
$1835	27 mm. (1-1/16")	Kellner	4.50
$1355	32 mm. (1¼")	Plossl	12.50
$1253	35 mm. (1⅜")	Symmetrical	8.00
$1255	55 mm. (2-3/16")	Kellner	6.00
$1485	56 mm. (2¼")	Symmetrical	6.00

COATED LENSES 75 cents extra.

"Giant" Wide-Angle Eyepieces

Erfle eyepiece with 65° field, contains 3 coated achromats. 1½" E.F.L., clear aperture 2⅛". Has a focusing mount with diopter scale. Also makes an excellent 35-mm. Kodachrome viewer, magnifies seven times.

Cat. No. $1405 (Illustrated) ..... $12.50 ppd.
Cat. No. $1858 Same as above without diopter scale ..... 9.95 ppd.
Cat. No. $1595 1¼"-diam. ADAPTER for eyepieces above ..... 3.95 ppd.

Wide-Angle Erfle

Brand-new eyepiece with 68° field; coated. E.F.L. 1¼". Focusing mount, 3 perfect achromats, 1-13/16" aperture.

Cat. No. $1020 ..... $13.50 ppd.
Cat. No. $1593 1¼" diam. ADAPTER for eyepiece above ..... 3.95 ppd.

An Economical Eyepiece

This mounted eyepiece has two magnesium-fluoride-coated achromatic lenses 29 mm. in diameter. Excellent definition. E.F.L. 1¼". Cell fits 1¼" tubing.

Cat. No. $1911 Coated ..... $5.90 ppd.
Cat. No. $1991 Not Coated ..... 5.25 ppd.

Rack-&-Pinion Eyepiece Mounts



Here is a wonderful opportunity for you to own a most mechanically perfect Rack-&-Pinion Focusing Eyepiece Mount with variable tension and adjustment. Will accommodate a standard 1¼" eyepiece, positive or negative. The body casting is made of lightweight aluminum with black-crackle paint finish, focusing tube of chrome-plated brass. Focusing tube for refractors has a travel of 4", for reflectors 2", and will fit all size tubing.

REFRACTOR TYPE

Cat. No. $1494 for 2⅛" I.D. Tubing ..... $12.95 ppd.
Cat. No. $1495 for 3¼" I.D. Tubing ..... 12.95 ppd.
Cat. No. $1496 for 4⅛" I.D. Tubing ..... 12.95 ppd.

REFLECTOR TYPE

Cat. No. $1976 (less diagonal holder) ..... $8.50 ppd.
Cat. No. $1982 DIAGONAL HOLDER ..... 1.00 ppd.

● FREE CATALOG ●

Millions of lenses, prisms, eyepieces, rack-and-pinion eyepiece mounts, cells, aluminum tubing, mirrors, binoculars, telescopes, parts, accessories, and so forth. Write today!

We pay POSTAGE IN U. S. — C.O.D.'s you pay postage. Satisfaction guaranteed or money refunded in 30 days.

A. JAEGERS
6915 MERRICK RD., LYNBROOK, N. Y.

From time to time we get letters comparing Questar's performance to that of much larger telescopes. So many of these praise Questar extravagantly that we often wonder, as we sit here in the office, if Questar is as good as they say, or if the other telescopes are of poorer quality than their owners realize. Ah, well — perhaps we'll never know. This typical letter is from Mr. M. G. Voet of Holland:

"I'm a Dutch amateur astronomer and owner of a 9-inch reflecting telescope. It gives rather good images but the instrument is so heavy to take into my garden that I seldom use it. Recently an American relative in West Germany allowed me to look through his small catadioptric telescope — a Questar — and I was very amazed to see that its excellent images showed as much detail on the moon as my heavy reflector. I should be very pleased if you could give me any further information about this Questar telescope."



LAY THAT BURDEN DOWN

When you finally get tired of lifting and carrying your telescope in and out of doors, tired of setting it up and taking it down in chilly darkness —

When you've had enough of heavy loads, of quivering tubes and images, enough of drives that falter and slow-motions that fall short —

When you finally realize that it has become too much trouble to use your telescope any more because it only gives you an aching back and a pain in the neck — when you've had your fill of the whole unhandy contrivance — *send for the Questar booklet!*

The Questar booklet will tell you how to lay your burden down. No more lifting, no more toting, no more setting up of heavy, clumsy parts. Questar weighs but 7 pounds. It is always assembled, always ready to use.

It will tell you how Questar stands alone, the only thing of its kind, with the latest kind of optics, the mixed lens-mirror system of the new catadioptric optics. How Questar's folded focal length keeps it fabulously short, how so short a telescope can be as stiff and rigid as a great observatory instrument. It will tell you how Questar's images are as rock-steady as a microscope's, how its controls are ready to your fingertips, and how its 360° continuous slow-motions have a buttery smoothness with absolutely no backlash at all. It will tell you of finer performance than was ever dreamed of from only 89 mm. of aperture, and prove that point by the amazing resolution of the photographs it takes.

But hold on — let the booklet tell you this — let us use this space to tell you other things.

Let us speak, for instance, of investment value. Questar costs no more than ordinary 'scopes would if they were so well mounted as to be equally solid and vibration-free. But let's face it — Questar optics cost more by the extra hours of human labor required to make, for example, mirrors that must be 16 times more accurate of figure than the ordinary kind. Questar's mounting, too, has over 235 separate parts, each one of the best procurable alloys down to the last small stainless-steel screw.

So let us tell you what we have found out — that Questars are so greatly in demand that the few which reach the second-hand market depreciate an average of less than 7% per year! Imagine this — telescopes 3 years old may bring 80% of their purchase price! We know of few manufactured products with such amazingly high value at resale.

Remember then, that if you too become a Questar owner, you will be making the most conservative investment possible. We firmly believe that it will cost you less per year to enjoy a Questar.

Questar, as illustrated, still costs only $995 postpaid, in handmade velvet-lined English leather case. Terms are available. May we send you the booklet?

Questar

NEW HOPE · PENNSYLVANIA

Wayne L. Norton, Ridgeville, Indiana, photographed the April 23rd aurora with a 75-mm. f/3.5 lens, the exposure time being about seven minutes. The constellation Cassiopeia is left of center.

APRIL AURORAS

WIDESPREAD aurora activity occurred late in April, according to reports sent to SKY AND TELESCOPE. On Saturday evening, April 23rd, an evening display was seen by Jack K. Vorrenter at Lakemont, New York; Lewis Dewart, Sunbury, Pennsylvania; LaVerle Berry, Perrysville, Ohio; Donn Cuson, Grand Rapids, Michigan; Wayne L. Norton, Ridgeville, Indiana; Al Stewart, Elmhurst, Illinois; George W. Rippen, Madison, Wisconsin; and Josef R. Otoupalik, Greeley, Colorado.

Four evenings later, northern lights were again seen at Lakemont, Sunbury (by William J. Nagle), Ridgeville, and Elmhurst. They were photographed by Carl Kwadrat at Duquesne, Pennsylvania, 12 miles east of Pittsburgh, and seen at Appleton, Wisconsin, by David Geenen, John Roegner, and Thomas Kemen, as a "brilliant display."

Also, from as far west as Pinehurst, Idaho, auroral phenomena took place. In one night's observing Claire C. Cahill saw a pale green and yellow aurora, which later showed green and red flashes and draperies, a brilliant reddish fireball between the Big Dipper and Cassiopeia, and Comet Burnham 1959k.

Again on April 28th, Mr. Vorrenter saw auroral activity from the shores of New York's Seneca Lake.

THE ASTRONOMER KIT

A **complete** telescope mirror making kit.

★ FOUCAULT TESTER, in its entirety, with light source, knife-edge, measuring scale
PYREX MIRROR BLANK
★ NEW, NONVITREOUS TOOL, faster, smoother, more accurate
SEVEN ABRASIVES for greater safety and speed
CERIUM OXIDE for fast, clean polishing
SPECIAL OPTICAL PITCH to minimize danger of turned-down edge
MAGNIFYING LENS, essential in mirror grinding
★ DETAILED, ILLUSTRATED INSTRUCTIONS, "Mirror Making in the Kitchen"

(Starred items exclusive with The Astronomer Kit)

6-inch kit ..... **$15.00 ppd.**
4¼-inch...$11.50 ppd.; 8-inch...$22.50 ppd.
Foucault tester only ..... **$ 6.00 ppd.**

Money-back guarantee. Write for catalogue.

ASTRONOMY, INC.
Suite 305, American National Bank Bldg.
Denver 2, Colorado

Breathtaking Performance —

with an

ASTROLA REFLECTING TELESCOPE

American Made — Available on Time Payments

Truly breathtaking performance is yours with an ASTROLA Reflector. If you are an ASTROLA owner, you will enjoy many thrilling views — the finer markings on Jupiter's cloud belts, gaps in Saturn's ring system, delicate details on Mars, such as the canals — all far beyond the grasp of smaller or less perfect telescopes. If you haven't ordered your ASTROLA, why wait? Countless observing thrills will be yours throughout the rest of 1960 and for many years to come — with an all-precision ASTROLA Reflecting Telescope. For solid observing comfort, nothing matches the De Luxe ASTROLA models, with electric clock drive, large solid-brass setting circles, and smooth rotating tube always allowing the eyepiece to be horizontal.

Pictured here, we are proud to present our newest 10" f/7 ASTROLA on a permanent 9"-diameter steel observatory pedestal, with clock drive, setting circles, 2" finder, and four Brandon orthoscopic oculars. Full price, including packing and crating (f.o.b. Long Beach), **$795.00**

PORTABLE ASTROLA REFLECTORS

6" Student, f/7 to f/9.. **$194.50**

	Standard	De Luxe
6"	$325.00	$500.00
8"	$390.00	$590.00
10"	$495.00	$750.00
12½" Transportable	$1150.00	

NEW ALUMINIZED PYREX MIRRORS AND DIAGONALS

6"	$60.00
8"	$92.50
10"	$160.00
12½"	$250.00

Send for our new 1960 complete color catalogue and full-price sheet. Visit our display room when you are in the Los Angeles area. Always in stock are many small reflectors, refractors, books, and accessories.

CAVE OPTICAL COMPANY

4137 E. Anaheim St., Long Beach 4, Calif.
Phone: GEneva 4-2613

DEEP-SKY WONDERS

ONE of the most interesting types of telescope to be developed lately is the official Moonwatch apogee refractor. Designed for observing faint artificial satellites, it combines a standard M-17 ocular and roof-prism assembly with a 5-inch objective of about 20 inches focus. The field is 2½° and the power 20. It provides a revelation for observers of clusters and nebulae.

On a sharp, unseasonably cold night in late March, when two feet of snow blockaded my observing site, an apogee telescope was set up in the cleared area around my car. I first turned it on Coma Berenices. The night was very clear, for to the unaided eye this cluster did not have its usually hazy shimmer. Instead, each star stood out clearly, and I needed a second or two to be sure that it really was Coma.

In the telescope the images were sharp and small, and the galaxy NGC 4565 was noticed without effort, just off the luminous V of stars. The object seemed bright, about magnitude 8.5, though the Skalnate Pleso *Atlas Catalogue* gives 10.2. It looked like a blazing little needle in the sky, and even fast sweeping picked it up readily. Held in the field, this galaxy seemed all of 15′ long by perhaps 45″ wide, fairly uniform along its entire length.

Photographs reveal NGC 4565 to be a beautiful edgewise spiral, and while the apogee telescope could not show the dark band of dust that cuts the nucleus through the middle, a 10-inch reflector will. The 1950 position is 12ʰ 33ᵐ.9, +26° 16′.

Then the hand-held telescope slipped, the field sliding rapidly about 10°. But I was able to see a bright globular cluster as it whipped by. A little cautious hunting recovered the object, with a curious snake of bright stars above it and a wide pair below, identifying the cluster as M53 (NGC 5024) without even consulting a chart. It was probably the most dramatic view of this globular I have ever had, for it seemingly hung between the earth and the starry background. Much brighter at the center, M53 too appeared more luminous than its catalogue magnitude of 7.6. Those who depend on setting circles will find this cluster at 13ʰ 10ᵐ.5, +18° 26′.

The fine edge-on galaxy NGC 4565 was discovered by Sir William Herschel, and listed by him as No. 24 of his class V (very large nebulae). Mount Wilson and Palomar Observatories photograph.

N. T. Bobrovnikoff has shown that the estimated magnitude of a comet depends greatly on the telescope used, the comet seeming brighter in smaller instruments. This appears to be true, too, for globular clusters and galaxies, at least to some extent. Several objects near M53 — M3, NGC 4559, and NGC 4656 — looked much brighter in the apogee telescope than expected.

The night must have been an unusually fine one. The naked-eye limit for the North Polar Sequence stars was 7.4, but I made no test there with the telescope. About midnight I saw a small amount of zodiacal light on the western horizon; at the same time the Beehive cluster to the naked eye looked like M13 in a 3-inch telescope. The gegenschein was found after a minute of searching, and a zodiacal band clearly ran from the western horizon to it. But even with averted vision it was not possible to trace the band from there to the eastern horizon.

WALTER SCOTT HOUSTON
Rte. 3, Manhattan, Kans.

SKY-GAZERS EXCHANGE

Classified advertising costs 30 cents a word, including address; minimum charge, $4.00 per ad. Only one *for sale* ad per issue for each advertiser. *Remittance must accompany order.* Insertion is guaranteed only on copy received by the 20th of the second month before publication; otherwise, insertion will be made in next issue. We cannot acknowledge classified ad orders. Sky Publishing Corporation assumes no responsibility for statements made in classified ads, nor for the quality of merchandise advertised. Write Ad Dept., *Sky and Telescope*, Harvard Observatory, Cambridge 38, Mass.

4″ DYNASCOPE equatorial, clock drive, three eyepieces, $70.00. Richard Crutcher, 345 Dudley Rd., Lexington, Ky.

WANTED: 8″ to 15″ telescope and mount suitable for student observation and research. Pomfret School Observatory, Pomfret, Conn.

ALUMINUM TUBING, eyepieces, and so forth. Peninsula Scientific, 2421 El Camino Real, Palo Alto, Calif.

FOR SALE: Telescope manufacturing and retail business; sales and service on surveying instruments, binoculars, and microscopes. Now operating one man full time, one part time. Can be readily expanded to three- or four-man shop. Want to retire, but will remain reasonable time to break in new owner. Will finance to right buyer. Waring-Cleveland Instrument Co., 21564 Lorain Rd., Cleveland 26, Ohio.

BOOKLET: *The Universe Through the Eye*, $1.00. Also used telescopes. Frank J. Hereford, 1809 20th St. N.W., Washington 9, D. C.

SOUTHWESTERN OBSERVERS: Finest refractor telescopes supplied in 2.4″, 3″, and 4″ altazimuth and equatorial models. Details on request. Melton Industries, 1901 Levee St., Dallas 7, Tex. Phone: RI 8-4769.

FOR SALE: Excellent 3″ refractor, all Unitron components, finder, $150.00. Perfect 4″ f/6 Ektar lens, shutter, iris, $20.00. 3″ f/10 folding wood reflector, $15.00. Tank periscope, contains 3″ eyepiece prisms, $10.00. Bakelite tube, 9¾″ I.D., 54″ long, $30.00. Arthur N. Wood, 289 Washington Ave., Brooklyn 5, N. Y.

FINEST f/10 4¼″ pyrex parabolic mirrors, guaranteed to Dawes' limit, still only $14.95 each. Single-element Barlows: 1.250″, $5.95; 0.946″, $4.95. All types of model or production machine-shop service. Vernonscope and Co., Candor, N. Y.

TELESCOPE OBSERVATORY, excelling design. Fabricated from structural steel and aluminum. Revolving turret dome, 8′ diameter, 7′ high. This beautiful and highly versatile observatory will be shipped directly to you in easy-to-assemble kits. Write for free photographs and details. $595.00. Unique Products Agency, 212 E. Key, Oklahoma City 10, Okla.

INTERESTED in astronomy as a career? *Vocational and Professional Monographs: Astronomy*, by Dr. Freeman D. Miller, describes personal qualifications, scholastic training, and job opportunities. $1.00 postpaid. Send to Box B, *Sky and Telescope*, 49 Bay State Rd., Cambridge 38, Mass.

FOR SALE: Unitron 4″ clock-driven photo-equatorial refractor, complete with pier and tripod, spectroscope, plus many accessories. Details on request. $875.00 f.o.b. R. S. Waude, 2515 Ridgeway, Evanston, Ill.

FOR SALE: Questar de luxe, full sun filter, complete, original container, $750.00. Jess Williams, 1515 S. 40th St., Lincoln, Neb.

WANTED: 16″ pyrex mirror blank. Montclair Telescope Club, 280 N. Mountain Ave., Upper Montclair, N. J.

FOR SALE: De luxe Questar. Purchased new October, 1959. Never been used. Price $850.00. John Schroeder, 900 Lake Shore Dr., Chicago 11, Ill.

Lafayette **INSTRUMENT DIVISION For Research Equipment**

Professionally Designed and Produced

2.4" EQUATORIAL REFRACTOR

79.50

Polaris

- 800-mm. focal length
- 62-mm. objective
- Micromotion adjustments on both axes
- Coated optics throughout
- Equatorial mount
- Eyepieces for 160x, 88x, 40x (200x available at extra cost*)

Latest in a long line of Lafayette refractors at reasonable prices. The unusual value of the Polaris is recognizable in the following specifications. Objective: Fraunhofer-type achromat, hard coated, 62.5 mm., 800-mm. focal length. Collects about 75 times as much light as the naked eye, resolving power 2 seconds, faintest discernible star 10.7 magnitude. All eyepieces are hard-coated Huygenians: 160x (5 mm.), 88x (9 mm.), 40x (20 mm.).

Finder scope is 6x, 30 mm. Equatorial mount with slow-motion controls in right ascension and declination. Tripod head with latitude adjustment. Clamp lever for declination and inclination. Accessories include sunglass, star diagonal, erecting prism, sun projection screen, field tripod, and wooden case. Rack-and-pinion focusing. Heavy plating used throughout to prevent rusting. Shipping wt. 30 lbs. VIA EXPRESS ONLY.

F-342 ..... 5.00 Down ..... Net **79.50**

F-391 *4-mm. orthoscopic eyepiece for 200x ..... Net **8.95**

Galactic 3" Equatorial Refractor

- 910-mm. focal length
- 76.2-mm. clear aperture
- Micromotion controls for declination and right ascension
- Resolving power 1.6 seconds of arc

Truly superior quality — advanced design — optically and mechanically suitable for serious research. Objective lens is 79-mm., hard-coated, air-spaced Fraunhofer achromat with clear aperture of 76.2 mm. (3"). Focal length 910 mm., focal ratio f/12, resolving power 1.6 seconds. 7 coated eyepieces providing 227x, 152x, 101x, 73x, 45x, 35x, plus 25x through finder. Focusing by means of microprecise rack-and-pinion drive. View finder has 42-mm. (1.6" clear aperture) objective, 500-mm. focal length, rack-and-pinion focusing, and will accommodate various eyepieces. Oversized equatorial mount insures stability and smooth action. Finely calibrated hour and declination circles for rapid finding and setting. Micromotion controls and clamps for both declination and right ascension. Controls fitted with flexible shafts and oversized knobs for ease of positioning while viewing. White-enameled aluminum body tube for maximum strength with minimum weight. Accessories include 3 sunglasses, moonglass, 2 star diagonals, sun diagonal, erecting prism, sun projecting screen, extendable field tripod with chain brace, accessory shelf, wooden cabinet. Shipping wt. 60 lbs. VIA EXPRESS ONLY.

F-384 ..... 5.00 Down ..... Net **189.00**

189.00

269.50

Arcturus 3" Equatorial Refractor

- Ultra-precise helicoid focusing
- 76.2-mm. clear aperture
- 7 coated eyepieces
- Most advanced equatorial mount

The finest 3" refractor — true research quality — within the price range of the serious amateur. Incorporates a 79-mm. hard-coated air-spaced Fraunhofer achromat of 910-mm. focal length, with a full 3" clear aperture, f/12, and resolving power of 1.6 seconds of arc. 7 coated eyepieces provide 227x, 152x, 101x, 73x, 35x, 18x, and 25x through finder. Helicoid focusing — the finest available — by means of a massive wheel and ultra-fine helical gear. Finder scope, with rack-and-pinion focusing, features a 1.6"-clear-aperture objective of 500-mm. focal length. Provides for interchangeable eyepieces. Equatorial mount of massive construction and advanced design incorporates finely calibrated hour and declination circles. Micromotion controls with extended flexible shafts and compression locks on all axes. Accessories include 3 sunglasses, moonglass, sun diagonal, 2 star diagonals, sun projection screen, erecting prism, heavy extendable field tripod, brace, accessory shelf, separate wooden cases for telescope and mount. Shipping wt. 100 lbs. VIA EXPRESS ONLY.

F-385 ..... 10.00 Down ..... Net **269.50**



29.95

STAR SPECTROSCOPE WITH 3 EYEPIECES

- Observe the spectra of stars of magnitudes 1 to 3
- Identify Fraunhofer lines from C to G
- Drawtube focus arrangement
- Fits threads of 25-mm. O.D. eyepieces

The Star Spectroscope (Amici-prism type) is excellent for visual observations of the spectra of bright stars, comets, and novae. The spectroscope consists of a 5-piece prism assembly, threaded ocular tube (25.4-mm. I.D.), and 3 cylindrical-lens eyepieces. These widen the star spectrum for easier recognition of details. Use this direct-vision spectroscope on medium-size telescopes to observe stars as faint as magnitude 3. The dispersion angle between the Fraunhofer C line (wave length 6600 angstroms) and the G line (4300 angstroms) is 9°. The resolution is enough to separate the yellow D lines of sodium. Body is made of black-coated brass. All in a plush-lined case. Shipping wt. 8 oz.

F-569 ..... 2.00 Down ..... Net **29.95**

LAFAYETTE RADIO

165-08 LIBERTY AVE.
JAMAICA 33, N. Y.

NEW YORK, N. Y., 100 Sixth Ave.
BRONX, N. Y., 542 E. Fordham Rd.
NEWARK, N. J., 24 Central Ave.
PLAINFIELD, N. J., 139 West 2nd St.
BOSTON, MASS., 110 Federal St.

USE OUR EASY PAYMENT PLAN — DOWN PAYMENTS AS LOW AS $2.00 AND UP TO 24 MONTHS TO PAY

LAFAYETTE RADIO P. O. BOX 1000 JAMAICA 31, NEW YORK

☐ Please Send Stock #.....
I Enclose $..... Dept.
☐ Rush Free Catalog. SKF6

Name .....

Address .....

City ..... Zone ..... State .....

ENGINEERED FOR THE LAST WORD IN BREATHTAKING PERFORMANCE . . . PRICED FOR FIRST CHOICE IN VALUE . . . FULLY EQUIPPED WITH MANY EXTRA FEATURES!

You'll Marvel At How The Superb Optics Of This Portable RV-6

6-inch DYNASCOPE®

Gives The Same Exquisite Definition As Far More Expensive Instruments!

Including . . . ● ***ELECTRIC DRIVE (Patented)*** ● ***SETTING CIRCLES*** ● ***ROTATING TUBE***

A Complete Instrument, No Costly Accessories Needed!

Model RV-6 Complete with Dyn-O-Matic Electric Drive and All Features Described Below

$194.95

f.o.b. Hartford, Conn.
Shipping Wt. 55 lbs.
Express Charges Collect
No Packing or Crating Charges

This new addition to the Dynascope line has won immediate recognition from schools, colleges, and professionals, as an outstanding achievement in a 6-inch telescope. Although it was only recently introduced, our files are already filled with complimentary letters from excited amateurs and professionals all over the country. Each one is truly amazed at the superior optical performance of this new RV-6 6-inch Dynascope! Here is large aperture in a quality instrument at a price that compares with many 4-inch telescopes. *And this low cost includes such exclusive extra features as electric drive* (patented), *setting circles, and rotating tube!* There are no "extras" to run up your cost!

The superb optical system resolves difficult objects with definition that is absolutely breathtaking. The close tolerance of the precision construction assures an accuracy and smoothness of operation once associated only with the finest custom models. The heavy-duty mount, complete with electric drive, provides the stability so essential for satisfactory viewing, yet there is easy portability because in a matter of minutes the entire telescope can be dismantled into three easy-to-handle sections.

Only Criterion's engineering ingenuity, coupled with volume production and modern manufacturing methods, makes this handsome 6-inch model available at such reasonable cost. You can order it with complete confidence that it will live up to your expectations in every way, for this assurance is *guaranteed* under our full-refund warranty. Send your check or money order today. Or use our liberal time-payment plan and take months to pay.

YOU COULD PAY $100 MORE WITHOUT GETTING ALL THESE SUPERIOR FEATURES (Except on Another Dynascope)

1. **EXQUISITE OPTICAL SYSTEM INCLUDES F/8 6-INCH PARABOLIC PYREX MIRROR** accurate to better than ⅛ wave, zircon-quartz coated, and guaranteed to reach all theoretical limits of resolution and definition. Teamed with elliptical diagonal, mounted in 4-vane adjustable spider.

2. **NEW DYN-O-MATIC ELECTRIC DRIVE** with smooth self-acting clutch that engages and disengages automatically as you seek different objects. Will not interfere when manual operation is desired. Entire drive housed in trim aluminum case. Plugs into ordinary household socket.

3. **CHOICE OF ANY 3 EYEPIECES** from the following: **65X**-18-mm. Achromatic Ramsden; **100X**-12.7-mm. Achromatic Ramsden; **150X**-9-mm. Achromatic Ramsden; **220X**-6-mm. Orthoscopic; **320X**-4-mm. Orthoscopic. All are precision-threaded, give sharp images to extreme edges.

4. **SOLID NEW EQUATORIAL MOUNT** extra-reinforced design to provide pillarlike stability. No annoying side play or wobble. Adjusts easily to any latitude.

5. **SETTING CIRCLES** for both right ascension and declination. Handsomely engraved and finished in fine aluminum.

6. **6 x 30 FINDERSCOPE, ACHROMATIC, COATED,** with accurate crosshairs and fine focus. Durable cast-aluminum bracket with 6 adjusting screws allows positive collimation.

7. **ROTATING TUBE FOR MAXIMUM VERSATILITY AND VIEWING COMFORT.** Solid-cast, chrome finish, rings are generous 1" wide with felt lining. Newly designed construction, with over-sized knurled adjusting knobs, affords maximum rigidity and allows for quick disassembly and portability, with or without tube.

8. **STRIKINGLY HANDSOME WHITE 50" BAKELITE TUBE** with porcelainized Duralite finish, durable yet light. Walls are ⅛" thick, completely insulated and anti-reflective blackened inside.

9. **BRASS RACK-AND-PINION EYEPIECE HOLDER** has precision-cut rack and gear for easier, smoother, more positive focusing. Takes standard 1¼" oculars, negative or positive.

10. **STRONG, VIBRATION-FREE, ALL-METAL TRIPOD** with easily removable legs. Provides sure, steady support, plus lightweight portability.

CRITERION MANUFACTURING CO.

331 Church St., Hartford 1, Conn.

Manufacturers of Quality Optical Instruments

ENJOY IT NOW FOR ONLY $74.95 DOWN

No need to put off the thrills of owning this magnificent instrument! Send your check or money order today for only $74.95 as full down payment . . . pay balance plus small carrying charge in your choice of 6, 12, or even 24 monthly payments. Same unconditional guarantee applies, of course. Or order today by sending your check or money order with coupon below.

Sound too good to be true? Then read what these delighted DYNASCOPE owners have to say:

"I never dreamed such a brilliant, clear image could be had with a telescope costing under $200. It is one of these rare bargains that you find only once or twice in a lifetime."
B.S. — New Jersey

"A friend of mine has a 6-inch telescope without electric drive, for which he paid over $300. He agrees that my new DYNASCOPE not only outperforms it, but is a much better-looking and better-built instrument." **J.L. — New York**

"Congratulations on the excellence of your workmanship. The optics are truly amazing. I never expected such wonderful performance."
L.H.N. — Massachusetts

Criterion Manufacturing Co.
Dept. STR-11, 331 Church St., Hartford 1, Conn.

☐ Please send me, under your MONEY-BACK guarantee, the RV-6, 6" Dynascope. Full payment of $194.95 is enclosed.

☐ I prefer your easy terms! Enclosed $74.95 as down payment with understanding that I will pay balance (plus small carrying charge) over 6___, 12___, 24___ months (check choice).

☐ Send FREE ILLUSTRATED LITERATURE of all the telescopes in the Dynascope line.

Name .....

Address .....

City ..... State .....

BOOKS AND THE SKY

INTRODUCTION TO THE MECHANICS OF THE SOLAR SYSTEM

Rudolf Kurth. Pergamon Press, New York, 1959. 177 pages. $6.50.

WITH the renewed interest over the last three years in dynamical astronomy, several books on celestial mechanics have appeared. Most of these are rehashes of standard works of the past, with more or less insight into methods initiated by Lagrange, Laplace, Gauss, Hamilton, Jacobi, and Poincaré. Some contain a chapter or so dealing with more modern material, such as the relativistic advance of Mercury's perihelion, but all tend to be presentations of classical material in a classical manner with classical notations.

In Rudolf Kurth's new textbook we discover a fresh and unconventional approach to the problems of celestial mechanics. "Like Socrates," as the author says in the preface, he "dislikes long speeches — and long formulae; and the formulae of celestial mechanics can indeed be very long." His avowed intent is to promote the understanding of fundamental principles and methods. He is not concerned with "ready-made recipes" but with a "methodical approach."

The book has four chapters. The first is called "The Kinematics of a Single Planet." Beginning with the axiomatic treatment that he uses through most of the text, Kurth derives the relation between the synodic and sidereal periods that is found in all elementary textbooks in astronomy, but in a rigorous manner. He indicates the assumptions and approximations that are made and the order to which the expressions are valid. He shows how Kepler's laws of planetary motion may be derived from the observations and then how, knowing the elliptic elements, the orbital motion may be determined. Kepler's equation is obtained and solved by a series of successive approximations. Convergence of the method used is proved by the methods of analysis. At this point vectorial notation is introduced, to be used throughout the remainder of the book. The author shows theoretically how an orbit may be determined from three observations and later improved by comparison with additional observations.

Chapter II, "The Dynamics of a Single Planet," begins with a discussion of force and mass, assuming that the reader has never seen the axiomatic treatment of this subject found in physics books. The differential equations of motion are solved analytically, as well as by the methods of Laplace and Gauss for orbit determination purposes.

The next section, "The Dynamics of the Planetary System," is the heart of this work, for it deals with the general integrals of the equations of motion and perturbation theory. Perturbations in the co-ordinates and in the elements are developed. In the former there is a brief discussion of long-period and secular terms, as well as an indication of the methods employed by Adams and Leverrier in determining the elements of Neptune from the observed perturbations of Uranus. In the variation of elements, the methods of Lagrange and Poisson are employed.

Stability of the solar system is touched upon, and a simple derivation of some lunar inequalities is given. The secular advance of Mercury's perihelion is obtained by assuming an acceleration, additional to the Newtonian, which is inversely proportional to the distance and the square of the velocity of light. This gives a term equivalent to that obtained in relativity theory. Finally, there is a brief discussion of the restricted problem of three bodies.

In Chapter IV, "The Planets and the Moon as Rigid Bodies," Kurth derives the motion of pericenter and nodes about a rotationally symmetric planet, the precession and nutation of the earth, and gives a brief treatment of the moon's rotation.

This book assumes a knowledge of advanced calculus, some matrix algebra and

13 Noted Scientists Present A SPACE AGE SYMPOSIUM...

Robert Jastrow
Fred L. Whipple
Thomas Gold
Eugene Parker
James A. Van Allen
N. C. Christofilos
Homer E. Newell
Gerard P. Kuiper
Harold C. Urey
G. de Vaucouleurs
Herbert Friedman
Leo Goldberg
J. W. Townsend, Jr.

THE EXPLORATION OF SPACE
edited by Robert Jastrow
illustrated, $5.50

Van Allen discusses the geomagnetically trapped corpuscular radiation; Christofilos reports on "The Argus Experiment;" de Vaucouleurs, on Mars and Venus; Goldberg, on astronomy from satellites and space vehicles; Whipple, on solid particles in the solar system. Other vital topics include rocket astronomy, plasma and magnetic fields in the solar system, the U.S. space-exploration program, and the U.S.S.R. report of an active volcano on the moon.

Order Today From Your Nearest Bookstore Or Write Dept. ST-12.

The Macmillan Company
60 FIFTH AVENUE, NEW YORK 11, N.Y.

Star Atlases and Books on Astronomy

New: STRANGE WORLD OF THE MOON, by V. A. Firsoff.....$5.50
THE OTHER SIDE OF THE MOON.....$2.50
New: LAROUSSE ENCYCLOPEDIA OF ASTRONOMY.....$12.50
AMATEUR ASTRONOMER'S HANDBOOK, by J. B. Sidgwick....$12.50
OBSERVATIONAL ASTRONOMY FOR AMATEURS, by J. B. Sidgwick....$10.00
THE SKY OBSERVER'S GUIDE.....$2.95
THE PLANET VENUS, by P. Moore..$3.75
THE PLANET JUPITER, by B. Peek..$8.50
STANDARD HANDBOOK FOR TELESCOPE MAKING, by N. Howard....$5.95
AMATEUR TELESCOPE MAKING
Book 1, $5.00; Book 2, $6.00; Book 3, $7.00
Norton's STAR ATLAS.....$5.25
Beyer-Graff STAR ATLAS.....$15.00
BONNER DURCHMUSTERUNG.....$100.00

Pocketbooks and paperbacks on astronomy — write for listing. Ask for new free list on astronomical literature. Books on telescope making and optical glassworking.

HERBERT A. LUFT
69-11 229th St., Oakland Gardens 64, N. Y.

Astronomy Films

16-mm. sound, 400-foot reels
I THE SUN; II THE MOON;
III SOLAR SYSTEM; IV MILKY WAY;
V EXTERIOR GALAXIES.

2 x 2 SLIDES

35-mm. STRIPS OF SLIDES

THROUGH **200-INCH** AND OTHER GREAT TELESCOPES
Catalogues on request.

International Screen Organization
1445 18th Ave. North, St. Petersburg 4, Fla.

A NEW PRODUCT FOR SPRINGTIME OBSERVING

A new and different set of sky maps!

12 circular maps, slightly overlapping, cover the sky and show all stars to 5th magnitude including the 1,078 stars listed in the *American Ephemeris and Nautical Almanac*. Each chart, 8½" square with rounded corners and punched for binders, is printed on 1/100"-thick clear plastic with details displayed in acrylic white over luminous stars (phosphorescent painted). Brightest stars are labeled.

You can see the chart stars in the dark, and look through the chart to match up the stars in the real sky. The gnomonic projection makes them fit the sky without distortion. Packaged in a neat plastic envelope with an index map and explanation, the charts are sized to give the star watcher a chart that is not ungainly to handle. Figuratively speaking, you can now look through an illuminated window that matches the stars. A chart that glows with the sky. No need to use a flashlight to check up on an object and at the same time spoil your eyes' dark adaptation.

This new idea is a significant advance in star study. Do you want the heavens to be really yours? Then you will want this new study help. Are you one of those people (and there are many) with a new interest in the sky because of satellite and space talk, but who know little about the stars? Then you need this set of charts! THE SKY CAN BE YOURS NOW!

Price, including postage and packaging, only **$5.25**

Write for free catalogue.

ASTRONOMY CHARTED
33 Winfield St., Worcester 10, Mass., U.S.A.
Phone: PL 5-6092

Now in smaller sizes

NEW! **AERO PLASTIC RELIEF MAPS**

16 x 28

UNITED STATES
THE WORLD each **$9.95**

These maps are an excellent visual aid in the teaching and study of earth sciences, as well as a handsome addition to home or office. Vertical exaggeration and color emphasize relief features. The maps are molded of tough, sturdy Vinylite and are self-framed with brass grommets for easy hanging. They can be cleaned in a minute with a damp cloth. These are the maps selected by the U. S. Weather Bureau for display in airport weather stations. (The U. S. map has insets showing Alaska and Hawaii.)

Also Standard-Size Aero Plastic Relief Maps.

Write for complete catalogue.

SCIENCE ASSOCIATES

Instruments/Weather • *Astronomy/Teaching Aids*

194 Nassau St., P. O. Box 216, Princeton, N. J.

WEATHER OBSERVATION
16-mm. Camera and Data Recorder

Military-type weather observation unit contains a sun-angle optical system; 16-mm. magazine camera, motor-driven, taking single-frame pictures (similar to gun cameras); 8-day aircraft-type clock with sweep-second dial and separate hour scale; precision mirror and lens system with graph and float level; filter assembly; compass; barometer; sealed relay; 5-digit solenoid-operated counter.

System records simultaneously one frame showing exposure, barometer, compass, time, and counter readings, on 16-mm. film. System operates on 12-volt d.c.

Unit is shown disassembled, but it comes completely assembled in original government shock-mounted packing.

Perfect for celestial and industrial photography at a fraction of government cost.

Brand new. Shipping weight, 45 lbs. 15" x 9" x 17".

Price **$35.00** each
f.o.b. N. Hollywood, Calif.,
or f.o.b. Utica, N. Y.
(Please specify shipping point)

STANDARD ELECTRONICS, INC.
4900 Lankershim Blvd., North Hollywood, Calif.

vector analysis, and is on the senior or first-year graduate level. Except for a few places where diagrams would have greatly improved the clarity of presentation, and for a very few sentences translated awkwardly from the German, the material is lucidly presented.

There are few typographical errors — page headings for Chapter I erroneously use the word kinetics instead of kinematics; the power 2 is missing in equation (1) on page 48; the draconitic period is confused with the saros on page 128; incorrect references to equations are occasionally given. One great inconvenience is the system of references to equations. A reference such as III § 6.2(5) generally requires going through the table of contents, which does not contain the subsection number, only its title. (Subsections contain number but not title.)

This book can be recommended highly for giving the feel and some of the spirit of celestial mechanics. It can profitably be used as collateral reading in a first course. Some ideas presented are open to serious criticism, in particular the author's feeling that canonical methods are useless except in statistical cases. The fruitfulness of such an approach is attested by its successful application to many classical and current problems. A recent issue of the *Astronomical Journal*, for example, has three papers on the motion of artificial satellites in which canonical variables give elegant and practical solutions.

The author's insistence on first-order simplicity may mislead many students into thinking that actual planetary or satellite problems can be solved without the long formulae of celestial mechanics. Unfortunately, this is not so.

MORRIS S. DAVIS
Yale University Observatory

KEPLER

Max Caspar. Abelard-Schuman, New York, 1959. 401 pages. $7.50.

MAX CASPAR'S long biography of Johannes Kepler, translated from the German by C. Doris Hellman, is a compassionate and thorough survey of the life of the great 17th-century astronomer. Starting with an excellent introductory account of the religious turmoil of the period, the book traces the life of Kepler from his childhood in Weilderstadt to his death at Regensburg in 1630.

Intricately detailed and always sympathetic to the central character, this is probably the most authentic picture of Kepler yet drawn. The author's scholarship and confessed love for the astronomer result in an extremely penetrating yet readable history of a genius tormented by the conflicts of his time.

Following the introduction, the book is divided into five chronologically arranged sections and a concluding comment. "Childhood and Youth 1571-1594" is concerned with the development of the young Kepler as he prepares for the ministry. A verbal portrait of his family and the faculty at his university gives the reader a comprehension of some of the forces that were to drive the man relentlessly toward his goal, despite ill health, family upheaval, church disputes, and wars.

The next two sections, "District Mathematician and Teacher in Graz 1594-1600" and "Imperial Mathematician in Prague 1600-1612," trace the triumphs and failures of Kepler's early manhood, through the publication of the first two of his three immortal laws of planetary motion. His tumultuous association with Tycho Brahe, his unending financial difficulties,

The 4¼" De Luxe VERNONscope

Read These Ultimate Features:

★ 4¼" pyrex parabolic mirror, f/10, ground and polished to better than ⅛ wave, aluminized and overcoated with quartz for maximum optical protection, guaranteed to perform to Dawes' astronomical limit of resolution.

★ NEW, rugged PAR Jr. Equatorial Mount, designed to give utmost rigidity at the points of greatest stress (note tapered aluminum housings). Includes latitude adjustment, large knurled locking screws and close-tolerance machined bearings with ¼" chrome-plated precision-ground steel shafting. Base of mount is fully rotatable for altazimuth viewing and can be quickly disassembled from the tripod. Steel legs fold for easy portability. Mount has black primer and 3-dimensional space-blue marbleized finish.

★ Seamless aluminum tube, blackened inside, with 3-D space-blue finish.

★ Finest 14-mm. wide-angle Kellner eyepiece and Barlow lens mounted in black-anodized tubing, giving magnifications of 80x and 160x.

★ New achromatic-type 4x finder with crosshairs and adjustable mounting bracket.

★ Smooth, precision helical focusing unit permits micrometer accuracy to give sharpest images possible.

★ Machined aluminum end caps and adjustable mirror mounting.

★ Covers for all optical components.

★ 44-page telescope operation manual included.

4¼" VERNONscope $79.50

Shpg. wt., 25 lbs. f.o.b. Candor, N. Y.

Telescopes are completely assembled, thoroughly tested, and correctly aligned before leaving the factory. They are carefully packaged to insure safe shipment.

We unconditionally guarantee the 4¼" VERNONscope to be exactly as described and illustrated, and to surpass even your greatest expectations, or return it within one month and your money will be immediately refunded. VERNONscope & Co. is the sole manufacturer of the 100%-American-made 4¼" VERNONscope, selling to our customers direct from the factory. Send your order today for immediate delivery.

VERNONscope & Co.
Candor, New York

and his troubles with authority, although important factors in the development of his character, are seen to have little or no effect upon his keen intellect and scientific curiosity.

"District Mathematician in Linz 1612-1626" pictures one of the darkest eras of Kepler's life and one of his greatest triumphs. The pervading misery of his mother's trial for witchcraft is vividly portrayed as Caspar describes the idiocy of the proceedings, and the tribulations they brought to Kepler. The publication of his third or harmonic law and the studies in music that preceded it are equally well handled.

The last four years of an ill and tired old man are depicted in the fifth section. Although still active in mind, Kepler was failing in health. Denied the sacraments of his church, he clung steadfastly to his faith, and finally was buried in the churchyard in front of Peter's Gate in Regensburg.

Professor Caspar points out that, because of impending invasion, the townspeople plowed up the cemetery to make fortifications, shortly after Kepler was laid to rest. "Thus, but a few years after his death, the resting place of his bones was no longer known. Tycho Brahe's grave is in the Tyn church in Prague, Galileo is buried in the venerable church of Sante Croce in Florence, Newton rests among the great dead in Westminster Abbey. Veneration for genius erected these worthy monuments. But no tombstone covers the place where the no less gifted Kepler was interred. It is as though the fate, which in life gave him no peace, continued to pursue him even after death."

Thus Caspar pictures the genius fighting a losing battle, but still persevering to make far-reaching scientific contributions. The last part of the book is a final comment upon the life and works of the astronomer during his 59 troubled years.

The author effectively dispels the erroneous notion that Kepler's astrological activity removes him from the realm of the true scientist. Kepler did not believe in his own astrological predictions, but published them only for the needed income they produced. This is clearly shown in many places in his writings, where the astronomer urges his patrons to disregard astrology when making important decisions.

The fact that Kepler delved into the false sciences is further excused by the temper of the times. As Caspar says: "One who looks about in that departed era of writing and printing is astonished at the flood of astrological, alchemical, magical, cabbalistic, theosophic, mock mystic and pseudoprophetic writings which held the intellects in a spell."

This volume is unfortunately printed in small type that is rather difficult to read. Undoubtedly, the length of the material forced a choice between an excessively bulky book and diminutive print. Shortening the text would have seriously weakened the completeness of description and documentation that are among its finest features.

Sir Isaac Newton once said that if he saw farther than other men, it was because he stood on the shoulders of giants. Without doubt, one of those giants was Johannes Kepler, and his biography by Max Caspar befits his stature.

RAYMOND N. WATTS, JR.
Longway Planetarium
Flint, Mich.

ASTROPHYSIQUE GENERALE

J. C. Pecker and E. Schatzman. Masson et Cie., Paris, 1959. 756 pages. 130 NF.

FRENCH TEXTS on astrophysics at the college level are few and far between. The previous work of similar scope, *Astrophysique* by J. Bosler (1928), was primarily descriptive. It covered much the same ground and had about the same elementary level as the standard American textbook of Russell, Dugan, and Stewart.

In *Astrophysique Générale*, two well-known French astronomers have joined forces to write a comprehensive, up-to-date treatise on modern astrophysics for the student with a good background in physics and mathematics (about two or

Astronomy Teaching Aids

ESSCO Publications

Teachers of astronomy, both amateur and professional, will find the following ESSCO study materials useful in their classrooms. The test charts are challenging fun for the amateur astronomer, too!

SC1	Equatorial constellation chart — with star designations
SC1T	**Test** equatorial chart — **without** star or constellation names
SC2	Circumpolar constellation chart — with star designations (new large size)
SC2T	**Test** circumpolar chart — **without** star or constellation names (new large size)
SS08A	Ecliptic-based star map — with equatorial grid and names
SS08	Ecliptic-based star map — with equatorial grid, **without** names
SS08B	Ecliptic star map list — positions and magnitudes for 224 stars
SS05	Nine-inch protractor on paper — for planet orbit drawings
SS11	Inner planet chart — orbits of Mercury, Venus, Earth, Mars
SS12	Outer planet chart — orbits of Mercury to Saturn
SS01A	Special rectangular co-ordinate paper — for star maps
SS02	Polar co-ordinate paper — for circumpolar star maps

Price for each item listed above: 1 to 9 sheets, 10 cents each; 10 to 24 sheets, 8 cents each; 25 to 99 sheets, 6 cents each; 100 or more, 5 cents each.

From Stetson's *Manual of Laboratory Astronomy*, the chapter "Star Chart Construction" is available as a separate booklet, at 50 cents per copy.

SPECIAL: DC5 — Large wall chart of the Draper spectral classes, printed in four colors and mounted on canvas. Limited quantity. (Slightly damaged along edges.) **$14.00 each**

SKY PUBLISHING CORPORATION
Cambridge 38, Massachusetts

YOUR TELESCOPE IS NO BETTER THAN YOUR ABILITY TO FIND THE THINGS YOU WANT TO SEE

Now — for the first time

An entirely practical solution to the amateur's biggest problem. Now you can find celestial objects with an ease, speed, and accuracy never before approached.

To find any object you must know the sidereal time and **ACCUSTAR** will give it to you instantly. Having already set the outer disk to your longitude, turn the inner disk until your clock (standard) time mark coincides with the date. The sidereal time is then indicated on the inner dial. It's as simple as that. Consistently accurate within two minutes or less.

ACCUSTAR will do many things: tell precisely where any star or constellation will be at any time or place, determine longitude, tell the solar time with one simple observation easily made with **ACCUSTAR.**

ACCUSTAR and the book, *Find the Stars*

$9.75

A precision instrument, blue and gold in color, 10 by 12 inches, plastic coated, metal backed, weighs less than a pound. Nothing to get out of order. The 56-page book *Find the Stars* has 23 sky maps and needed information on over 250 celestial objects of prime interest to the amateur.

ACCUSTAR will be your indispensable guide to the heavens and multiply your pleasure in exploring them. Place your order now.

ACCUSTAR **P. O. Box 2806, Detroit 31, Michigan**

Perfect companions for your observing program

Here, in these two Skalnate Pleso Observatory publications, is provided most complete information on celestial objects to find with your telescope. Together they make ideal companions for your serious observing projects.

DE LUXE ATLAS OF THE HEAVENS and the ATLAS COELI CATALOGUE

Both by Antonin Becvar and his coworkers at the Skalnate Pleso Observatory

The **De Luxe Atlas of the Heavens** has 16 sturdily bound charts, which cover the entire sky to magnitude 7.75. Printed in many colors, more than 35,000 celestial objects, including over 100 radio sources, are plotted on the large 16½-by-23-inch maps. You'll find double, multiple, and variable stars; novae, clusters, globulars, and planetaries; bright and dark nebulae; the Milky Way and constellation boundaries. Bayer-letter and Flamsteed-number designations are given. The transparent grid overlay facilitates locating the object under study. An atlas without equal!

The **Atlas Coeli Catalogue** (*Atlas Coeli — II. Katalog 1950.0*) is the most complete check list of celestial objects ever offered the amateur observer. Listed, with descriptive data, are the 6,362 stars brighter than magnitude 6.26, with their right ascensions and declinations for 1950, precessions, proper motions, magnitudes, and spectra; 293 open star clusters; 100 globular clusters; 240 bright diffuse nebulae; 144 planetaries; 1,131 galaxies; some 1,750 visual double and multiple stars; and 633 variables bright enough for amateur observing. Sturdily cloth bound, this 367-page book is 8¼ by 11¾ inches in size. Explanations in English.

De Luxe Atlas of the Heavens **$9.75**

Atlas Coeli Catalogue **$8.75**

SPECIAL: Both of these items **$17.50**

OTHER ATLASES

Field Edition Atlas of the Heavens. Each chart is reduced from the original Atlas Coeli and is printed on heavy, stiff paper 18 by 12¼ inches. Stars are white on black background. The 16 charts are unbound. Perfect for outdoor use. **$4.00 each; 2 for $7.50**

Norton's Star Atlas. This famous star atlas and reference handbook covers the whole heavens, showing over 9,000 objects: stars to magnitude 6½, nebulae, and clusters. Descriptive lists of 500 interesting subjects for viewing with small telescopes, and useful data for observing the sun, moon, and planets. New 14th edition, 1959. 8½ by 11 inches. 108 pages. **$5.25**

Popular Star Atlas. A simpler version of Norton's *Star Atlas*, the 16 bound maps show all stars down to magnitude 5½. 7½ by 9½ inches. 38 pages. **$2.00**

Atlas Eclipticalis 1950.0. A bound set of 32 charts, each 17½ by 24 inches, covers declinations between +30° and −30°, complete to magnitude 9.0, scale two centimeters per degree, epoch 1950.0. (Place your order with us and allow time for its transmission to the publisher in Czechoslovakia, from whom the atlas will be shipped directly to you.) **$17.00**

BOOKS FOR THE AMATEUR

Larousse Encyclopedia of Astronomy. By Lucien Rudaux and G. de Vaucouleurs. The long-awaited English translation of this monumental volume — one of the most complete and best-illustrated compendiums of astronomy ever offered in one book. Many full color renditions. Full-page size is 8 by 11⅛ inches. 506 pages, 818 illustrations. **$12.50**

The History of the Telescope. By Henry C. King. A full account of the development of the telescope from the crude instruments of the ancients to the giants of today. "An inspiring story of human progress. . . ." 7½ by 10 inches, 456 pages, 196 illustrations. **$7.50**

Making Your Own Telescope. By Allyn J. Thompson. Join the tens of thousands of amateurs who are using this basic book on telescope making. Complete step-by-step directions for making and mounting your own 6-inch reflecting telescope at low cost. In easy-to-understand chapters, you learn how to grind, polish, and figure the mirror, and how to make an equatorial mount that will provide a sturdy, solid support for your mirror. 211 pages, 104 illustrations (6th printing). **$4.00**

PHILIP'S PLANISPHERE

The latest edition of this world-famous star finder, suitable for use within 10 degrees of latitude 42° north. Beautifully printed in dark blue and gold, it identifies the principal constellations and stars above the observer's horizon for any time of the night throughout the year. It is set quickly by turning the transparent plastic overlay around its central pivot, which is at the pole of the star chart on the substantial cardboard base plate. Directions for using the device are given in four languages. **$3.00**

MAPS AND CHARTS

Color Map of the Northern Heavens. This informative and colorful wall chart is a huge 30 by 34½ inches, and shows the northern sky to −45° on a polar projection. Each star is colored according to its spectral class. Stars brighter than magnitude 5.1 included. Mailed unfolded. **$1.00**

Color Charts of the Moon. Two striking renderings of the first- and last-quarter moon. Each lunar half is an impressive 27 inches in diameter; the over-all size of the chart is 23 inches wide by 33 inches high. Printed in predominantly gold and black on heavy paper. Charts mailed unfolded. **$2.00 per set of 2**

Elger's Map of the Moon. The moon chart itself is 18 inches high by 17½ inches wide and identifies all the important lunar features. Below the map are notes by H. P. Wilkins on 146 of the more interesting regions. Mailed unfolded. **$3.00**

Lunar Map. In two colors and over 10 inches in diameter, the map identifies the most important features on the moon, including 326 mountains, seas, and craters. Handy finding list on reverse side. **25c each; 3 or more, 20c each**

CELESTIAL PHOTOGRAPHS

Splendors of the Sky. A 36-page large picture booklet, with short and easy-to-understand captions. Among the many full-page illustrations, taken with the giant telescopes of Mount Wilson and Palomar Observatories and Lick Observatory, are a close-up view of the moon's surface, and a field of distant galaxies. 36 pages, 66 illustrations, paper bound. Now only **50c**

Moon Sets. 18 pictures of the entire visible face of the moon, made from unsurpassed Lick Observatory negatives of the first and last quarters. Each print 8½ by 11¾ inches. Key charts supplied. **$3.00 per set**

Lunar Crescent Sets. 10 Lick Observatory pictures that form a matching series to Moon Sets, but for the waxing crescent 4½ days after new moon, and the waning crescent about five days before new moon. **$2.50 per set**

Sky Sets I. 24 pictures of objects in the solar system and in the Milky Way, all celestial wonders of interest and beauty. Each print 8½ by 11¾ inches. **$4.00 per set**

Sky Sets II. 24 pictures of nebulae in our galaxy, portraits of other galaxies, many made with the 200-inch telescope, and four drawings of the 200-inch telescope by Russell W. Porter. Each print 8½ by 11¾ inches. **$4.00 per set**

OTHER SKY PUBLICATIONS

SOUTHERN HEMISPHERE CONSTELLATIONS. By Sir William Peck. 12 star maps for latitude 40° south. **$2.50**

RELATIVITY AND ITS ASTRONOMICAL IMPLICATIONS. By Dr. Philipp Frank. **75c**

HOW TO BUILD A QUARTZ MONOCHROMATOR for Observing Prominences on the Sun. By Richard B. Dunn. **50c**

THE STORY OF COSMIC RAYS. By Dr. W. F. G. Swann. **75c**

Write for free descriptive catalogue. All items sent postpaid. Please enclose your check or money order.

SKY PUBLISHING CORPORATION Harvard Observatory Cambridge 38, Massachusetts

three years at the college level). Although the book is based on the authors' lectures to astronomy undergraduates at Clermont-Ferrand and Paris universities, much material has been added and the treatment so developed that some parts will be most valuable to the graduate student. The reviewer is not aware of a treatise of similar scope and level in the English language. It is no small feat for two authors to be able to cover competently such a wide range of topics.

The book has five parts: basic physical notions (100 pages), instruments and techniques (135), stellar physics (120), stellar systems (155), sun and solar system (105). There is a useful notation index (four pages) and a good name and subject index (15). Each chapter is followed by a substantial bibliography with brief comments. There are 396 illustrations, mainly graphs and sketches, with rather few photographs. There is a total of 303 tables of numerical data, a remarkable compilation of valuable information.

The first part is a compact but well-organized summary of fundamental ideas in statistics, classical mechanics, hydrodynamics, spectroscopy, and the theory of energy exchanges and statistical equilibrium between radiation and matter. It is well up to date (including, for example, sections on magnetohydrodynamics and on synchrotron radiation), perhaps occasionally at the expense of classical subjects of practical importance to the astronomy student (such as the method of least squares, also molecular spectra).

Part 2 is primarily a digest of standard French texts on classical instruments and techniques of observation, discussing such subjects as atmospheric absorption, photometry, spectroscopy and spectrophotometry, optical telescopes, receivers, accessories, mountings, and domes. Here the treatment is elementary and essentially descriptive. Despite some mention of radio telescopes and interferometers, birefringent filters and rockets, these chapters show the French astronomical instrumentation of a decade or two ago rather than of the present. A serious effort of revision and updating is needed here.

Part 3 forms the core of the book, covering the fields of special competence of the authors: stellar atmospheres (Pecker) and stellar interiors (Schatzman). This is reflected in the development accorded to many details. After a survey of the empirical classification of stellar spectra, their interpretation by the physical theory of stellar atmospheres is worked out. The radiation transfer problem, the computation of model atmospheres in gray and nongray cases (with one of the few numerical examples in the book), the formation of spectral lines and line profiles (including rotation, turbulence effects) are clearly explained. Departures from local thermodynamic equilibrium, convection zones, coherent and incoherent scattering are then discussed, and applications made to the determination of temperatures and abundances (curve of growth). An appendix gives additional details and numerical data useful in the theory of stellar atmospheres.

This is followed by a descriptive chapter on stellar distances, the H-R diagram, and the mass-luminosity relation. The section on double stars (visual, spectroscopic, photometric) and stellar masses is fairly routine, but adequate, except perhaps for the discussion of eclipsing binaries, which is too succinct and lacks a numerical example (such omissions weaken many other sections of the book).

Variable stars are considered at some length, with an outline of the theory of stellar pulsations, including shock waves (Cepheids). Types of variables are illustrated with typical light curves. The one-page discussion of supernovae is much too brief, and some statements there are not even correct.

The chapter on the internal structure of the stars (45 pages) contains an excellent presentation of the classical and nuclear physics involved, including fairly detailed treatments of the nuclear cross sections and thermonuclear reactions of interest in astrophysics. The principles of the computation of stellar models are described, followed by details of some special solar and stellar models, with ap-

Astronomical

featuring our

SPACE K-4 DELUXE

TELESCOPES

by SPACEK INSTRUMENT CO.

COMPLETELY ASSEMBLED — READY TO USE

- **Optical system:** 4¼-inch mirror, f/11, spherically corrected with surface accurate to ⅛ wave, aluminized and quartz over-coated.
- **Mounting:** Equatorial and adjustable for latitude. Massive aluminum castings with 1-inch-diameter shafting on both axes and Tensalloy bearings. Clamps provide any degree of tension desired. Two lock-nuts on saddle permit simple removal of tube. All steel parts chrome plated and carefully machined to give maximum rigidity.
- **Tube:** Seamless aluminum, painted black inside, with hammer-tone green finish.
- **Rack-and-pinion focusing:** Accommodates standard 1¼-inch eyepieces.
- **Finder:** 6 power, with achromatic objective, and mounted in adjustable bracket.
- **Pedestal:** Heavy-wall steel tube with collapsible legs. Guaranteed free from torque and wobble. Design allows tube to be swung in any position without bumping into legs. Pedestal, mount, and legs painted black crinkle finish.

$98.50

- **Three eyepieces:** 50x Kellner, 100x and 200x Ramsdens.
- **Instructions.**
- Send for new 16-page catalogue.

WANTED
Professional and Amateur Astronomers

Put your ideas and experience to work. Extensive expansion program by Spacek Instrument Co. requires individuals with a knowledge of telescopes, optics, and astronomy.

Proven design, low cost, and excellent performance of our SPACE K-SERIES telescopes have met with the approval of many schools, observatories, and clubs.

Here is an excellent opportunity for responsible persons, who are interested in supplementing their incomes, to demonstrate and sell our telescopes.

Write for complete information about our Individual Dealer Plan.

OUR NEW K-4 DELUXE KIT!

Assemble the K-4 Deluxe yourself and save almost $30.00. Shipped with all optics mounted and collimated, with interior of aluminum tube painted black. All parts carefully machined and ready for assembly. No special tools required. Three complete eyepieces included. Same fine quality as in our regular K-4 Deluxe illustrated above. Complete with all hardware and full instructions.

$79.50

All prices are f.o.b. Pottstown, Pa.
Pennsylvania residents add 4% sales tax to all prices.

All prices subject to change.
DEALER INQUIRIES INVITED

SPACEK INSTRUMENT CO.

1130 Sembling Ave.
Pottstown, Pa.
Telephone: FAculty 3-2825

THE MARK III

Sidereal Telescope Drive

Bodine Synchronous Motor, Automatic Clutch, Automatic Sidereal Time Circle requiring no calculation for location of objects, R.A. Indicator, Sidereal Time Indicator, Lifetime Quality, Precision Fabrication.

Ramsden Eyepieces
Declination Circles
Hour-Angle Circles

Write for price list.

H & W OPTICAL CO.
654 Milwood Ave., Venice, Calif.

DE LUXE

SKYSCOPE

As illustrated — with new plastic tube, 6x finder, heavy all-metal tripod, equatorial mounting, and 60x eyepiece.

Price **$44.75**

Unconditionally guaranteed.
100% American made.

Write for free brochure showing our standard model which has been sold world-wide for over 20 years. Skyscope still remains outstanding in value by any comparison.

THE SKYSCOPE CO., INC.
P. O. Box 55S, Brooklyn 28, N. Y.

✓ Astronomers
✓ Navigators
✓ Satellite Observers

PLOT STARS - TRACK SATELLITES



This transparent, 30" graphic computer simulates rotation of the earth with respect to the sun and stars. 20 First-Magnitude navigational stars and the sun's diurnal motion are preplotted. The user can plot and predict the apparent motion of any star for which he knows Right Ascension (SHA) and Declination. "Great Circle" curves permit the predicting and plotting of satellite positions (both relative and absolute).

Determine star and satellite positions for any given time - past, present, or future - from any earth location, in either Northern or Southern Hemisphere.

Determine celestial horizon, time of sunrise, time of sunset, for any location on earth and any day of year.

NAVIGATORS - PREP CELESTIAL NAVIGATION FIXES AND USE MARK I TO CHECK LINE-OF-POSITION CALCULATIONS

MARK I - $ 4.95
by BEKR, Box 8041, Mpls. 16, Minn.

BEKR, Box 8041, Minneapolis 16, Minnesota

Send ___ Mark I (s) complete with plastic marker and 30-page instruction booklet at $4.95 each.
Enclosed is $ _____. BEKR pay postage.
Send C.O.D. I'll pay postage and C.O.D. charge.

The latest
Spitz MODEL A-2
PLANETARIUM
has been installed at
Rock Creek Nature Center
Washington, D. C.

★

Spitz Laboratories
Inc.
YORKLYN, DELAWARE
Phone: CEdar 9-5212

plications to evolution problems. The white dwarfs are touched upon, while hydrodynamic and stability problems are developed at some length.

Part 4 opens with a descriptive account of stellar motions and distribution, with remarks on clusters and associations, leading to the determination of the direction of the galactic center and separating the various stellar subsystems. The derivation of space densities from star counts is accorded only two pages, resulting perhaps from a strong reaction against the emphasis placed on the subject by astronomers of the previous generation.

Stellar kinematics and dynamics are then adequately treated in two chapters (30 pages), including both classical and modern problems, such as the stability and structure of star clusters and associations, and the mapping of H-I arms through the application of the theory of differential rotation of the galaxy to 21-centimeter observations.

The following section is a return to problems of stellar evolution, incorporating the evidence from galactic clusters, the luminosity function, and miscellaneous other data (stellar rotation, abnormal abundances). Questions related to element formation and abundances (novae, supernovae) are not explored, however.

The important problems of interstellar matter are presented in a chapter of 45 pages, which begins with a brief survey of statistical methods (Wolf diagrams, fluctuations in galaxy counts and in sky brightness). The observations and theory of interstellar absorption, scattering and polarization, and the physics of emission nebulosities are then discussed in more detail, including brief sections on continuous and 21-cm. radio emission.

A final chapter reviews classical and current ideas on galaxies and cosmology. Here the treatment of the empirical data is rather sketchy and occasionally inaccurate. As far as it goes, the brief survey of cosmologies is better, but fails even to mention the steady-state theory.

Part 5, reflecting happily the special interest of one of the authors, concerns the sun: energy distribution, limb darkening, solar models, chromosphere and corona, magnetic and hydromagnetic effects. There is a good chapter on sunspots and solar activity and another on solar-terrestrial relationships.

By contrast, the final section, on planets and minor bodies of the solar system, is disappointing. A few points, such as the theory of surface temperatures, escape of atmospheres, internal structure, are briefly outlined; but the discussion of individual objects is almost nonexistent (Venus, six lines; Mars, 10; zodiacal light, 12). Some will think that in this space age the neglect is unfortunate.

All in all, *Astrophysique Générale* is a major and successful effort to provide students with a good grounding in most of the fields of astrophysics active during the past two decades. One hesitates to criticize such a courageous undertaking. However, if a general appraisal must be made, it is that the book reflects a little too clearly, if understandably, the fields of special interest and competence of the authors, at the expense of other important subjects where the compilation was obviously hasty and uncritical. There should therefore be a thorough revision and rewriting of several chapters, especially if the book were to be translated into other languages.

It is, of course, almost impossible to achieve perfection in the first edition of a book of this size and scope, so it would be pointless to record here the several dozens of minor errors and misprints

new
PRODUCT RESEARCH and DEVELOPMENT

The ALL NEW ASTRO-DOMETTE

We have developed Astro-Domettes with high schools, junior colleges, and the serious amateur astronomer in mind. These units are fabricated on an assembly-line basis, resulting in high quality yet modest cost. Because the sections are stamped or molded, dome components are uniform and interchangeable. The result is an Astro-Dome that every owner will be proud to use and display. In the space age, progressive schools will want to include this new aid to education in their science department. The Astro-Sciences encourage young people to enter fields of science and engineering. The well-informed and well-equipped student of today is the scientist, technician, and engineer of tomorrow.

Astro-Domettes are fabricated and shipped in large preassembled sections. Each Astro-Domette is equipped with an "up-and-over" shutter system and is manually rotated. Electric drives are available as an accessory. Astro-Domettes are of lightweight construction, strong and durable because of their new design. Astro-Domettes of molded fiberglass have metal tracks and come in outside diameters of 8, 10, and 12 feet, each with a one-foot cylindrical section around the base of the hemisphere. A 10-foot fiberglass Astro-Domette weighs about 500 pounds, the other sizes in proportion.

ASTRO-DOMETTES are available in pastel colors

Serving the Astro-Sciences

ASTRO-DOME INCORPORATED

MANUFACTURERS OF ASTRONOMICAL OBSERVATORY DOMES

1801 BROWNLEE AVE. N. E. CANTON 5, OHIO Phone GL. 6-8361

FIRST STEP TO FINER PERFORMANCE!

Easy, Low-Cost Way To Enjoy Thrills Of Astrophotography

Convert your present 35-mm. camera with this new adapter

Developed by Criterion especially for single-reflex 35-mm. cameras with interchangeable lens. Simply remove present lens mount and add this precision-made achromatic lens that adapts camera to eyepiece of any telescope — refractor or reflector. When ordering, *be sure to specify make of your camera.*

For 35-mm. cameras with SCREW-TYPE lens mount
Cat. #CPA-36 for 1¼" eyepiece holders..**$19.00**
Cat. #CPA-37 for 4" standard Dynascopes ..**$17.50**

For 35-mm. cameras with BAYONET-TYPE lens mount
Cat. #BPA-36 for 1¼" eyepiece holders..**$22.50**
Cat. #BPA-37 for 4" standard Dynascopes ..**$21.00**

New!

Dyn-o-Astro 35-mm. Camera

at less than regular price of camera alone!

No need to be an expert photographer to take exciting astrophotos with this *single-reflex*-type, precision-made 35-mm. camera. No complicated settings. No plates or filmholders to load and unload. No worries about missing target. Large focusing screen shows you *exactly* what you are shooting, right up to moment you take the picture. Includes such advanced features as:

— No accidental double exposures. Winding knob automatically advances film, positions mirror, winds shutter, counts exposures.
— Dual-speed setting knob controls both fast and slow shutter speeds. Color coding makes mistakes impossible.
— Integrated magnifier for critical focusing even on dim objects.

Takes time exposures and also has speeds up to 1/500 second. Guaranteed for 2 years. Complete, ready for use.

Model CP-35 fits 1¼" eyepiece holder **$89.00 postpaid**

Model CP-36 fits all standard 4" Dynascopes **$85.00 postpaid**

Dyn-o-Swing Camera Support

fits any 4" or 6" telescope without drilling!

Takes guesswork out of astrophotography by providing *precise centering* of camera over eyepiece. Smooth rack-and-pinion adjustment. Easily attached or detached from tube, with rigid clamp for maximum stability. Special arm lets you swing camera away from eyepiece for visual observation, with instant return for photographing. Can be used with almost any camera. Postpaid.

Cat. #CS-4 to fit all 4" Dynascopes..... **$17.50**
Cat. #CS-47 to fit all 4¼" O.D. tubes.. **$18.95**
Cat. #CS-67 to fit custom 6" Dynascope and 7¼" O.D. tubes..... **$19.95**

Catalog F, describing other accessories and parts, cheerfully sent on request. Satisfaction guaranteed, or money refunded. All items sent postpaid. We pay all postage costs. No shipping, crating or packing charges. Send check, cash, or money order for immediate delivery.

Paraboloidal Mirrors

The most important part of a reflector telescope is the precisely figured mirror. A mirror with a spherical surface suffers from spherical aberration, so it must be altered to a paraboloid to focus all the light rays in each bundle to the same point. Considerable skill is required to parabolize a fine mirror properly. Criterion Custom mirrors are made of the best pyrex glass, selected for freedom from internal stress and strain, and of the correct thickness for each size, parabolized by craftsmen and tested by Ronchi and Foucault tests, as well as by diffraction rings and resolution of double stars. They are aluminized and overlaid with zircon quartz. Each is guaranteed unconditionally, and to perform to the limit of resolution for its size.

4" pyrex, f.l. approx. 40"	**$31.00**
6" pyrex, f.l. approx. 54"	**$45.00**
8" pyrex, f.l. approx. 64"	**$89.00**
10" pyrex, f.l. approx. 80"	**$179.00**
12" pyrex, f.l. approx. 96"	**$275.00**

A tolerance of 5% in focal length is customary. A deposit of ⅓ is required with orders for 8" to 12" mirrors.

Rack-and-Pinion Eyepiece Mount

The most mechanically perfect focusing is by rack and pinion. This mount takes standard 1¼" eyepieces. Full 3½" of travel — more than ever before. Accommodates almost any type of eyepiece — positive and negative. Two knurled focusing knobs, variably tensioned and positioned. Solid cast-metal sliding brass tube — close tolerance prevents looseness. Mount aligns itself to any type tube. Four mounting holes, nuts and bolts included. Eye mount has square-rod-type diagonal holder which prevents loose alignment and vibration. Rod tempered to minimize temperature changes. Adjustable for 5" to 8" scopes, also 12" scopes if so specified at no extra cost. Order one or more of the complete eyepieces described below at the same time you send for this rack-and-pinion device, which accommodates any of our eyepieces perfectly.

Cat. #SU-38 **$7.95 postpaid**

New Model Eyepiece Mount

Same features as above but has wider base that is contoured to match the curve of a 7" to 8" diameter tube. Makes professional appearance. Furnished without Diagonal Rod #SU-9R **$9.95**

Diagonal Rod — Cat. #SU-9R..... **$1.00**

Reflecting Telescope Mirror Mounts

Mounting the mirror to your scope correctly is most important. Criterion mounts are especially well designed, and are made of cast aluminum with brass mounting and adjustment screws. One section fits tube, other section holds mirror. Alignment accomplished by three spring-loaded knurled adjusting nuts. Outer cell designed to fit into or over your tube. Sufficient space left between the two cells. All drilled and tapped. Complete with holding clamps, springs, nuts, etc. Ready for use. Will prevent vibration and hold alignment once set. Will hold mirror without distortion of surface figure.

3".....	**$3.00**	6".....	**$6.00**
4".....	**3.50**	8".....	**12.50**
5".....	**4.00**	10".....	**14.75**

Complete Eyepieces

Finest quality. They are precision machined, mounted in standard 1¼" outside diameter barrels. Can be taken apart for cleaning. Designed to give sharp flat field clear to edge.

Huygens 18-mm. f.l. (¾")	**$ 7.50**
Kellner 9-mm. f.l. (⅜")	**7.90**
Kellner 7-mm. f.l. (9/32")	**8.50**
Kellner 12.7-mm. f.l. (½")	**9.50**
Kellner 18-mm. f.l. (¾")	**9.50**
Kellner 30-mm. f.l. (1-3/16")	**12.50**
Orthoscopic 6-mm. f.l. (¼")	**12.50**
Orthoscopic 4-mm. f.l. (5/32")	**14.50**

Revolving Turret

The Criterion Revolving Turret holds three eyepieces so that, as desired, the power of the telescope can be changed by merely turning the turret to a different ocular. Click stop insures positive and accurate positioning of each eyepiece. Turret holds eyepieces of standard 1¼" outside diameter. Fits into the holder of any refractor or reflector telescope that uses 1¼" eyepieces. Requires no alteration or adjustment and can be attached as easily as putting eyepiece into scope. Made of brass and aluminum with polished chrome-plated barrels.

Cat. #SRT-350..... **$14.50**

Achromatic Finder Scopes

Two models: 6x, 30-mm., and 10x, 42-mm. Coated achromatic air-spaced objective, crosshairs, built-in duraluminum tube finished in white enamel, dewcap. Sliding focus adjustment. Can also be used as excellent hand telescopes for wide-field views of the sky. Fit Mount Bracket #SF-610.

6 x 30 Achromatic Finder	**$12.50**
10 x 42 Achromatic Finder	**$18.00**

Wide-Angle Erfle Eyepiece

Our 16.3-mm. Erfle wide-angle eyepiece has a 75° field. Astonishing wide-angle views. Coated. Highest precision and specifically designed for telescopic use. Chrome barrel. Guaranteed to be superior in every respect.

Cat. #SE-63 — 1¼" O.D.	**$18.50**
Cat. #SE-62 — 0.946" O.D.	**$16.50**

Four-Vane Diagonal Holders

Criterion 4-vane diagonal mountings are fully adjustable, will hold elliptical diagonals in perfect alignment. Made of brass, chemically blackened. Precision adjusting screws center flat and vary its angle so that primary and secondary mirrors can be set in perfect alignment. Thin vanes with special adjustable studs.

Cat. #	Minor-Axis Size	For Tubes	Price
S-51	1.25"	6½" to 7½"	**$10.00**
S-52	1.30"	6½" to 7½"	**10.00**
S-53	1.50"	8½" to 9½"	**10.00**
S-54	1.75"	9½" to 10½"	**12.50**
S-55	2.00"	11" to 11½"	**14.95**
S-56	2.50"	Specify tube I.D.	**19.95**

CRITERION MANUFACTURING CO.

Manufacturers of Quality Optical Instruments

Dept. STP-23, 331 Church St., Hartford 1, Conn.

noticed in a first reading. Also, captions of figures and references are often incomplete, sometimes incorrectly given, and require checking.

As the book is clearly destined to run through several editions and to become a standard text, the authors should have ample opportunity to polish up this valuable work, for which they certainly deserve the congratulations and gratitude of teachers and students.

G. DE VAUCOULEURS
Harvard Observatory

NEW BOOKS RECEIVED

ASTRONOMISCH-CHRONOLOGISCHE TAFELN FUR SONNE, MOND UND PLANETEN, *Paul Ahnert,* 1960, *Johann Ambrosius Barth,* Salomonstr. 18B, Leipzig C1, East Germany. 93 pages. DM 10.20, paper bound.

Astronomical and Chronological Tables for Sun, Moon, and Planets furnishes the means of calculating the approximate positions of solar system bodies for any selected date, using only simple arithmetic. These tables begin with 3001 B.C. for the sun and moon, and with 1501 B.C. for the planets Mercury through Saturn, extending to A.D. 2499 in each case.

Dr. Ahnert's publication can also be used for finding the dates of planetary phenomena, and of full and new moon. In addition, the approximate circumstances of eclipses can be calculated with its aid. The 42-page explanation of the use of the tables is in German.

THE OSCILLATING UNIVERSE, *Ernst J. Opik,* 1960, *Mentor Books.* 144 pages. 50 cents, paper bound.

Despite its title, this book is mainly an up-to-date account of the nature of solar system bodies. Popularly written, it contains the views of a professional astronomer whose special field is the planets and meteors.

PROPERTIES OF DOUBLE STARS, *Leendert Binnendijk,* 1960, *University of Pennsylvania Press.* 349 pages. $12.50.

A staff member of Flower and Cook Observatory presents a survey of the methods of modern double star astronomy. Successive sections deal with photographic measurements employing long-focus refractors, visual double stars, spectroscopic binaries, and eclipsing variables. The emphasis throughout is on the mathematical bases of observing techniques and orbit determinations.

AL-BIRUNI ON TRANSITS, *al-Biruni,* 1959, *American University of Beirut.* 201 pages. 6.25 Lebanese pounds.

This is a translation into English of a work on spherical astronomy and planetary motions, written by the Arab astronomer al-Biruni, who died in the year 1048. For historians of astronomy, it contains much valuable source material bearing on the problem of the transmission of astronomical ideas in the Near East. The translators are M. Saffouri and A. Ifram, and E. S. Kennedy has provided a commentary.

The book can be ordered at $2.00 per copy from Khayat's Bookstore, 23-24 Rue Bliss, Beirut, Lebanon.

THE MOON, *Franklyn M. Branley,* 1960, *Crowell.* 114 pages. $3.50.

Earth's natural satellite is described for teen-agers in this well-illustrated book.

U.S. SURPLUS BARGAINS

IN HIGH-QUALITY OPTICAL PARTS AND EQUIPMENT

BAUSCH & LOMB f/6 AERO-TESSAR LENS

Focal length 24". Completely mounted with iris and shutter. Excellent for wide-field telescope. All in excellent condition. Price **$25.00**

WIDE-ANGLE ERFLE EYEPIECE (68° Field)

Coated optics, 3 achromatic lenses. 1¼" focal length, 1-13/16" aperture. Price **$12.50**

16-mm. AERIAL GUN CAMERA, MODEL AN-N6

Takes standard 16-mm. magazine load (50'). Operates at 16, 32, or 64 frames per second. Complete with Wollensak Type V lens, 1⅜" (35-mm.), f/3.5. Excellent condition. Operates on 24-volt d.c. Price **$29.95**

METAL PARABOLOIDAL MIRROR

These are made of hastelloy hard metal. 12" diameter. 5¾" focal length. Manufactured by Bausch & Lomb. Approx. weight, 3½ lbs. Brand-new condition. (Not for telescopes.) Price **$10.00** each

7 x 50 BINOCULAR ERECTING PRISM

This is complete prism assembly which consists of two porro prisms fastened to a prism shelf. Used to give optical systems an erect image. Aperture is 1" with coated optics. Price **$2.50** each



BAUSCH & LOMB f/8 TELEPHOTO LENS

Coated lenses. Focal length 36". Completely mounted with iris and shutter. Approx. weight 25 lbs. Excellent condition. Price **$49.50**

8-DAY AIRCRAFT CLOCK

24-hr. dial and civil-date indicator. Center sweep second hand. Luminous figures and hands on black face. Case is made of black plastic. 3⅛" mounting. Manufactured by Waltham Watch Co. Price **$20.95** postpaid

8-POWER WIDE-FIELD ELBOW TELESCOPE

COATED LENSES



Field of view 8° 45'. Large focusing Erfle eyepiece. Eye lens diameter 2-1/16" with diopter scale +2 - −4. 4 built-in filters — clear, neutral, red, amber. Length 15⅜", width 6⅛", height 7¾", weight approx. 9½ lbs. Excellent unused condition. Price **$39.50**

8-POWER ELBOW TELESCOPE

2" objective; Kellner eyepiece; Amici erecting prism; 4 built-in filters; reticle illumination; field is 6° (325 ft. at 1,000 yds.). The focusing 28-mm. eyepiece allows focus from 15 ft. to infinity. Weight 5 lbs.

These were used by the government for antiaircraft. Government cost over $200.00. Price **$12.50**

5" SCHMIDT ULTRA-HIGH-SPEED OBJECTIVE LENS SYSTEM

Eastman Kodak infrared receiver, formerly known as U. S. Navy Metascope, Type B. 7" long with 5" Schmidt ultra-high-speed objective lens (approx. f/0.5). Elaborate optical system, many coated lenses. Uses two penlight batteries. Government cost, approx. $500.00. Factory-new. Shipping wt. 9 lbs. Price **$19.95**

Waterproof carrying case extra. Shipping wt., 3 lbs. Price **$3.00**

NAVY INFRARED RECEIVER, TYPE C-3



Produces visible image from infrared image in complete darkness. For seeing in dark with infrared light source. Nothing to wear out. Operates on two flashlight batteries. Has high-voltage power supply and image tube (1P23) and elaborate optical system. Weighs only 6¼ pounds and is only 11" long, 8" high, 5½" wide. Manufactured by R. C. A. Objective f/0.9 Schmidt system, 2.4" focal length, 3¼" aperture. Excellent condition, with waterproof carrying case. Price **$35.00**

INFRARED FILTERS

5⅛" diam. x ⅛" thick. Price **$2.95**



16-mm. SINGLE-FRAME CAMERA

Manufactured by Bell & Howell (200 series). 50' magazine load. Operates on 12-volt d.c. Has rotary solenoid, standard C mount, less lens and view finder. Excellent for photographing records, nature study, and so forth. Price **$35.00**

Send full amount with order. All prices, except as noted, net f.o.b. Pasadena, Calif. No C.O.D.'s, please.

C&H SALES CO. 2176 East Colorado St.
Pasadena 8, Calif. MUrray 1-7393

UNIVERSAL RACK-AND-PINION FOCUSERS

For reflectors or refractors.

Take standard 1¼"-diameter eyepieces. Specially designed base fits any tube 5" or more in diameter. Carefully machined aluminum and brass construction permits critical setting. Slotted extension tube holds eyepiece firmly and gives sufficient working distance for Barlows. $9.95 postpaid

MIRROR CELLS

Solid cast aluminum, fully adjustable, painted, complete and ready to use. Shipped postpaid.

6" mirror	cell for	7"	or larger tube	$6.75
8"	"	9"	"	8.95
10"	"	11¾"	"	15.95
12½"	"	14½"	"	20.95

PYREX MIRROR-MAKING KITS

With new velvet-finishing tools.

4¼" diameter	$5.70 postpaid
6" "	9.50 postpaid
8" "	12.25 shipped collect
10" "	21.75 shipped collect
12½" "	41.25 shipped collect

Kits include five abrasives with our special superfine finishing abrasive for superior fine grind, selected pitch, cerium oxide, pyrex mirror, and velvet-finishing tool (heat resistant, approximate hardness of pyrex). C.O.D.'s accepted.

Used telescopes, binoculars, microscopes, and optics bought, sold, or exchanged.

Write for free catalog.

NYE OPTICAL CO.

2100 Cherry Ave., Long Beach 6, Calif.

Infrared Optical Systems

Prototypes or production runs in Cassegrain or catadioptric forms — short and long focus — have been satisfactorily supplied. If you have a problem, we will be pleased to discuss it.

GLEANINGS FOR ATM's

CONDUCTED BY ROBERT E. COX

A Portable 6-inch Catadioptric Telescope

MY GREGORY-MAKSUTOV is a 6-inch f/23 instrument, yet compact and portable for such a powerful telescope. Everything but the tripod fits into a wooden carrying case and weighs a total of 69 pounds. The spherical mirror was fairly simple to make, as no parabolizing was necessary. This f/23 design gives excellent results with no aspherizing, although that extra figuring would be desirable for an f/15 instrument.

Making the corrector lens is considerably more difficult. It is no job for anyone who might be in a hurry to get a Maksutov finished for the next apparition of Mars and has yet to start grinding. The better part of a year and a half of spare time went into constructing the testing equipment and the corrector. The three instruments in the picture opposite are a radius spherometer, the jig for determining central thickness, and a jig for controlling wedge and concentricity of the lens.

It is convenient for all three of these instruments to have their own dial indicators, especially for the later stages of grinding the last surface. Here the lens is approaching its final thickness, so it is necessary to stop every few minutes and check both the radius and wedge to be sure they are within the design tolerance.

The corrector was made from an Edmund square glass blank. Grinding was done on a vertical spindle, a lead lap being used for roughing, a cast-iron one for smoothing, and tiles cemented on the cast iron for fine grinding. All polishing was performed with a Draper machine, while the optical figures were checked with a beam-splitter light source and a combination Foucault-Ronchi tester.

Since the image from the first surface (the concave one) is about four times as bright as the one from the convex surface when testing through the lens, checking for zones and smoothness would have been a problem without the suggestions of A. S. Leonard in Maksutov Club *Circular* 38. In Dr. Leonard's method, the lens is deliberately left with a 0.006" wedge between the surfaces, the central thickness a bit too great, and the front surface concentric with the rear. The first side is given a good polish and made spherical; then the rear surface is polished and tested through the first.

By arranging the lens properly on its



Gordon Konstanzer's 6-inch telescope has an extremely rigid mounting, with thrust bearings 3½ inches in diameter at the top ends of both axes. When he first observed, Mr. Konstanzer spent more time searching for objects than looking at them, so he added the finder, which has a 7-x-50-binocular objective and a 6-x-30-binocular eyepiece. The Linhof heavy-duty camera tripod was not steady enough in its original form, so aluminum struts were added, joining the top ends of the lower legs. Observing stability was greatly improved. All photographs with this article are by the author.



At the left, resting on a glass plate for setting it to zero, is the radius-measuring spherometer. The middle device was used for checking the center thickness of the lens, and the third for testing the corrector's edge.

test stand, the image from the first surface is made to fall behind the knife-edge, allowing the worker to test the rear side without interference. After this surface is finished, the front one is reground to the design radius, the wedge removed, and the central thickness reduced to its proper value.* One must produce a total of three optical surfaces on the correcting lens to employ this technique, but the extra work is not difficult. In fact, it is good experience, and in my case enabled me to obtain an excellent figure on the convex surface. Of course, great care must be taken so that the finished rear side does not get scratched while the front one is being worked.

Since the corrector had to remain in a single position during the testing of the convex surface, the lens and the lap were rotated at different speeds on the Draper polishing machine to avoid astigmatism, which might have been masked by the fixed lens position.

The telescope tube was completely machined in one lathe setting, thereby assuring perfect alignment of the corrector in its cell. The mirror is in a conventional cell with spring-loaded screws and locking nuts. Collimation of the instrument is very important, so I devised the following method for doing this. The technique is simple and accurate, provided the aluminized spot is centered perfectly on the corrector.

First, the corrector is removed and a piece of clear plastic, having its center well marked, is inserted. An 8″ length of tubing, 1¼″ in outside diameter, is put in place of the eyepiece. This tube has crosshairs at one end and a centered peephole in the other; the hole is made with a No. 50 drill, which is 0.07″ in diameter. By looking through the peephole, the crosshairs are aligned with the center of the plastic disk at the far end of the tube.

The flat in the diagonal housing is then adjusted until the crosshairs stay centered on the plastic disk for any position of the housing. The adjustment is quite easy if the flat is mounted on a piece of sheet brass held in the housing by three spring-loaded screws.

Then the plastic is replaced by the corrector. The tube is removed from the eyepiece holder and a plug with a small hole in its center is inserted in its place. The worker looks through the system at the daytime sky, and the reflection of the corrector's aluminized spot can be readily seen, unless, of course, it is already centered over the spot itself and no adjustment is necessary.

The finished instrument is superb, performing so well that my 12-inch Newtonian will probably get dusty from disuse.

GORDON KONSTANZER
2735 Milan Court
Los Angeles 41, Calif.



The telescope's carrying case is 26 by 22 inches in area, eight inches high, weighing 69 pounds when packed.

BRANDON OCULARS

These orthoscopic oculars are the choice of the amateur as well as the professional astronomer. Seven sizes available: 4-mm., 6-mm., 8-mm., 12-mm., 16-mm., 24-mm., and 32-mm. focal lengths. Standard 1¼″ outside diameter.

$15.95 each

Brandon Oculars may be purchased at —

Cave Optical Co., 4137 E. Anaheim St., Long Beach 4, Calif.

Cleveland Astronomics, Box 209, Chagrin Falls, Ohio

American Lens and Photo Co., 5700 Northwest Highway, Chicago 30, Ill.

Optron Laboratory, Box 25, D.V. Station, Dayton 6, Ohio

Adler Planetarium, 900 E. Achsah Bond Dr., Chicago 5, Ill.

Polaris Telescopic Shop, 14319 Michigan Ave., Dearborn, Mich.

—or order direct. We will ship airmail.

AVAILABLE SOON

A complete 4″ refractor telescope with all accessories. Write for details.

LIBRASCOPE P. R.

Guaynabo **Puerto Rico**

Formerly BRANDON INSTRUMENTS

TELESCOPE HOBBYISTS



TEN DAY
MONEY-BACK GUARANTEE
HOME INSPECTION
of the finest
TELESCOPE PARTS AND KITS

MIRROR MAKING KITS
Build a powerful precision telescope. Quality supplies and instructions. **$4.50 UP**
6″ PYREX KIT $9.50

HARD OVER-COATED
ALUMINIZING
6″ **$3.50** 8″ **$4.50**
Superior reflecting surface. Guaranteed not to peel or blister.
YOUR MIRROR TESTED FREE ON REQUEST.

Complete Instructions, 10c. Free Catalog.
Precision Optical Supply Co.
1001-T E. 163 St., New York 59, N. Y.

DELUXE PYREX
Reflecting Telescope Kits

Our kits have PYREX mirror blank, PYREX tool the same thickness, ample supply of optical quality abrasives, fast-polishing cerium oxide, red rouge and pitch. Packed in metal cans.

Size	*Thickness*	*Price*
4¼"	¾"	$ 6.00
6"	1"	$10.50
8"	1½"	$18.75
10"	1¾"	$33.65
12½"	2⅛"	$59.95

ADD POSTAGE: 1st and 2nd postal zones from Detroit, add 5%; 3rd and 4th, add 10%; 5th and 6th, add 15%; 7th and 8th, add 20%. Or we will ship C.O.D.

Send for free catalog of supplies, accessories, and refracting telescopes.

ASHDOWNE BROS.
18450 Grand River Detroit 23, Michigan

A Modern Telescope
for a Modern College

Astronomy plays an important role in the curriculum of Foothill College, which serves the scientific community of the San Francisco peninsula. This new California state college, insisting on the finest equipment, has selected VEGA instruments for its Astronomy Department.

VEGA 6" Maksutov $1475
VEGA 6" Reflector-Corrector $875

VEGA INSTRUMENT CO.
840 Lincoln Avenue
Palo Alto, California

Deep-Sky Observers

An extremely fine, imported Zuiho binocular with a wide field of view — 10½°!

$35.00
Tax Paid

Complete with beautiful case. Delivered anywhere in the Continental United States.

AMERICAN TYPE WIDE ANGLE
7 x 35 Central Focus

SPECIFICATIONS

Magnification, 7x. Objective aperture, 35 mm. Eyepiece aperture, 24 mm. Exit pupil, 5 mm. Field of view at 1,000 yds., 551 ft. Field-of-view angle, 10.5°. Height, 128 mm. Breadth, 195 mm. Net weight, 930 grams. Weight of pigskin case, 400 grams.

We have sold hundreds of pairs of these binoculars with the utmost satisfaction. They are unconditionally guaranteed. If not pleased, return them and your money will be immediately refunded.

Before you buy or trade a telescope or radio amateur gear, see WARD W2FEU for the best deal.

Established 1936

ADIRONDACK
RADIO SUPPLY
P. O. Box 88, Amsterdam, N. Y.
Ward J. Hinkle, W2FEU — Owner

GLASS REMOVAL IN PARABOLIZING

MOST amateur telescope makers' first mirrors have diameters of 6" and focal lengths near 48". To change such a mirror from a sphere to a perfect paraboloid involves removing approximately 0.000012" of glass from the center of the disk. The time needed to figure a mirror like this under ideal conditions can run from half an hour to two hours for the experienced ATM or carefully tutored beginner.

However, anyone who has made a 6-inch telescope with a short focal length, between 24" and 30", knows that it takes a lot of work to deepen the sphere to the desired paraboloid. Recently, a fairly experienced amateur who was working on a 12-inch mirror of 60" focus remarked he was happy that only a few millionths of an inch of glass would have to be removed to obtain the final figure. He was quite surprised when shown that the difference was very nearly 0.0001" in the center of the glass for the full correction.

The exact formula for the sagitta, **S**, of a sphere is

$$S = R - (R^2 - r^2)^{\frac{1}{2}}, \qquad (1)$$

where **R** is the radius of curvature of the mirror and **r** is the radius of the glass (its semidiameter). This formula is illustrated on page 187 of the February, 1957, issue. The approximate expression in telescope making books,

$$S = r^2/2R, \qquad (2)$$

is not the sagitta of a sphere, but actually that of a paraboloid!

It is also common practice to expand the term $(R^2 - r^2)^{\frac{1}{2}}$ by the binomial theorem, to give:

$$(R^2 - r^2)^{\frac{1}{2}} = R - r^2/2R - r^4/8R^3 - r^6/16R^5 - 5r^8/128R^7. \ldots \qquad (3)$$

In the past, only the terms through the $r^6/16R^5$ expression have been published in telescope making articles, and one would think the expansion simpler than it really is. Most telescope making literature uses the third term, $r^4/8R^3$, in one form or another, as a close approximation for the difference between a sphere and a paraboloid.

To find the exact difference between a sphere and a paraboloid, the sagitta of the sphere should be obtained in equation (1), that for the paraboloid from equation (2), and the difference between the two found. This has been done in Tables I, II, and III, the first giving the depth of a sphere, the second that of a paraboloid, and the third the difference between them.

It will be noticed that the paraboloid is shallower than the sphere, and this is contrary to the usual idea of deepening the sphere to obtain the paraboloid. In the table the two are tangent at the center of the mirror; if we move the paraboloid down by the amount of the difference, the two are tangent at the edges, the situation generally pictured.

Examination of Table III shows that the amount to be removed at the center of a 6-inch f/8 mirror in parabolizing it is 0.000012". At f/10 it is only half this amount, and at f/15 the mirror may be left spherical, as the difference is less than 0.000001" (one millionth of an inch). For a 6-inch f/4 mirror the central difference is 92 millionths.

However, in figuring a mirror we are actually removing stock from an area. Considering the two surfaces tangent at the edges, the amount of stock removed in a 6-inch f/8 varies from 12 millionths at the center to zero at the edges. What,

Aperture (inches)	f/4	f/5	f/6	f/7	f/8	f/10	f/12	f/15
				TABLE I: SPHERE				
6	0.093842	0.075047	0.062529	0.053589	0.046887	0.037506	0.031251	0.025000
8	0.125122	0.100069	0.083370	0.071452	0.062515	0.050008	0.041671	0.033336
10	0.156403	0.125078	0.104212	0.089314	0.078144	0.062510	0.052089	0.041670
12	0.187689	0.150094	0.125054	0.107177	0.093773	0.075012	0.062507	0.050004
16	0.250254	0.200125	0.166739	0.142903	0.125031	0.100016	0.083342	0.066671
				TABLE II: PARABOLOID				
6	0.093750	0.075000	0.062500	0.053571	0.046875	0.037500	0.031250	0.025000
8	0.125000	0.100000	0.083333	0.071429	0.062500	0.050000	0.041667	0.033333
10	0.156250	0.125000	0.104167	0.089286	0.078125	0.062500	0.052083	0.041667
12	0.187500	0.150000	0.125000	0.107143	0.093750	0.075000	0.062500	0.050000
16	0.250000	0.200000	0.166667	0.142859	0.125000	0.100000	0.083333	0.066667
				TABLE III: DIFFERENCE BETWEEN TABLES I AND II				
6	0.000092	0.000047	0.000029	0.000018	0.000012	0.000006	0.000001	0.000000
8	0.000122	0.000069	0.000037	0.000023	0.000015	0.000008	0.000004	0.000003
10	0.000153	0.000078	0.000045	0.000028	0.000019	0.000010	0.000006	0.000003
12	0.000189	0.000094	0.000054	0.000034	0.000023	0.000012	0.000007	0.000004
16	0.000245	0.000125	0.000072	0.000044	0.000031	0.000016	0.000009	0.000004
				TABLE IV: TOTAL STOCK REMOVAL IN CUBIC INCHES				
6	0.000433	0.000221	0.000128	0.000081	0.000054	0.000028	0.000016	0.000008
8	0.001026	0.000525	0.000303	0.000191	0.000128	0.000065	0.000037	0.000019
10	0.002003	0.001025	0.000593	0.000373	0.000250	0.000129	0.000074	0.000038
12	0.003462	0.001735	0.001024	0.000645	0.000432	0.000221	0.000128	0.000065
16	0.008206	0.004197	0.002427	0.001528	0.001023	0.000524	0.000303	0.000155

then, is the total amount of material removed from a mirror in parabolizing?

To find this, we need the equations for the volumes of a spherical and a paraboloidal segment. The following formulas can be used:

Volume of a spherical segment = $\pi S(r^2/2 + S^2/6)$

Volume of a paraboloidal segment = $\pi r^2 S/2$.

The difference between them gives $\pi S^3/6$, or $0.5236S^3$ for the volume of stock removed, and Table IV contains the values for the same mirrors as are listed in the other tables.

Thus, for the 6-inch f/8, 54 millionths of a cubic inch of glass (0.000054) must be removed. But for the same sized mirror at f/4, the total is 433. It is this extra stock (eight times as much) that makes it take so long to parabolize short-focus reflectors. Comparing the 6-inch f/8 with the 12-inch f/5 gives a good idea of the work needed to produce such a large surface (the 1,735 millionths of a cubic inch for the larger mirror is 32 times that for the smaller).

It is now clear why big instruments take so much longer to figure, and why it is necessary to increase polishing action by using subdiameter laps or special techniques. Professional opticians often begin parabolizing in the final stages of fine grinding, but this requires extremely good judgment of when to stop. Otherwise, the result will be a hyperboloid, which is even more difficult to correct than a sphere.

A good solution was proposed by E. L. Mason in Maksutov Club *Circular* 9: Semipolish the mirror on a hard lap, using very fine abrasives instead of rouge or Barnesite. A large part of the figuring can be achieved in this way, the polish obtained allowing Foucault testing. The final polishing and parabolizing are done with a regular or subdiameter lap and polishing compound.

This method is actually an old one, dating back to the 1930's, when kits did not contain the fine abrasives of today, but included as the finishing material either No. 400 or 600 grit having a micron size of 22 or 16. Modern finishing powders are a third to a quarter this size.

ALLAN MACKINTOSH
97 McLoughlin St.
Glen Cove, N. Y.

EDITOR'S NOTE: This article has been adapted in part from Maksutov Club *Circular* 62.

CORRECTION

The photograph of the Double Cluster in Perseus, page 332 of the April issue, is incorrectly described there. North is up, not south; the cluster to the left is Chi Persei, with h Persei to the right. This was pointed out by W. H. Sell, Platte City, Missouri.

"GLEANINGS" INDEX

A subject index to articles of lasting interest that have been published in this department during the past 18 years has been compiled by Allan Mackintosh and published as Maksutov Club *Circular* 64. The index covers Vols. I through XVIII of SKY AND TELESCOPE, but the names of authors are not listed. Also omitted are pure descriptions of observatories and of telescopes unless over 16 inches in aperture, but many subject references include smaller instruments.

Nonmembers of the Maksutov Club may secure a copy of the nine-page index by sending 25 cents to Mr. Mackintosh at 97 McLoughlin St., Glen Cove, N. Y.

ALUMINIZING
ALUMINUM OVERCOATED
CHROMIUM ALLOY

★ ★ BERAL COATINGS ★ ★

The ideal coating for front surface precision mirrors for these reasons:

1. Beral has HIGH reflectivity.
2. Beral is HARD; does not sleek easily.
3. Beral can be cleaned easily — no porous OVERCOATING of quartz.
4. Beral is NOT a Chromium alloy, so can be removed easily.

Prices for Beral coating telescope mirrors: 4", $3.50; 6", $5.00; 8", $6.50; 10", $8.50; 12½", $12.50. Prices for sizes up to 37" diameter on request. Add Postage — Insurance for return mail.

LEROY M. E. CLAUSING
8038 MONTICELLO AVE. SKOKIE, ILL.

GARTH ACCESSORIES

TRIGARTH TURRET — Holds three standard 1¼" O.D. eyepieces. $15.95 ppd.

RACK AND PINION — Machined from solid aluminum castings. Main tube, 1¾" long; sliding tube, 2"; total movement, 3¾". Takes standard 1¼" eyepieces. Gray or black crackle finish. $15.95 ppd. (Both Turret and Rack and Pinion as illustrated at left, $31.90 ppd.)

WIDE-ANGLE RAMSDEN EYEPIECES — Precision made, standard 1¼" O.D. Three sizes: ¼", ½", and 1" E.F.L. $7.00 each, ppd.

MIRROR CELLS — Light sturdy aluminum. Spring-adjusted to absorb shocks. Cut away for ventilation. 6", $7.00; 8", $11.50; 10", $35.00; ppd.

ELLIPTICAL DIAGONAL HOLDER — Accurately machined from solid brass to fit 1¼" minor-axis elliptical diagonal. Fully adjustable for rotational and longitudinal movement. $10.00 ppd.

Satisfaction guaranteed. Write for free catalog.

GARTH OPTICAL CO. P. O. Box 991 Springfield 1, Mass.

1/20-WAVE PARABOLOIDAL TELESCOPE MIRRORS

Who should buy for his telescope the finest optics now available?

* The astronomer (amateur or professional) who requires for his work or enjoyment the finest lunar and planetary detail.

* The astronomer who takes a measure of pride in employing the finest tools for his hobby or profession.

* The astronomer who is mature enough to sense that cheap prices match the goods offered, claims notwithstanding.

* The astronomer who has had some experience in optics and hence knows the care that goes into the making of near-perfect optical surfaces.

I am prepared to justify the *need* for 1/20-wave accuracy in the primary mirror of the telescope, with sound theoretical data showing why, for best planetary and lunar definition, it is not enough merely to confine the light rays to the theoretical diffraction pattern of a star (in effect, simply to define to Dawes' limit).

Please write for a copy of *The Reflecting Telescope* at no charge. It contains information that you will find valuable in considering a telescope for your own use.

NEW 1/20-WAVE PYREX MIRRORS, with 1/10-wave diagonal: 6-inch f/9, $95.00; 8-inch f/8, $155.00; 10-inch f/8 or f/7, $255.00; 12½-inch f/8 or f/7, $395.00.

RETOUCHING DEFECTIVE MIRRORS: 60% of new mirror price above.

Terms: ¼ with order, ¼ when ready to ship, remainder on arrangement to 6 months, or 2% discount if paid within 10 days. If full payment is enclosed with order, 2% may be taken on the full amount.

frank vaughn Optics 1806 South Park St., Box 2053 Madison 5, Wisconsin

3-inch Astronomical Reflector

60 to 180 Power

An Unusual Buy!

Assembled — ready to use! See Saturn's rings, the planet Mars, huge craters on the moon, star clusters, moons of Jupiter, double stars, nebulae, and galaxies! Equatorial-type mounting with locks on both axes. Aluminized and over-coated 3"-diameter f/10 primary mirror, ventilated cell. Telescope comes equipped with a 60x eyepiece and a mounted Barlow lens, giving you 60 to 180 power. A finder telescope, always so essential, included. Sturdy, hardwood, portable tripod.

FREE with Scope: Valuable **STAR CHART** plus 272-page **"HANDBOOK OF THE HEAVENS"** plus the book **"HOW TO USE YOUR TELESCOPE."**

Stock #85,050-Y.....$29.95 ppd.

OFFSPRING OF SCIENCE . . . REALLY BEAUTIFUL!

CIRCULAR DIFFRACTION-GRATING JEWELRY

A Dazzling Rainbow of Color!

Shimmering rainbows of gemlike color in jewelry of exquisite beauty — made with CIRCULAR DIFFRACTION-GRATING REPLICA. Just as a prism breaks up light into its full range of individual colors, so does the diffraction grating. Promises to become a rage in current fashion.

Stock #30,349-Y..Earrings (clip style).....**$2.75 ppd.**
Stock #30,350-Y..Cuff Links.....**$2.75 ppd.**
Stock #30,372-Y..Pendant.....**$2.75 ppd.**
Stock #30,373-Y..2 pins.....**$2.75 ppd.**
Stock #30,390-Y..Tie Clasp.....**$2.75 ppd.**
(All prices include tax.)

STANDARD 4-mm. ORTHOSCOPIC EYEPIECE

These are best for extremely high magnification (300 power with a 48"-f.l. objective). You get a wide, flat field — almost 3 times as much field as a Ramsden of the same power — excellent color correction and definition. Precision made of brass, chrome plated and black enameled. Inside is dead-black anodized with anti-glare shield.

Stock #30,364-Y.....Only **$14.50 ppd.**

WAR-SURPLUS TELESCOPE EYEPIECE



Mounted Kellner eyepiece, type 3. Two achromats, focal length 28 mm., eye relief 22 mm. An extension added, O.D. 1¼", standard for most types of telescopes. Gov't. cost $26.50.

Stock #5223-Y.....**$7.95 ppd.**

Rack & Pinion Eyepiece Mounts

Real rack-and-pinion focusing with variable tension adjustment; tube accommodates standard 1¼" eyepieces and accessory equipment; lightweight aluminum body casting (not cast iron); focusing tube and rack of chrome-plated brass; body finished in black wrinkle paint. No. 50,077-Y is for reflecting telescopes, has focus travel of over 2", and is made to fit any diameter or type tubing by attaching through small holes in the base. Nos. 50,103-Y and 50,108-Y are for refractors and have focus travel of over 4". Will fit our 2⅜" I.D. and our 3⅜" I.D. aluminum tubes, respectively.

For Reflectors

Stock #50,077-Y..(less diagonal holder)....**$8.50 ppd.**
Stock #60,049-Y..(diagonal holder only)....**1.00 ppd.**

For Refractors

Stock #50,103-Y..(for 2⅜" I.D. tubing)....**12.95 ppd.**
Stock #50,108-Y..(for 3⅜" I.D. tubing)....**13.95 ppd.**

NEW BINOCULAR-TO-CAMERA HOLDER

For Exciting Telephoto Shots
Will fit any camera.

Bring distant objects 7 times nearer with a 35-mm. camera, 7 x 50 binocular, and our NEW BINOCULAR-TO-CAMERA HOLDER. Ideal for photographing the constellations, star clusters, the moon, as well as cloud formations, wildlife, vistas. Camera and binocular attach easily. Use any binocular or monocular — any camera, still or movie. Take color or black-and-white. Attractive gray crinkle and bright chrome finish, 10" long. Full directions for making telephotos included.

Stock #70,223-Y.....**$11.50 ppd.**

Take Pictures Through Your Telescope with the EDMUND CAMERA HOLDER for TELESCOPES

Bracket attaches permanently to your reflecting or refracting telescope. Removable rod with adjustable bracket holds your camera over scope's eyepiece and you're ready to take exciting pictures of the moon. You can also take terrestrial telephoto shots of distant objects. Opens up new fields of picture taking!

SUN PROJECTION SCREEN INCLUDED

White metal screen is easily attached to holder and placed behind eyepiece. Point scope at sun, move screen to focus . . . and you can see sunspots!

All for the low, low price of $9.95

Includes brackets, 28¾" rod, projection screen, screws, and directions. Aluminum . . . brackets black crinkle painted.

Stock #70,162-Y.....**$9.95 ppd.**

PRISM STAR DIAGONAL

For comfortable viewing of the stars near the zenith or high overhead with refracting telescopes using standard size (1¼" O.D.) eyepieces, or you can make an adapter for substandard refractors. Contains an excellent high-quality aluminized right-angle prism. The tubes are satin chrome-plated brass. Body is black wrinkle cast aluminum. Optical path of the system is about 5½".

Stock #70,077-Y.....**$12.00 ppd.**

AMICI-PRISM STAR DIAGONAL

Same as above except contains Amici roof prism instead of usual right-angle prism. Thus your image is correct as to right and left, making it excellent for terrestrial viewing.

Stock #50,247-Y.....**$12.00 ppd.**

ASTRO COMPASS and STAR FINDER

Gov't. Cost $75 — Price $14.95 ppd.

Determines positions of stars quickly. Shows various celestial co-ordinates. An extremely useful star finder which can be rotated through 60° angles along calibrated degree scales. Has single eye lens with viewing stop, two spirit levels for aligning, tangent screw with scale for fine precision readings, azimuth scale graduated in two-degree intervals, adjustable tilting azimuth scale for angle reference of stars on distant objects. War surplus. Gov't. cost $75.00. Instructions, carrying case included.

Stock #70,200-Y.....**Only $14.95 ppd.**

NOW! LENS ERECTOR FOR TERRESTRIAL VIEWING WITH YOUR REFLECTOR

This new Edmund development adds real convenience to viewing objects on the earth. Just put the lens erector in your eyepiece holder, insert eyepiece, and focus normally. You see everything right side up and correct as to left and right. Made of polished chrome-finish brass telescoping tubing that will fit any standard 1¼" eyepiece holder. Tubing is 9½" long and slides 3" into eyepiece holder. Erecting system consists of two coated achromats.

Stock #50,276-Y.....**$9.95 ppd.**

TELESCOPE ROLL-FILM CAMERA

This model uses rolls of #127 film. Picture area will be a circle 1-9/16" in diameter.

The advantage of this model is the ease of using roll film. With each camera you get a piece of ground glass. Before loading film in the camera, you focus the telescope. Then lock it in this position. For positions other than infinity, you can scribe a mark on your tube.

Stock #70,182-Y.....**$29.50 ppd.**

SHEET-FILM CAMERA

Uses sheet film 2¼" x 3¼" size. Camera box size is 3" x 4" x 3".

Stock #70,166-Y.....**$39.50 ppd.**

Ideal for Beginners . . .

STARMASTER ASTRONOMY SET!

Bring the thrills and wonders of outer space right into your home with this fascinating, educational Astronomy Set. De Luxe, 37-piece Set includes separate film projector and action pictures of a trip to the moon, from blast-off to return. Exciting views of the moon, planets, comets, distant galaxies, sun explosions, star clusters, other space wonders.

Also star projector and constellation projector (each approx. 4½" high). Projectors show many great constellations and stars, outline forms of Big Bear, Sagittarius, Southern Cross and others, for easy identification.

Also includes 10x telescope (single-element lens, meniscus, nonachromatic) with 1" aperture, suitable for viewing the moon.

Power source, flashlight pointer, and instructions included. Lower-priced Junior Set with single projector also available, but without telescope.

Stock #70,234-Y....De Luxe.....**$10.00 ppd.**
Stock #70,233-Y....Junior.....**$ 5.00 ppd.**

6X FINDER TELESCOPE

Has crosshairs for exact locating. You focus by sliding objective mount in and out. Base fits any diameter tube — an important advantage. Has 3 centering screws for aligning with main telescope. 20-mm.-diameter objective. Weighs less than ½ pound.

Stock #50,121-Y.....**$8.00 ppd.**

STANDARD 1¼" EYEPIECE HOLDER



Here is an economical plastic slide-focus eyepiece holder for 1¼" O.D. eyepieces. Unit includes 3"-long chrome-plated tube into which your eyepiece fits for focusing. Diagonal holder in illustration is extra and is not included.

Stock #60,067-Y.....**$2.50 ppd.**

EDMUND SCIENTIFIC CO.

DOUBLE AND TRIPLE YOUR TELESCOPE'S POWER WITH A BARLOW LENS



WHAT IS A BARLOW? A Barlow lens is a negative lens used to increase the power of a telescope without resorting to short focal length eyepieces, and without the need for long, cumbersome telescope tubes. Referring to the diagram above, a Barlow is placed the distance P inside the primary focus of the mirror or objective. The Barlow diverges the beam to a distance Q. This focus is observed with the eyepiece in the usual manner. Thus, a Barlow may be mounted in the same tube that holds the eyepiece, making it very easy to achieve the extra power. The new power of the telescope is not, as you might suppose, due to the extra focal length given the objective by the difference between P and Q. It is defined as the original power of the telescope times the quotient of P divided into Q.

Beautiful chrome mount. We now have our Barlow lens mounted in chrome-plated brass tubing, with special spacer rings that enable you easily to vary the power by sliding split rings out one end and placing them in other end. Comes to you ready to use. Just slide our mounted lens into your 1¼" I.D. tubing, then slide your 1¼" O.D. eyepieces into our chrome-plated tubing. Barlow lens is nonachromatic.

Stock #30,200-Y...Mounted Barlow lens....**$8.00 ppd.**

UNMOUNTED 3X BARLOW LENS

These lenses are made for telescopes that have smaller diameter eyepieces than the standard 1¼" size. Mount one between the eyepiece and objective, and triple your power. Instructions included. Single-element lens, focal length −1-5/16", unmounted.

Stock #30,185-Y....0.932" diam.....**$3.50 ppd.**
Stock #30,328-Y....0.912" diam.....**$2.50 ppd.**

3X ADJUSTABLE-DIAMETER BARLOW LENS

For telescopes with eyepieces smaller than the standard 1¼" outer-diameter size. Prongs on mount can be opened or closed to fit tubes from 15/16" to 1" outer diameter. Directions for using included.

Stock #30,339-Y.....**$5.00 ppd.**

MORE POWER FROM YOUR JAPANESE TELESCOPES

Mounted Barlow for Japanese Telescopes

By inserting this single-element lens in the eyepiece end of your Japanese telescope, and putting your regular eyepiece in the end of the Barlow tube, you can increase your telescope's power up to three times. Thus, instead of 60x, you will get 120x or 180x. Barlow is mounted in two pieces of telescoping brass tubing each 4" long, satin chrome plated on the outside. Inner diameter of large tube and outer diameter of small tube are 0.965", the standard size for most Japanese telescopes. Measure yours before ordering. 0.965" is approximately 31/32" or 24.5 mm.

Stock #30,370-Y.....**$6.00 ppd.**

BARGAIN! MOUNTED ACHROMATIC BARLOW LENS

2-element, low-reflection-coated, negative achromat which will increase the power of your telescope over 3 times. The short focal length (−1.74") allows the lens to be used close to the primary focus, eliminating the need for long cumbersome tubes as in most long-focus Barlow systems. Outside diameter of tube, 1¼" (standard eyepiece size). Your standard eyepieces will fit in the other end. Spacers are included to vary the power. Complete directions.

Stock #30,374-Y.....**$15.00 ppd.**

SPACE RINGS THE FLOATING MOBILE

New Space Rings kit creates beautiful floating mobiles in endless variety — graphically demonstrates engineering concepts, math equations utilizing rectangular and polar co-ordinates. Kit consists of 4 perforated aluminum rings from 4" to 8" diameter, metallic elastic yarn in 7 shimmering colors, 1 large bronze-wire hoop, special ceiling hanger, and complete directions. Ideal creative hobby for older child or adult. Excellent teaching aid.

Stock #70,285-Y.....**$4.95 ppd.**

EQUATORIAL MOUNT and TRIPOD with CLOCK DRIVE

Heavy-duty mount. Drive operates on 110-volt, 60-cycle, a.c. house current. Follows motion of stars smoothly. 32" tripod legs included.

Stock #85,081-Y....**$76.50** f.o.b. Barrington, N. J.

Same mount as above, without clock drive, for 8" or smaller reflectors and for 4" or smaller refractors.

Stock #85,023-Y.....New Low Price.....**$39.50** f.o.b. Barrington, N. J.

WAR-SURPLUS! AMERICAN-MADE!

7 x 50 BINOCULARS

Big savings! Brand new! Crystal-clear viewing — 7 power. Every optical element is coated. An excellent night glass — the size recommended for satellite viewing. Individual eye focus. Exit pupil 7 mm. Approx. field at 1,000 yds. is 376 ft. Carrying case included. American 7 x 50's normally cost $195. Our war-surplus price saves you real money.

Stock #1533-Y.....Only **$55.00 ppd.** (Tax included)

THE STARFINDER 12" CELESTIAL GLOBE

This beautiful new celestial globe brings the heavens before your eyes! The satellite-type mounting provides new ease in adjustment to place the stars on the globe in positions relating to the heavens at any given place and time.

Stock #70,279-Y..**$19.95 ppd.**

Mounted Ramsden Eyepieces

Standard 1¼" Diameter

Our economy model, standard-size (1¼" O.D.) eyepiece. We mounted two excellent quality plano-convex lenses in black anodized aluminum barrels instead of chrome-plated brass to save you money. The clear image you get with these will surprise you. Directions for using short focal length eyepieces are included with both the ¼" and ½" models.

Stock #30,204-Y.....¼" focal length.....**$4.75 ppd.**
Stock #30,203-Y.....½" focal length.....**$4.50 ppd.**

"MAKE-YOUR-OWN" 4¼" MIRROR KIT

The same fine mirror as used in our telescopes, polished and aluminized, lenses for eyepieces, and diagonal. No metal parts.

Stock #50,074-Y.....**$16.25 ppd.**

STAR AND SPACE MAPS

Three giant maps: 1. THE SOLAR SYSTEM, 50" x 38", showing solar statistics; detailed moon map; 12 telephoto pictures of moon, sun, planets. 2. WORLD STAR CHART, 50" x 38"; locates stars for any time of year, any position on earth. 3. MAP OF THE SOLAR SYSTEM, 35" x 48"; shows planets, zodiac, and so on.

Stock #9245-Y....Set of 3 maps.....**$1.00 ppd.**

8" SETTING-CIRCLE SET

Stock #50,133-Y..Complete set ..... **$3.00 ppd.**
Stock #60,078-Y..360° declination circle only **$1.60 ppd.**
Stock #60,079-Y..24-hour right-ascension circle only **$1.60 ppd.**

5¾" SETTING-CIRCLE SET

Stock #50,190-Y..Complete set..... **$2.50 ppd.**
Stock #60,080-Y..360° declination circle only **$1.35 ppd.**
Stock #60,081-Y..24-hour right-ascension circle only **$1.35 ppd.**

LARGE ERFLE EYEPIECE 1½" F.L.

War-Surplus Bargain — Gov't. Cost Approx. $100

Large telescopes should have one of these for low-power viewing. Apparent field of view 65°. Also use with the 24"-focal-length Aerial Camera lens to make a 16-power wide-field telescope or a 27-power scope with one of the 40"-focal-length Aerial Camera lenses. Low-reflection-coated, 5-element lens system. Field lens of Eastman Kodak's rare-earth glass for better aberration correction. Has diopter scale. Smooth focusing ⅝" movement. Outside diameter of attaching threads, 3" — 32 threads per inch. Clear aperture of eye lens 2", field lens 1-25/32". Weight 3½ lbs.

Stock #50,091-Y.....**$9.95 ppd.**

Attention! For Beginners, Junior Astronomy Clubs, Boy and Girl Scouts, Camp Groups, School Science Clubs

MAKE 8-POWER ASTRONOMICAL TELESCOPE with Low-Cost Beginner's Kit!

Every boy and girl of today dreams of being a part of the exploration of outer space. That desire makes building his own telescope a real thrill. Now anyone of Cub Scout or Brownie age on up can make his own astronomical 8-power telescope in one evening, without tools or machinery. Here is an ideal, attractive group project for scouts, junior astronomy clubs, or similar groups. (See special quantity prices.) Scope is powerful enough to show craters of the moon, Jupiter's satellites, and many stars not visible to the naked eye. Kit includes objective lens, field lens, eye lens, glare stops, kraftboard tubes, cadmium-plated metal ferrules, and other parts to build an 18"-long, 1¼"-diameter telescope of 8 power.

Stock #70,238-Y.....**$3.00 ppd.**

SPECIAL QUANTITY PRICES

Stock #70,239-Y.... 5 kits.....**$12.50 ppd.**
Stock #70,240-Y....10 kits.....**$22.50 ppd.**

BE SURE TO GET FREE CATALOG "Y"

128 Pages! Over 1000 Bargains!

Fantastic variety — rarely before have so many lenses, prisms, optical instruments, and components been offered from one source. Probably the greatest assembly of bargains in all America. Imported! War Surplus! Hundreds of other hard-to-get optical items. Many science and math learning and teaching aids.
Write for Free Catalog "Y".

EASY PAYMENT PLAN AVAILABLE! DETAILS WITH CATALOG

ORDER BY STOCK NUMBER . . . SEND CHECK OR MONEY ORDER . . . SATISFACTION GUARANTEED!

BARRINGTON • NEW JERSEY

CELESTIAL CALENDAR

Universal time (UT) is used unless otherwise noted.

Mercury in the Evening Sky This Month

GEMINI is the guide constellation to Mercury this June, for the planet will be within its boundaries most of the month. Greatest elongation will take place on June 19th, with the planet 25° east of the sun. At the beginning of the month, Mercury sets 1¼ hours after the sun, in midmonth 1⅝ hours, and at month's end more than one hour.

Familiarity with the stars of Gemini, particularly Castor and Pollux, Gamma (Alhena), Delta, Epsilon, and Mu Geminorum, will help the observer in tracking Mercury through the month. For instance, on the evening of June 4th, it will be about 10° to the right (north) of Alhena, but much brighter than the star, for the planet's magnitude is then −0.3. It is to be very close to Mu, which may, however, be lost in the twilight glare.

By the 8th, Mercury will have moved eastward close to Epsilon Geminorum, the two making an interesting unequal pair in binoculars. At sunset, they are about as high above the horizon as Procyon, the 1st-magnitude star some 25° to the left of them in the sky. Mercury is also about 12° below Castor. The planet will form a long thin triangle with Castor and Pollux on the 12th, then being only about 3° east of Delta.

On the evening nearest elongation, the 18th, the planet will be passing some 5° south of Pollux, these two and Castor making a fine sight in the sky. The visual magnitudes then are Mercury +0.8, Pollux +1.2, and Castor +1.6. A line from Pollux toward Procyon will pass close to Mercury.

During the latter part of the month, the apparent motion of Mercury among the stars will be slower. By the end of June, it is almost in line with the twin stars. Mercury should still be easy to find if one has watched it from night to night, but it will have faded to magnitude +1.4, almost as faint as Castor.

Telescopic observations will show marked changes in Mercury's appearance during June. On the first it is small and gibbous, about 80 per cent of its disk illuminated and only 5".7 in diameter. By the 10th, with the disk somewhat larger, the phase resembles that of the first-quarter moon. At elongation, Mercury will be a broad crescent 8" in diameter, and by month's end the disk will be only 20-per-cent illuminated and 10" across.

JUPITER'S SATELLITES

The curves in the accompanying chart show the positions of Jupiter's four bright moons, as seen in an inverting telescope, with north at the bottom and east at the right. Each horizontal line is for 0^h Universal time on the date specified, and the intersections of the line with the curves indicate the places of the satellites at that time. For other Universal times, interpolate between the 0^h lines. The double vertical lines represent the planet's disk.

The lower section is intended to aid observations of the eclipses of Jupiter's moons; *d* is the point of disappearance of the satellite in Jupiter's shadow, *r* is the point of reappearance. The chart is from *The American Ephemeris and Nautical Almanac;* for further explanation, see page 446 of Sky and Telescope for May, 1960.

Jupiter's Satellites in June



SZ HERCULIS

USERS of 6-inch telescopes or larger can spend an interesting June evening watching the striking brightness changes of SZ Herculis. It is an Algol-type variable with the short period of 19 hours 38 minutes. Normally near magnitude 10.2, it fades to about 11.9 in only 2.2 hours, and regains its former brightness in an equal interval. Thus, the light changes are exceptionally rapid and easy to observe.

The 1950 position of SZ Herculis is 17^h 37^m.8, +32° 58′, roughly midway between Vega and Delta Herculis. Observers who do not use setting circles should first pick up the 6½-magnitude star shown in the Skalnate Pleso atlas at 17^h 37^m.0, +32° 46′; this is the brightest object plotted in the accompanying field chart.

Approximate Universal times, to the nearest 0.1 hour, of the midpoints of eclipses convenient for observation in North America are: June 1, 2^h.6; 5, 4^h.8; 14, 4^h.8; 18, 7^h.0; 19, 2^h.6; 23, 4^h.8; 27, 7^h.0; 28, 2^h.6. Predictions of other minima can be obtained by adding multiples of 19.63 hours to these times.

The period of SZ Herculis is changing; hence new determinations of the times of its minima are highly desirable. Readers with some experience in observing variable stars are invited to co-operate in this. The magnitude of the variable is to be estimated every quarter hour or so, beginning 1½ or two hours before the predicted time of minimum, and continuing that long after it. The time of each estimate should be recorded to the nearest minute.

All relevant details should be given with any such series of observations sent in to Sky and Telescope for analysis. Observers who wish to derive times of minima from their own estimates will find a simple but precise graphical procedure explained in the February, 1957, issue, page 190.



SZ Herculis is indicated by a small circle in this finder chart, which is one degree wide, with south on top. The brightest star is of magnitude 6½. Approximate visual magnitudes of labeled comparison stars are: A, 9.8; B, 10.2; C, 10.4; D, 10.9; E, 11.4; F, 11.9.

MINIMA OF ALGOL

June 2, 18:36; 5, 15:25; 8, 12:14; 11, 9:03; 14, 5:51; 17, 2:40; 19, 23:29; 22, 20:18; 25, 17:06; 28, 13:55.

July 1, 10:44; 4, 7:32; 7, 4:21.

These minima predictions for Algol are based on the formula in the 1953 *International Supplement* of the Krakow Observatory. The times given are geocentric; they can be compared directly with observed times of the star's least brightness.



This light curve of the Algol-type variable SZ Herculis was derived by Miss A. A. Vasilieva from 214 visual estimates with the 6-inch refractor of Stalinabad Observatory. The vertical scale is brightness, expressed in arbitrary steps. Adapted from the Soviet journal, "Variable Stars."



THE SUN, MOON, AND PLANETS THIS MONTH

The sun, on the ecliptic, is shown for the beginning and end of the month. The moon's symbols give its phase roughly, with the date marked alongside. Each planet is located for the middle of the month or for other dates shown. All positions are for 0h Universal time on the respective dates.

Mercury reaches greatest eastern elongation on June 19th, when it will be 25° from the sun, setting about 1¾ hours after it. This is a favorable elongation for Northern Hemisphere observers, and Mercury should be fairly easy to find all month, as explained in the discussion on the facing page. The thin crescent moon will be near Mercury on the evening of June 25th.

Venus comes to superior conjunction on June 22nd, and will be too near the sun all month to be observed.

Earth reaches heliocentric longitude 270° on June 21st, at 9:43 Universal time. This marks the solstice, summer beginning in the Northern Hemisphere, winter in the Southern.

Mars rises about three hours before the sun in midmonth, and is a 1st-magnitude object in Pisces. Telescopically, the planet's disk is slightly gibbous — 89-percent illuminated — and only 5".8 in diameter. Mars is too distant for satisfactory observations of its surface detail. The moon will be near the red planet on the morning of June 18th.

Jupiter reaches opposition to the sun on June 20th, 394 million miles from the earth. It then rises about sunset and is prominent in the southern sky (in Sagittarius) all night. Its magnitude is −2.2, and a telescope will show its oblate disk, 46".5 in equatorial diameter and 43".4 in polar. The moon will be near Jupiter the night of June 9-10, being 5° north of the planet at 7h UT on the 10th. That same night, the giant planet will be located in front of the Trifid nebula, M20.

Saturn is in Sagittarius, being about 20° east of Jupiter on the 15th, and rising then about 1½ hours after sunset. The magnitude of the planet is +0.4. Even a small telescope will show Saturn's rings, 41".2 in extent and having their northern face tipped 24° to our line of sight this month. The planet's polar diameter is 16".4. The moon will pass near Saturn on the night of June 10-11, with conjunction at 10h UT on the 11th, the moon being 4° north.

Uranus is a 6th-magnitude object near the Leo-Cancer boundary in June, as shown in the finder chart on page 191 of the January issue. It may be seen in the western sky during the early evening, setting about three hours after the sun.

Neptune is near the Virgo-Libra border, and may be found with small telescopes and the chart on page 191 of January. This 8th-magnitude object crosses the meridian about an hour after sundown, and is in the southwestern sky later in the evening. The planet's tiny greenish disk is 2".5 in diameter.

W. H. G.

MINOR PLANET PREDICTIONS

Vesta, 4, is of the 6th magnitude this month. The finding chart and extended ephemeris, printed on page 447 last month, can be used for observing it in June.

Pallas, 2, 9.4. June 15, 19:20.0 +21-57; 25, 19:12.7 +22-11. July 5, 19:04.6 +21-57; 15, 18:56.3 +21-15; 25, 18:48.7 +20-07. August 4, 18:42.3 +18-38. Opposition on July 6.

Bamberga, 324, 9.8. June 25, 20:24.4 −31-59. July 5, 20:16.8 −32-08; 15, 20:06.4 −32-06; 25, 19:54.7 −31-47. August 4, 19:43.1 −31-06; 14, 19:33.4 −30-08. Opposition on July 20.

Melpomene, 18, 8.9. June 25, 20:29.1 −7-45. July 5, 20:24.1 −8-16; 15, 20:16.6 −9-12; 25, 20:07.5 −10-30. August 4, 19:58.1 −12-03; 14, 19:49.9 −13-44. Opposition on July 23.

After the asteroid's name are its number and the approximate visual magnitude expected at opposition. At 10-day intervals are given its right ascension and declination (1950.0) for 0h Universal time. In each case the motion of the asteroid is retrograde. Data are supplied by the IAU Minor Planet Center at the University of Cincinnati Observatory.

VARIABLE STAR MAXIMA

June 3, R Virginis, 123307, 6.9; 4, S Herculis, 164715, 7.6; 5, RU Sagittarii, 195142, 7.2; 9, T Centauri, 133633, 5.5; 10, RS Librae, 151822, 7.5; 17, T Aquarii, 204405, 7.7; 18, R Octantis, 055686, 7.9; 29, R Aquilae, 190108, 6.1.

July 2, RR Sagittarii, 194929, 6.8; 9, SS Virginis, 122001, 6.8.

These predictions of variable star maxima are by the AAVSO. Only stars are included brighter than magnitude 8.0 at an average maximum. Some, but not all of them, are nearly as bright as maximum two or three weeks before and after the dates for their maxima. The data given include, in order, the day of the month near which the maximum should occur, the star name, the star designation number, which gives the rough right ascension (first four figures) and declination (bold face if southern), and the predicted visual magnitude.

MOON PHASES AND DISTANCE

First quarter	June	2, 16:02
Full moon	June	9, 13:02
Last quarter	June	16, 4:36
New moon	June	24, 3:27
First quarter	July	2, 3:49

June	Distance	Diameter
Perigee 10, 2h	222,100 mi.	33′ 26″
Apogee 24, 10h	252,700 mi.	29′ 23″
July		
Perigee 8, 11h	221,900 mi.	33′ 27″

UNIVERSAL TIME (UT)

TIMES used in Celestial Calendar are Greenwich civil or Universal time, unless otherwise noted. This is 24-hour time, from midnight to midnight; times greater than 12:00 are p.m. Subtract the following hours to convert to standard times in the United States: EST, 5; CST, 6; MST, 7; PST, 8. To obtain daylight saving time subtract 4, 5, 6, or 7 hours, respectively. If necessary, add 24 hours to the UT before subtracting, in which case the result is your standard time on the day preceding the Greenwich date shown. For example, 6:15 UT on the 15th of the month corresponds to 1:15 a.m. EST on the 15th, and to 10:15 p.m. PST on the 14th.

Sky and Telescope Binders

A dark blue fabrikoid binder priced at $3.50 each, postpaid in the United States; $4.00 in Canada. Two sizes: Binder C is for volumes up to XVIII; Binder D is for volume XIX and after. When ordering, please specify the volume number for which the binder is to be used.

Your name can be gold-stamped for 75¢ extra, the volume number for 50¢, both for $1.20; print desired lettering clearly. Payment must accompany order. (Sorry, but no foreign orders accepted.)

Sky Publishing Corporation

Harvard Observatory, Cambridge 38, Mass.

Equatorial mounting of the 4" UNITRON refractor, Model 152.

Step up, friend. Sit yourself down at the controls of a UNITRON. Feel the sure response of the slow-motion controls. Note the extra-smooth handling ease. Observe the oversize components, which give UNITRON mountings strength to spare.

If it's an altazimuth model, you have micrometric adjustments for both altitude and azimuth. In the equatorial models, you'll find the mechanism more sophisticated — but the operation is even easier. Here, once you've pinpointed your target, only the single right-ascension control is needed to keep the object centered in the field of view. You'll welcome the added convenience of the new flexible cable extension which brings the right-ascension control within easy reach — a new feature included with all UNITRON equatorials as standard equipment.

Note, too, the precise slow-motion adjustment for declination. Scrutinize the precision gears designed to deliver generations of velvet-smooth performance. Examine the large easy-reading setting circles and verniers provided on the 3" and larger models.

(What you won't see is the instrument's complex of inner workings — a blend of the arts of the artillery engineer and the Swiss watchmaker that gives you an instrument whose response will be obedient to the slightest touch of your fingers.)

And — while you're at it — don't forget to look through the refractor. UNITRON's optical excellence is the other big reason UNITRON sales are mounting.

Sturdy altazimuth mounting with slow-motion controls as well as rapid motions for altitude and azimuth.

UNITRON INSTRUMENT DIVISION OF UNITED SCIENTIFIC CO. — 204-206 MILK STREET, BOSTON 9, MASS.

SEE THE BACK COVER FOR MORE ABOUT UNITRON.

Be Certain of Optical Excellence – Buy UNITRON

MANY Models To Choose From!

2" SATELLITE ($7.50 Down) 6x, diagonal eyepiece, altazimuth mount with circles, stand — **$75**

1.6" ALTAZIMUTH ($7.50 Down) with eyepieces for 78x, 56x, 39x — **$75**

2.4" ALTAZIMUTH ($12.50 Down) with eyepieces for 100x, 72x, 50x, 35x — **$125**

2.4" EQUATORIAL ($22.50 Down) with eyepieces for 129x, 100x, 72x, 50x, 35x — **$225**

3" ALTAZIMUTH ($26.50 Down) with eyepieces for 171x, 131x, 96x, 67x, 48x — **$265**

3" EQUATORIAL ($43.50 Down) with eyepieces for 200x, 131x, 96x, 67x, 48x — **$435**

3" PHOTO-EQUATORIAL ($55.00 Down) with eyepieces for 200x, 171x, 131x, 96x, 67x, 48x — **$550**

4" ALTAZIMUTH ($46.50 Down) with eyepieces for 250x, 214x, 167x, 120x, 83x, 60x — **$465**

4" EQUATORIAL ($78.50 Down) with eyepieces for 250x, 214x, 167x, 120x, 83x, 60x, 38x — **$785**

4" PHOTO-EQUATORIAL ($89.00 Down) with eyepieces for 250x, 214x, 167x, 120x, 83x, 60x, 38x — **$890**

4" EQUATORIAL with clock drive **($98.50 Down)**, Model 160V, eyepieces as above — **$985**

4" EQUATORIAL with clock drive and metal pier **($107.50 Down)**, Model 166V, eyepieces as above — **$1075**

4" PHOTO-EQUATORIAL with clock drive and Astro-camera **($117.50 Down)**, with eyepieces for 250x, 214x, 167x, 120x, 83x, 60x, 38x, 25x — **$1175**

4" PHOTO-EQUATORIAL with clock drive, pier, Astro-camera **($128.00 Down)**, eyepieces for 375x, 300x, 250x, 214x, 167x, 120x, 83x, 60x, 38x, 25x — **$1280**

6" EQUATORIAL with clock drive, pier, 2.4" view finder, with eyepieces for 625x, 500x, 416x, 357x, 277x, 200x, 138x, 100x, 62x, 42x — **$5125**

6" PHOTO-EQUATORIAL as above but with 4" guide telescope, illuminated diagonal, UNIBALANCE, Astro-camera Model 330 — **$5660**

6" PHOTO-EQUATORIAL as above with addition of 3" Astrographic Camera Model 80 — **$6075**

HAS IT OCCURRED TO YOU?

There is much to recommend a UNITRON Refractor as the logical choice for the amateur astronomer. A UNITRON, optically speaking, duplicates the performance of larger telescopes of other types. With its long focal length, higher magnifications of planetary and lunar images are obtained with low-power eyepieces. Moreover, there are no mirrored surfaces to become oxidized, no components which require periodic alignment, no secondary optics to cause diffraction patterns, and no folding of the light back on itself through turbulent air with consequent loss of definition. No wonder that you see more and see better with a UNITRON — the telescope that has withstood the test of time.

HOW TO ORDER

Send check or money order in full or use our Easy Payment Plan, as described below. Shipments made express collect. Send 20% deposit for C.O.D. shipment. UNITRON instruments are fully guaranteed for quality, workmanship, and performance, and must meet with your approval or your money back.

Use Our EASY PAYMENT PLAN

UNITRON's popular Easy Payment Plan is a convenient and economical way to buy your UNITRON Refractor when you do not want to disturb your savings or when you haven't the total cost of the telescope immediately available. The down payment required is 10%. The balance due is payable over a 12-month period, and there is a 6% carrying charge on the unpaid balance. Your first payment is not due until 30 days after you receive the instrument, and if you should want to pay the entire balance due at that time, the carrying charge is canceled. (6" models available on special plan.)

There is no "red tape" when you order — you merely fill in the UNITRON Easy Payment Order Form, return it together with the required down payment, and the model of your choice is shipped to you at once.

Do not hesitate to use this plan merely because you have never before purchased anything on time payments. The procedure is practically painless and is an ideal means of enjoying the use of your UNITRON while paying for it.

PORTABILITY PLUS

UNITRON 2.4" Altazimuth

Here is the telescope that has long been America's most popular low-priced refractor.

The UNITRON 2.4" Altazimuth is a favorite not only with the beginning amateur, but is chosen by many owners of larger instruments as a second telescope because of its light weight and extreme portability. A newly designed suitcase-type cabinet is now being included to house the complete telescope with tripod and mounting, thus permitting even more convenient transport than ever.

The UNITRON 2.4" Altazimuth Refractor is priced at only $125 complete with tripod, sturdy mounting with micrometric slow-motion controls, four eyepieces, choice of UNIHEX Rotary Eyepiece Selector or star diagonal and erecting prism system, cabinet, and other accessories. Using our Easy Payment Plan, a mere 10% down payment of only $12.50 brings this UNITRON to you.

Get UNITRON's FREE Observer's Guide and Catalog on ASTRONOMICAL TELESCOPES

This valuable 38-page book is yours for the asking!

With artificial satellites already launched and space travel almost a reality, astronomy has become today's fastest growing hobby. Exploring the skies with a telescope is a relaxing diversion for father and son alike. UNITRON's handbook contains full-page illustrated articles on astronomy, observing, telescopes and accessories. It is of interest to both beginners and advanced amateurs.

Contents include—

- Observing the sun, moon, planets and wonders of the sky
- Constellation map
- Hints for observers
- Glossary of telescope terms
- How to choose a telescope
- Amateur clubs and research programs

UNITRON

INSTRUMENT DIVISION of UNITED SCIENTIFIC CO.
204-206 MILK STREET • BOSTON 9, MASS.

Please rush to me, free of charge, UNITRON's new Observer's Guide and Telescope Catalog 20-C.

Name _____

Street _____

City _____ State _____

New UNITRON View Finders

UNITRON's popular view finders with newly designed optics and mechanical features are better than ever. From left to right: 23.5 mm., 30 mm., 42 mm.

1. VIEW FINDER (Used on UNITRON 2.4" Equatorials): 23.5-mm. (.93") achromatic objective, 6x eyepiece with crosshairs. Chromed brass tube. Mounting brackets with centering screws. **Only $8.50 postpaid**

2. VIEW FINDER (As used on UNITRON 3" Refractors): 30-mm. (1.2") coated achromatic objective and 8x eyepiece with crosshairs. Other details as in View Finder 3. **Only $10.75 postpaid**

3. VIEW FINDER (As used on UNITRON 4" Refractors): 42-mm. (1.6") coated achromatic air-spaced objective. 10x eyepiece with crosshairs. Duralumin tube finished in white enamel. Dewcap. Furnished with mounting brackets, centering screws for collimation, and mounting screws. This finder measures approximately 16" overall. It is light in weight, compact and small enough for use as a hand telescope furnishing spectacular wide-field views of the sky. **Only $18.00 postpaid**

UNITRON INSTRUMENT DIVISION OF UNITED SCIENTIFIC COMPANY
204-206 MILK STREET • BOSTON 9, MASSACHUSETTS

South
40° HORIZON
30° HORIZON
20° HORIZON
North
East
West
ECLIPTIC
EQUATOR
MERIDIAN
GALACTIC EQUATOR
SOUTH CELESTIAL POLE
FALSE CROSS
SOUTHERN CROSS
COAL SACK
LARGE MAGELLANIC CLOUD
SMALL MAGELLANIC CLOUD
GREAT SQUARE
NORTHERN CROSS
KEYSTONE
WATER JAR
CIRCLET
SOUTHERN TRIANGLE
SOUTHERN FISH
SOUTHERN CROWN
SOUTHERN GATE
Canopus
Rigil Kentaurus
Hadar
Achernar
Fomalhaut
Altair
Deneb
Vega
Sadr
Etamin
Alderamin
Markab
Schedar
Algenib
Alpheratz
Mirach
Almach
Diphda
Menkar
Menkent
Alphard
Regulus
Denebola
Algieba
Rasalgethi
Rasalhague
Kornephoros
Unukalhai
Antares
Shaula
Rasalgeuthi
Kaus Australis
Nunki
Ascella
Kaus Media
Kaus Borealis
Albireo
Rastaban
Eltanin
Nodus II
Nodus I
Ras Alhague
Sabik
Yed Prior
Yed Posterior
Cebalrai
Rasalhague
Gienah
Algorab
Minkar
Alkaid
Mizar
Alioth
Megrez
Phecda
Merak
Dubhe
Alula Borealis
Alula Australis
Talitha
Tania Australis
Tania Borealis
Chara
Muphrid
Izar
Seginus
Arcturus
Spica
Zubenelgenubi
Zubeneschamali
Unukalhai
Toliman
Hamal
Sheratan
Mesarthim
Alpha Arietis
Algol
Mirfak
Capella
Menkalinan
Elnath
Rigel
Bellatrix
Betelgeux
Saiph
Alnilam
Alnitak
Mintaka
Meissa
Wezen
Adhara
Sirius
Aludra
Castor
Pollux
Procyon
Alhena
Wasat
Mebsuta
Propus
Tejat
Alhena
Gomeisa
Naos
Suhail
Miaplacidus
Avior
Aspidiske

STARS FOR JUNE

The sky as seen from latitudes 30° to 50° north, at 9 p.m. and 8 p.m., local time, on the 7th and 22nd of June, respectively. For other dates, add or subtract ½ hour per week.

In the east at chart time are the familiar constellations of summer, while those of spring are descending in the west. Bootes the Herdsman is nearly overhead, with Arcturus prominent. Spica is now well placed in the south. Look low in the southeast for the red 1st-magnitude star Antares, in Scorpius.

GOTO
TOKYO

Established in 1926, Japan's oldest and largest firm specializing in astronomical telescopes.

The Goto Planetarium Hall at the 1959 Tokyo International Trade Fair.



Goto's Model M-1 has been acclaimed by many visitors to the Fair, including specialists.

GOTO'S MEDIUM-SIZE PLANETARIUM

Goto Optical Mfg. Co., Japan's foremost maker of astronomical telescopes, now has available its new medium-size planetarium, for delivery and erection anywhere in the world.

FEATURES

1. Projects the entire celestial sphere, and can show the sky above any point in the world. Thus, the starry sky above various points south of the equator, particularly the Antarctic, can be simulated to the very last detail.
2. The annual motions of the moon, sun, and five bright planets are reproduced, including the apparent retrograde movements of the planets.
3. The 25,800-year cycle of precession can be demonstrated, permitting turning the planetarium backward or forward in time.
4. With a record player and tape recorder, music, sound effects, and taped lectures can be given over a loud-speaker system.
5. The console provides for remote control of all planetarium movements and sound effects.
6. Auxiliary projectors are available for reproducing various celestial phenomena, in accordance with the lecture's subject.

Catalogues will be sent upon request.

GOTO OPTICAL MFG. CO.
1-115 Shimmachi, Setagaya-ku, Tokyo, Japan

Cable Address:
GOTOPTIC TOKYO

FOR UNIVERSITIES
JUNIOR COLLEGES
HIGH SCHOOLS

25-FOOT ASTRO-DOME AT UNIVERSITY OF WISCONSIN

Leading universities and astronomical research centers have found that Astro-Domes provide years of continuous and dependable service. Astro-Domes exclusive labyrinth seal shutter and design and its unique dome drive will give you smooth, quiet operation under all weather conditions. Reliable equipment like this is needed by the science educators who are training the future scientists, engineers, and technicians of the space age. Let Astro-Dome supply you with complete information on planning an Astro-Observatory for your institution.

The ALL NEW ASTRO-DOMETTE

Astro-Domettes have been developed for high schools and junior colleges. These units are fabricated on an assembly line basis, resulting in high quality yet modest cost. Because sections are stamped or molded, dome components are uniform and interchangeable. Astro-Domettes are available in sizes of 8, 10 and 12 feet outside diameters. In the space age, progressive schools will want to include this new aid to education in their science department.

ASTRO-DOMETTES are available in pastel colors

ASTRO-DOME
INCORPORATED

Serving the Astro-Sciences

MANUFACTURERS OF ASTRONOMICAL OBSERVATORY DOMES
1801 BROWNLEE AVE. N. E. CANTON 5, OHIO Phone GL. 6-8361

PRINTED BY WELLESLEY PRESS, INC.

It is with no Disrespect toward the mighty Johannes Kepler that we humbly suggest he overlooked Something.

We have no Quarrel with his Three Laws Unraveling the Mysteries of Celestial Motion. But what of Earthly Economics? What profits us to know about the Elliptical Orbits of Planets if we have not the Wherewithal to pursue them with Pleasure? Astronomy is all well and good — but what about Astromoney?

Astromoney is precisely what Kepler Forgot . . . the Fine Art of getting the most Pleasure out of Astronomy for the least Money. Its Laws, like Kepler's, are three in number:

First Law: when you consider Telescopes, consider Value first.

Second Law: when you consider Value, consider UNITRON first.

Third Law: when you consider UNITRON, you have it made.

There may be those who will Doubt. They may say the UNITRON of their Choice, although attractively priced, is too Taxing for their Budget. Torn by the Conflict between Desire and Stern Economic Reality, they may abandon the pursuit of Pleasure altogether.

For such as these, there is a fourth Law of Astromoney:

"If you would enjoy your UNITRON, and Keep the Wolf at bay —
Send just one tenth its Price — and take a Year to pay."

The wisdom contained in the fourth Law is summarized in the adjacent Table. It is as Valuable for the Reader as the Rudolphine Tables were for the contemporaries of Kepler.

Pursuing pleasure in the picture above are a few of the many interesting visitors who participate in the "Star Gazers" meetings offered by the Long Island State Park Commission in association with Abraham and Straus. Mr. Percy Proctor, director, indicates the location of a planet while a youngster views it through a UNITRON 2.4" Altazimuth Refractor.

	Prices	Down Payment	Monthly Payment
1.6" Alt.	$ 75	$ 7.50	$ 5.96
2.4" Alt.	125	12.50	9.93
2.4" Eq.	225	22.50	17.88
3" Alt.	265	26.50	21.05
3" Eq.	435	43.50	34.58
3" Ph. Eq.	550	55.00	43.72
4" Alt.	465	46.50	36.96
4" Eq.	785	78.50	62.40
4" 160	1175	117.50	91.41
4" 166	1280	128.00	101.76

UNITRON INSTRUMENT DIVISION OF UNITED SCIENTIFIC CO. — 204-206 MILK STREET, BOSTON 9, MASS.

SEE PAGES 510 AND 511 FOR MORE ABOUT UNITRON